

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				0021	0021	0021	0021
				90% FEDERAL	90% FEDERAL	100%	90% FEDERAL
				10% STATE ROADWAY	7.5% STATE TRAF. SIGNALS	2.5% CITY SAFETY (EVP)	10% STATE INTERCONNECT
			URBAN				
Δ 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4			
67100100	MOBILIZATION	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2084	2084			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	109	109			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4168	4168			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1877	1877			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	233	233			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2903	2903			
Δ 72000100	SIGN PANEL - TYPE 1	SQ FT	75		75		
Δ 72000200	SIGN PANEL - TYPE 2	SQ FT	63		63		
Δ 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1			
Δ 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	26	26			
Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	473	473			

Δ SPECIALTY ITEM

Rev.

SHT.PLAN	USER NAME * #USER#	DESIGNED - BFH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE * #SCALE#	DRAWN - BFH	REVISED -		UR RTE. 6 (159TH STREET) AND IL RTE. 83 (TORRENCE AVENUE)	351	539N-1	COOK	49	4		
	PLOT DATE * #DATE#	CHECKED - BA	REVISED -		SCALE: N.T.S.	SHEET 2	OF 6 SHEETS	STA.	TO STA.	CONTRACT NO. 60W90		
		DATE - 1/31/14	REVISED -							ILLINOIS FED. AID PROJECT		