

NEW RAMP - PAVING SCHEDULE						
LOCATION	31100100		35501324	40600200	40603570	
	SUBBASE GRANULAR MATERIAL, TY A		HMA BASE COURSE 10.25"	BITUMINOUS MATLS. PRIME COAT	POLY HMA SURF. CSE., MIX "E", N 90	
	TON		SQ. YD.	TON	TON	
I-55 MAINLINE						
NORTHBOUND						
STA 166+35.77	TO	STA 169+05.58	592.2	434.7	0.2	36.5
STA 169+05.58	TO	STA 173+05.55	327.8	799.9	0.3	67.2
SOUTHBOUND						
STA 153+41.80	TO	STA 159+02.86	734.8	966.3	0.4	81.2
STA 159+02.86	TO	STA 169+28.10	1712.5	2278.3	0.9	191.4
TOTAL			3367	4479	2	376

48102100 - AGGREGATE WEDGE SHOULDER, TYPE B					
LOCATION			WIDTH	QUANTITY	
			FOOT	TONS	
I-55 MAINLINE					
NORTHBOUND					
166+35.77	TO	166+94.68	4.0	101	
167+19.24	TO	171+84.58	4.0	795	
172+47.86	TO	173+05.55	4.0	99	
SOUTHBOUND					
153+41.80	TO	166+33.62	4.0	2207	
166+59.71	TO	169+28.10	4.0	367	
TOTAL				3568	

72400320 REMOVE SIGN PANEL - TYPE 2	
LOCATION	AREA
	SQ. FT.
I-55 MAINLINE	
SOUTHBOUND	
STA 174+98	16
TOTAL	16

RUTTING CORRECTION - PAVING SCHEDULE						
LOCATION	44000174	40603240	40603570	40600200	70300100	70301000
	HMA SURFACE REMOVAL - 6.25"	POLY HMA BINDER COURSE, IL 19.0, N90	POLY HMA SURFACE COURSE, MIX 'E', N90	BITUMINOUS MATERIAL, PRIME COAT	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
	SQ. YD.	TON	TON	TON	FOOT	SQ FT
I-55 MAINLINE						
SOUTHBOUND						
STA 165+00 TO STA 207+50	5666.7	1507.3	476.0	4.3	106.0	35.3
TOTAL	5667	1507	476	4.3	106	35

72000200 SIGN PANEL - TYPE 2				
LOCATION		SIGN DESIGNATION (MUTCD)	SIZE	AREA
			IN X IN	SQ. FT.
I-55 MAINLINE				
SOUTHBOUND				
STA 174+98	OUTSIDE	W4-3	48 X 48	16
TOTAL				16

PAVEMENT MARKING SCHEDULE										
LOCATION	COLOR	TYPE	78009005	78009012	X7830072	78003140	78004200	78100100	78300200	78300100
			MODIFIED URETHANE PAVEMENT MARKING LINE - 5"	MODIFIED URETHANE PAVEMENT MARKING LINE - 12"	GROOVING FOR RECESSED PAVEMENT MARKING LINE - 6"	PREFORMED PLASTIC PAVEMENT MARKING TYPE B - INLAID LINE 8"	PREFORMED PLASTIC PAVEMENT MARKING TYPE B - INLAID LETTERS AND SYMBOLS	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	PAVEMENT MARKING REMOVAL
			FOOT	FOOT	FOOT	FOOT	SQ. FT.	EACH	EACH	SQ FT
I-55 MAINLINE										
NORTHBOUND										
STA 166+36 TO STA 173+06	WHITE	SOLID			97					279
STA 166+36 TO STA 171+19	WHITE	DOTTED	97			97				
STA 171+19 TO STA 173+27	WHITE	SOLID				208				
STA 165+36 TO STA 173+06	WHITE	SOLID	770		770					
STA 171+00 TO STA 173+00	WHITE	DOTTED		10						
SOUTHBOUND										
STA 153+42 TO STA 169+28	WHITE	DOTTED	318		318					
STA 153+42 TO STA 169+28	WHITE	SOLID	1586		1586					661
STA 169+28 TO STA 174+09	WHITE	SOLID				481				
STA 159+10	WHITE	SYMBOL					42			
STA 161+60	WHITE	SYMBOL					42			
STA 164+10	WHITE	SYMBOL					42			
STA 166+60	WHITE	SYMBOL					42			
STA 174+09 TO STA 181+25	WHITE	SOLID	716		716					
STA 181+25 TO STA 184+94	WHITE	SOLID				369		9	9	
STA 184+94 TO STA 187+96	WHITE	DOTTED	60		60					
STA 187+96 TO STA 207+50	WHITE	SOLID	1954		1954					
TOTAL			5501	10	5501	1058	168	9	9	940