



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 17, 2025

SUBJECT: FAU 1509 (North Aurora Road)
Section 06-00133-00-BR (Naperville)
DuPage County
Contract No. 61G79
Item 009
April 25, 2025 Letting
Addendum (B)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Plan Sheets 245 & 246**
- 2. Revised page 57 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

STUMP REMOVAL

Description. This work shall consist of the removal and satisfactory disposal of tree stumps. All excess chips and debris from this operation shall be removed and disposed of outside the limits of the contract. This work will be done in accordance with Section 201 of the Standard Specifications for tree removal, except that stumps are to be removed a minimum of six (6) inches below the natural surface of the ground.

Basis of Payment. This work will be measured in place and paid for at the contract unit price per Each for STUMP REMOVAL, which price shall include all labor, material, and equipment required to complete the work as specified herein..

CLEARING AND GRUBBING

Description. This work shall consist of clearing and grubbing within the areas shown on the plans in accordance with Section 201 of the Standard Specifications and the following.

The Contractor is advised that it is the intent of the provision that the areas as specified in the contract plans, be clear of all fences, wall, foundations, buildings, accumulations of rubbish of whatever nature and existing structures, the removal of which is not otherwise provided for in Article 501.07 of the Standard Specifications; all logs, shrubs, bushes, saplings, grass, weeds, other vegetation and stumps of a diameter less than 6in. both prior to start of earthwork, and also at the conclusion of construction activities, such that the property can be site graded, seeded, and present a neat and clean appearance on completion of this project in accordance with applicable portions of Section 201 and the requirements of this Special Provision.

Construction Requirements. The Contractor will be required to remove and dispose of materials outlined herein to the satisfaction and approval of the Engineer.

The removal of these items specified herein does not include the removal of items already measured and paid for individually per the Contract Plan Summary of Quantities and/ or per the Special Provisions.

The Contractor is advised to inspect the various items and quantities of clearing required on the parcels involved prior to bidding. Any items identified, or quantities depicted on the contract plans for removal under CLEARING AND GRUBBING is for Contractor information only. No additional compensation will be allowed for variations in removal items required to complete the CLEARING AND GRUBBING as specified in this Special Provision for the subject parcels.

Unless specifically called out in the plans, existing utilities which are still located in the ground, including (but not limited to) power poles, light poles, utility structures, fire hydrants, water main, and sewers, shall not be included in the removal items for CLEARING AND GRUBBING. The Contractor shall note any such existing utilities which conflict with items to be cleared, and request direction from the Engineer prior to clearing at these locations. Any damage to existing utilities by the Contractor shall be repaired by the Contractor at his own expense to the satisfaction of the Engineer.