CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 100% STATE ROADWAY 0005 RURAL
44200050	WELDED WIRE REINFORCEMENT	SQ YD	915	915
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	118	118
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	762	762
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	137	137
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	12	12
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	16	16
44201299	DOWEL BARS 1 1/2"	EACH	1174	1174
44213200	SAW CUTS	FOOT	4149	4149
67100100	MOBILIZATION	L SUM	1	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
Z0017099	DOWEL BAR ASSEMBLY	EACH	6	6
Z0018911	DRILL AND GROUT #6 TIE BARS	EACH	84	84

1

MODEL: Default
FILE NAME: c:\pw_work\pwidot\woodshankrfd1051908\D366R17.dgn

USER NAME = ronald.woodshank	DESIGNED - RW	REVISED -	
	DRAWN - RW	REVISED -	
	CHECKED - JS	REVISED -	
PLOT DATE = 1/2/2025	DATE - 1/2/2025	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 1 OF 1 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(36)PP	IROQUOIS	9	3

CONTRACT NO. 66R17

ILLINOIS | FED. AID PROJECT

1 REV. 4/10/25 REV. 2/10/25