

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER
2	INDEX OF SHEETS, LIST OF HIGHWAY STANDARDS, GENERAL NOTES, & COMMITMENTS
3	SUMMARY OF QUANTITIES
4 to 5	FAI 57 TYPICAL CROSS-SECTIONS
6 to 7	SCHEDULE OF QUANTITIES
8	PLAN SHEET FAI 57 & FAI 72 INTERCHANGE
9 to 20	DETOUR MAPS

GENERAL NOTES

G.N.-100A
ELECTRONIC FILES AND/OR ELECTRONIC SURVEY INFORMATION INCLUDING CADD
FILES WILL NOT BE AVAILABLE TO THE CONTRACTOR.

HIGHWAY STANDARDS

STANDARD NO.	DESCRIPTION
000001-08	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
442101-09	CLASS B PATCHES
701400-12	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-13	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-09	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS ≥ 45 MPH
701428-01	TRAFFIC CONTROL, SETUP AND REMOVAL, FREEWAY/EXPRESSWAY
701451-05	RAMP CLOSURE FREEWAY/EXPRESSWAY
701901-10	TRAFFIC CONTROL DEVICES

COMMITMENTS

THERE ARE NO COMMITMENTS FOR THIS CONTRACT

MODEL: Index Standards GN Commit Sheet
FILE NAME: c:\pw_workspace\projects\1033076\0570H54-shl-Index_Standards_General Notes_Commitments.dgn

	USER NAME = Tyler.Pierson	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, LIST OF STANDARDS, GENERAL NOTES, & COMMITMENTS	FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			57	(10-33,33)PP	CHAMPAIGN	20	2
		CHECKED -	REVISED -			CONTRACT NO. 70H54				
	PLOT DATE = 1/24/2025	DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
						SCALE:	SHEET 1	OF 1	SHEETS	STA.

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FUNDING BREAKOUT:
CONSTRUCTION TYPE CODE:

FAI (I 57)
INTERSTATE

URBAN
STA. 445+00
STA. 535+00
CHAMPAIGN
100% STATE
0006

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
	44200050	WELDED WIRE REINFORCEMENT	SQ YD	339.00
	44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	690.00
	44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	36.00
	44201037	CLASS B PATCHES, TYPE IV, 15 INCH	EACH	303.00
	44201299	DOWEL BARS 1 1/2"	POUND	1,616.00
	44213200	SAW CUTS	FOOT	3,830.00
	44213204	TIE BARS 3/4"	EACH	70.00
	67100100	MOBILIZATION	L SUM	1.00
	70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8.00
	70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.00
	70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1.00
	70107025	CHANGEABLE MESSAGE SIGN	CAL DA	42.00
	X7200203	DETOUR SIGNING	L SUM	1.00
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1.00
* DENOTES SPECIALTY ITEM				



MODEL: SOQ-1 [Sheet]
FILE NAME: c:\paw\work\paw\tdol\person\td1053076\D570G88-shh-SOQ.dgn