



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 12, 2025

SUBJECT FAP Route 2 and FAU Route 9105 (IL 3/Main Street)  
Section (103,104)RS-2, 119RS-1  
Madison County  
Contract No. 76U26

Item No. 131, April 25<sup>th</sup>, 2025 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised pages i-ii of the Table of Contents of the Special Provisions.
3. Revised page 4 of the Special Provisions.
4. Add pages 8A-8C of the Special Provisions.
5. Revised sheets 2-4, 20, and 63 of the plans.
6. Add sheets 63A-68B of the plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

## TABLE OF CONTENTS

LOCATION OF PROJECT .....	1
DESCRIPTION OF PROJECT .....	1
SUBMITTAL OF EEO/LABOR DOCUMENTATION .....	2
PEAK HOUR RESTRICTIONS .....	4
TRAFFIC CONTROL PLAN .....	4
HOT-MIX ASPHALT SURFACE REMOVAL W/SKETCH OF ILLINOIS STANDARD W8-I107 .....	5
PAINT CURB .....	6
DETECTOR LOOP REPLACEMENT .....	7
TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL) .....	7
STATUS OF UTILITIES TO BE ADJUSTED .....	8
CLASS A PATCHES (SPECIAL) .....	8A
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) .....	9
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES; CONCRETE, AND MORTAR (BDE) .....	10
COMPENSABLE DELAY COSTS (BDE) .....	20
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) .....	23
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) .....	25
FUEL COST ADJUSTMENT (BDE) .....	27
HOT-MIX ASPHALT (BDE) .....	30
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE) .....	31
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE) .....	32
PAVEMENT MARKING INSPECTION (BDE) .....	32
PERFORMANCE GRADED ASPHALT BINDER (BDE) .....	33
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) .....	37
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE) .....	39
STEEL COST ADJUSTMENT (BDE) .....	42
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) .....	44
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) .....	45
SUBMISSION OF BIDDERS LIST INFORMATION (BDE) .....	45
SUBMISSION OF PAYROLL RECORDS (BDE) .....	45
SURFACE TESTING OF PAVEMENTS – IRI (BDE) .....	46
SURVEYING SERVICES (BDE) .....	52
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION .....	52
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) .....	54
WEEKLY DBE TRUCKING REPORTS (BDE) .....	54
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) .....	55

FAP ROUTE 2 AND FAU ROUTE 9105 (IL 3/MAIN STREET)  
SECTION (103,104)RS-2, 119RS-1  
MADISON COUNTY  
CONTRACT NO. 76U26

WORKING DAYS (BDE) ..... 56  
PROJECT LABOR AGREEMENT ..... 57

### PEAK HOUR RESTRICTIONS

The Contractor shall have all lanes open to traffic during peak hours in each direction along IL 3. The Contractor shall not be permitted to conduct any type of operation that would impede the flow of traffic during peak hours. The Contractor shall be permitted to have lane closures through the weekends, without peak hour restrictions, except for those holiday weekends specified in Article 107.09.

Peak hours are defined as:

AM: 6:00 AM – 8:00 AM  
PM: 3:00 PM – 5:00 PM

Should the Contractor fail to have all lanes open to traffic during the defined peak hours, the Contractor shall be liable and shall pay to the Department \$1000, not as a penalty but as liquidated damages, for every 15-minute interval or portion thereof that the flow of traffic is impeded by the Contractor's operations. The Department will deduct these liquidated damages from any monies due or to become due to the Contractor from the Department.

### TRAFFIC CONTROL PLAN

*Effective: July 12, 1993*

*Revised: May 12, 1997*

Traffic control shall be in accordance with the applicable sections of the "Standard Specifications for Road and Bridge Construction", the applicable guidelines contained in the "National Manual on Uniform Traffic Control Devices for Streets and Highways", Illinois Supplement to the National Manual of Uniform Traffic Control Devices, these special provisions, and any special details and highway standards contained herein and in the plans.

Special attention is called to Articles 107.09 and 107.14 of the "Standard Specifications for Road and Bridge Construction" and the following highway standards relating to traffic control:

701101      701422      701426      701601      701901

In addition, the following Special Provision(s) will also govern traffic control for this project:

Short Term and Temporary Pavement Markings  
Work Zone Traffic Control Devices  
Vehicle and Equipment Warning Lights

## **CLASS A PATCHES (SPECIAL)**

*Effective: February 8, 2021*

Description. This work shall consist of the removal of the existing pavement, the necessary excavation and the replacement with the class and type of patch specified at designated locations.

This work shall be according to Section 442 of the Standard Specifications for Class A.

Materials. Materials shall be according to Article 442.02 of the Standard Specifications.

### **CONSTRUCTION REQUIREMENTS**

Pavement Removal. Pavement removal shall be according to Article 442.05 of the Standard Specifications and as modified herein.

Revise Article 442.05(a) to read:

(a) Class A Patches. Two transverse full depth saw cuts shall be made perpendicular to the centerline at each end of the patch, except that the saw cuts may be skewed slightly if necessary to maintain a minimum distance of 18 inches from the end of the patch to the nearest transverse crack in the pavement to remain in place. When approved by the Engineer, this minimum distance may be reduced to 6 inches in areas of close crack spacing where the pavement otherwise appears to be sound. The longitudinal edges of the patch shall be formed by full-depth saw cuts. Saw cut extensions into pavement which is to remain in place will not be permitted. All saw cuts shall be made with an approved concrete saw. After the transverse saw cuts have been made, intermediate cuts as shown on plan details may be made to make pressure relief cuts or to reduce the pavement length to a size that accommodates removal and hauling operations. The saw cutting operations shall be controlled to limit subbase penetration to a maximum of 1/2 inch.

(b) The shoulder between the full-depth saw cut and the pavement edge shall be removed using a hand held hammer and hand tools prior to pavement removal. If available, the Contractor may use an approved wheel saw to make the shoulder cut and removal.

When the patch is adjacent to a Portland cement concrete shoulder, a saw cut shall be made at the shoulder-pavement joint sufficiently deep to sever the tie bars. A second full-depth saw cut shall be made in the pavement a minimum of 4 inches from the edge of the shoulder. The pavement between the full-depth saw cut and the shoulder edge shall be removed using a hand held hammer and hand tools prior to the removal of the remaining pavement.

The pavement between the saw cuts shall be removed by lifting. Sufficient care shall be taken to minimize subbase disturbance and prevent spalling of the pavement that is to remain in place. Any subbase or stabilize subbase material disturbed during pavement removal operations or determined unsuitable by the Engineer shall be removed and replaced with patch material.

If the Engineer determines that the concrete has deteriorated to the extent that it is not practical to lift, the pavement may be broken into small pieces and removed. The breaking equipment shall not transfer impact energy than 3,000 foot-pound per blow to the pavement surface.

Should the Contractor's operation cause a spall having a width or depth greater than 1 inch in the pavement to remain in place or cause excessive shattering or underbreaking of the existing slab

Revised 4-9-2025



to remain in place or cause excessive shattering or underbreaking of the existing slab to remain in place, a new saw cut shall be made extending the patch to remove the spall or underbreaking. After pavement removal, the pavement structure will be inspected by the Engineer to determine if it is sufficiently sound. If determined unsound, the Contractor shall extend the patch as directed by the Engineer.

Revise Article 442.06(a) to read:

(a) Reinforcement, Dowel Bars, and Joints. Reinforcement, dowel bars, joints shall be according to the following.

(1) Class A Patching. The reinforcement shall be constructed according to Articles 508.03 through 508.09.

Patch reinforcement (longitudinal) shall be tied to No. 6 epoxy coated tie bars, 33 inch long drilled and grouted into existing pavement at 12 inch centers.

Patches more than 20 feet in length shall be tied to the adjacent pavement, portland cement concrete shoulders, and curb and gutter with No. 6 transverse epoxy coated tie bars, 24 inches long, embedded 8 inch at 36 inch centers according to Article 420.05(b).

The Contractor shall tie the steel together, using at least two secure ties for each lap splice according to Article 508.08(a)(1).

Reinforcement steel shall be placed and supported on chairs according to Article 508.06, and the placement tolerance for individual reinforcement bars shall be +/- 1 inch horizontally and vertically.

Revise the first paragraph of Article 442.06(d) to read:

(d) Concrete Placement. The patch material shall match the elevation of the existing concrete pavement or hot-mix asphalt surface. Concrete shall be placed according to Article 420.07 of the Standard Specifications except a mechanical spreader will not be required. Placement shall be governed by the limitations set forth in Article 1020.14.

(e) Method of Measurement. This work will be measured according to Article 442.10 and as modified herein.

Revise the table and the third paragraph of the article to read:

% change of thickness	% change of quantity
0 to less than 15	0
15 to less than 20	10
20 to less than 30	15
30 to less than 50	20

If the thickness of the existing pavement varies by 50 percent or more from that shown on the plans, the character of the work will be considered significantly changed and an adjustment to the contract will be made according to Article 104.02.

Basis of payment. This work will be measured according to Article 442.11 and as modified herein.

Revised 4-9-2025

Revise paragraph 2 to read:

Where the Department requires a specific class of patch used, this work will be paid for at the contract unit price per square yard (square meter) for CLASS A PATCHES (SPECIAL), of the type and thickness specified. When a patch is adjacent to a wide flange beam terminal joint, this work will be paid for at the contract unit price per square yard (square meter) for PAVEMENT PATCHING (SPECIAL).

1