06A IDOT LETTING APRIL 25, 2025

DUPAGE AIRPORT AUTHORITY WEST CHICAGO, ILLINOIS CONSTRUCTION PLANS FOR DUPAGE AIRPORT

RECONSTRUCT POWIS ROAD APRON

ILLINOIS PROJECT: DPA-5200 S.B.G. PROJECT: 3-17-SBGP-TBD

FEBRUARY 28. 2025



LOCATION MAP

BATA

PROJECT

LOCATION

SITE PLAN

INDEX TO SHEETS

COVER SHEET

- SUMMARY OF QUANTITIES SITE PLAN/PROJECT CONTROL PLAN
- SEQUENCE OF CONSTRUCTION 1
- **SEQUENCE OF CONSTRUCTION 2**
- SEQUENCE OF CONSTRUCTIONN 3 SEQUENCE OF CONSTRUCTION GENERAL NOTES
- AND DETAILS 1
- SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS - 2
- STORM WATER POLITION PREVENTION PLAN 10. STORM WATER POLLUTION PREVENTION PLAN NOTES
- AND DETAILS 11. EXISTING CONDITIONS/PROPOSED REMOVALS
- 12 TYPICAL SECTIONS 1
- 13. TYPICAL SECTIONS 2
- 14. GRADING AND DRAINAGE PLAN
- 15. JOINTING PLAN
- 16. JOINTING DETAILS
- 17. PROPOSED IMPROVEMENTS
- 18. MISCELLANEOUS DETAILS -
- 19. MISCELLANEOUS DETAILS 2
- 20. GEOTECHNICAL INFORMATION





CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811.

DU094 TOTAL SHEETS = 20

CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS License No. 184-000613 SUBMITTED BY
DUPAGE AIRPORT AUTHORITY DuPage Airport
2700 INTERNATIONAL DRIVE SUITE 200 WEST CHICAGO, IL. 60185
APPROVED BY
DATE02/28/2025

NCMT

22004901-00

Steller A

SUMMARY OF QUANTITIES					
ITEM	DESCRIPTION	FEDERAL/STATE/ LOCAL QUANTITY	LOCAL ONLY QUANTITY	TOTAL QUANTITY	UNIT
AR150510	ENGINEER'S FIELD OFFICE	1	0	1	L SUM
AR150520	MOBILIZATION	1	0	1	L SUM
AR152410	UNCLASSIFIED EXCAVATION	440	0	440	CU YD
AR152540	SOIL STABILIZATION FABRIC	978	522	1,500	SQ YD
AR152511	SUBGRADE REPAIR	1055	505	1,560	SQ YD
AR156520	INLET PROTECTION	8	0	8	EACH
AR209606	CRUSHED AGG. BASE COURSE - 6"	1368	522	1,890	SQ YD
AR209650	AGGREGATE BASE PREPARATION	2840	1150	3,990	SQ YD
AR401610	BITUMINOUS SURFACE COURSE	157	193	450	TON
AR401900	REMOVE BITUMINOUS PAVEMENT	4330	0	4,330	SQ YD
AR401810	BITUMINOUS TRANSITION	45	0	45	SQ YD
AR403610	BITUMINOUS BASE COURSE	490	350	840	TON
AR501506	6" PCC PAVEMENT	1600	0	1,600	SQ YD
AR501530	PCC TEST BATCH	1	0	1	EACH
AR501605	5" PCC SIDEWALK	135	0	135	SQ FT
AR501690	PCC SIDEWALK REMOVAL	170	0	170	SQ FT
AR501900	REMOVE PCC PAVEMENT	840	0	840	SQ YD
AR510510	TIE DOWN	0	21	21	EACH
AR510900	REMOVE TIE DOWN	21	0	21	EACH
AR602510	BITUMINOUS PRIME COAT	635	505	1,140	GALLON
AR603510	BITUMINOUS TACK COAT	219	156	375	GALLON
AR620520	PAVEMENT MARKING - WATERBORNE	0	80	80	SQ FT
AR701200	SLOTTED DRAIN	75	0	75	FOOT
AR701512	12" RCP, CLASS IV	15	0	15	FOOT
AR701900	REMOVE PIPE	4	0	4	FOOT
AR705506	6" PERFORATED UNDERDRAIN	123	0	123	FOOT
AR751540	MANHOLE 4'	2	0	2	EACH
AR751943	ADJUST MANHOLE	1	0	1	EACH
AR901510	SEEDING	0.05	0	0.1	ACRE
AR908515	HEAVY-DUTY HYDRAULIC MULCH	0.05	0	0.1	ACRE



SEE NOTES 2&3











ht: K:UupageApi22004901-00. ReconPowisRdApron/Draw/Sheets/2200490100 - DPA - Sequence of Con.

	DU094 SCMT
UL ROUTE ACE IAL CTIONS ER TAXIWAYS OPEN	FINAL FEBRUARY 28, 2025 RECONSTRUCT POWIS ROAD APRON
A) -TOFA TOFA TOFA TOFA TOFA TOFA TOFA	DUPAGE AIRPORT AUTHORITY
CONTRACTOR'S STAGING AND STORAGE AREA EXISTING GATE C D A	DUPAGE AIRPORT WEST CHICAGO, ILLINOIS

GENERAL

- THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE REQUIREMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP), FAA AC 150/5370-2G OR LATEST EDITION, AND ALL AIRPORT SAFETY AND SECURITY REQUIREMENTS.
- PRIOR TO THE NOTICE TO PROCEED, THE CONTRACTOR SHALL SUBMIT TO THE 2. AIRPORT THROUGH THE RESIDENT ENGINEER, FOR APPROVAL A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2G OR LATEST EDITION. NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT HAS APPROVED THE SPCD.
- THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER PERSONNEL AND MEETING З. OSHA REQUIREMENTS
- A MINIMUM OF 10 DAYS PRIOR TO THE NOTICE TO PROCEED THE CONTRACTOR 4 SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL SUPPLIERS.
- ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED ON THIS 5. SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE NEW IMPROVEMENTS WHILE MAINTAINING TENANT/AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED WITH THE APPROVAL OF THE ENGINEER IN CONSULTATION WITH THE AIRPORT DIRECTOR OF OPERATIONS. HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT DIRECTOR OF OPERATIONS.

1. COORDINATION

- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A 1. PRE-CONSTRUCTION CONFERENCE WITH THE AIRPORT AND RESIDENT ENGINEER. THE COST OF PREPARING FOR AND ATTENDING THE PRE-CONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT.
- PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT A 2. PROGRESS SCHEDULE TO BE APPROVED BY THE ENGINEER. THIS SCHEDULE SHALL SHOW START/ STOP DATES OF ALL PHASES. THE APPROVED PROGRESS SCHEDULE SHALL BE DISTRIBUTED TO ALL PARTIES 3 WORKING DAYS PRIOR TO START OF CONSTRUCTION. THE CONTRACTOR MAY BE REQUIRED TO SUBMIT A REVISED PROGRESS SCHEDULE TO ACCOMMODATE AIRPORT EVENTS OR CONTRACTOR'S LACK OF PROGRESS, SHOULD A REVISED SCHEDULE BE REQUIRED, THE REVISION SHALL BE COMPLETED AT NO ADDITIONAL COST TO THE CONTRACT
- DURING CONSTRUCTION THE CONTRACTOR SHALL ATTEND A WEEKLY COORDINATION MEETING WITH AIRPORT STAFF, FAA, RESIDENT ENGINEER AND 3. OTHER APPROPRIATE STAKE HOLDERS TO DISCUSS PROJECT PROGRESS. AT A MINIMUM, PROJECT SCHEDULE SHALL BE DISCUSSED. REPRESENTATION BY THE PRIME CONTRACTOR IS MANDATORY. ALL COSTS ASSOCIATED WITH ATTENDING THE WEEKLY MEETING SHALL BE INCIDENTAL TO THE CONTRACT

2. PHASING

- TOTAL CONTRACT TIME SHALL BE 63 CALENDAR DAYS
- PHASING SHALL BE AS NOTED BELOW AND AS SHOWN ON THE 2 CONSTRUCTION SAFETY AND PHASING PLANS.
- TO CLOSE A RUNWAY OR TAXIWAY, THE CONTRACTOR SHALL PLACE 3 RUNWAY AND TAXIWAY CLOSURE MARKERS AND BARRICADES AT THE LOCATIONS SPECIFIED. TO RE-OPEN THE RUNWAY OR TAXIWAY, THE CONTRACTOR SHALL CLEAN ANY DEBRIS OFF OF THE PAVEMENT AND BEMOVE THE BUNWAY/TAXIWAY CLOSUBE MARKERS ALL WORK ASSOCIATED WITH CLOSING AND OPENING AIRFIELD PAVEMENTS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- CONTRACTOR SHALL COVER ALL AIRFIELD SIGNS AND LIGHTS ON CLOSED TAXIWAYS UNTIL THE TAXIWAY IS REOPENED FOR AIRCRAFT USE. THE METHOD AND MATERIALS USED TO COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL.
- SEE CONTRACTOR ACCESS NOTES ON THIS SHEET FOR SITE ACCESS AND 5. AULING GUIDELINES.
- PRIOR TO REOPENING A CLOSED RUNWAY OR TAXIWAY. THE ENTIRE RUNWAY SAFETY AREA (RSA), MEASURED 250 FEET FROM THE RUNWAY CENTERLINE, INCLUDING BEYOND THE RUNWAY END WITHIN THE EXTENDED RSA, AND THE ENTIRE TAXIWAY OBJECT FREE AREA (TOFA), MEASURED 85.5 FEET FROM GROUP III TAXIWAYS (I.F. TAXIWAY C AND G) MUST MEET FAA CRITERIA. FAA CRITERIA REQUIRES THAT THERE BE NO OPEN EXCAVATIONS OR TRENCHES IN THESE AREAS. THE MAXIMUM PAVEMENT DROP OFF SHALL BE 3 INCHES, AND ALL GRADES IN ANY DIRECTION BE LESS THAN 3 PERCENT, STEEL PLATES OR TEMPORARY WEDGING OF BASE COURSE MAY BE REQUIRED TO MEET CRITERIA. ALL NECESSARY TEMPORARY MEASURES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- NO MATERIAL OR FOLIPMENT SHALL BE STOCKPILED WITHIN AN BSA, BOFA APRON OR OBSTACLE FREE ZONE (OFZ) OF AN ACTIVE RUNWAY, OR WITHIN THE TOFA OF AN ACTIVE TAXIWAY
- 8. WORK AREAS AND DESCRIPTIONS

3. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY

- ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE PHASING PLAN.
- 2. THE ENGINEER AND AIRPORT DIRECTOR OF OPERATIONS OR HIS DESIGNATED REPRESENTATIVE SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING SEQUENCE AS IT RELATES TO PEDESTRIAN. VEHICULAR AND AIRCRAFT OPERATIONS AIRCRAFT OPERATIONS HAVE THE RIGHT-OF-WAY ON THE AIRFIELD. VEHICULAR TRAFFIC AND CONTRACTOR ACTIVITIES SHALL YIELD TO AIRCRAFT OPERATIONS, SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE FOUIPMENT AT ANY TIME TO ALLOW AN AIRCRAFT TO PASS, THE CONTRACTOR SHALL DO SO IMMEDIATELY AT NO EXTRA COST TO THE OWNER.

4. NAVAIDS THAT COULD BE AFFECTED

NOT APPLICABLE

5. CONTRACTOR ACCESS

- THE CONTRACTOR ACCESS ROAD AND STAGING AREAS SHALL BE AS SHOWN ON THE REFERENCED PLAN. THE CONTRACTOR SHALL MAINTAIN AND REPAIR THE CONSTRUCTION ACCESS ROAD AND STAGING AREA IN ITS ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE CONTRACT. ALTERNATE STAGING AREAS AND ACCESS FOR THIS AREA WILL NOT BE ALLOWED
- THE ENTRANCE SHALL BE SIGNED ACCORDINGLY AS TO ALLOW ONLY 2. CONSTRUCTION VEHICLE ACCESS AND WILL ONLY BE ACCESSIBLE DURING THE CONTRACTOR'S SCHEDULED WORK DAY. ALL SIGNAGE SHALL CONFORM TO THE CITY OF WEST CHICAGO AND IDO CONSTRUCTION STANDARDS FOR VEHICLES ENTERING AND LEAVING THE SITE
- THE GATE SHALL BE MAINTAINED, CLOSED AND LOCKED AS DIRECTED BY THE AIRPORT DIRECTOR OF OPERATIONS. SHOULD 3. THE CONTRACTOR'S OPERATIONS REQUIRE THE GATE TO REMAIN OPEN TO PROVIDE ACCESS TO HAULING OPERATIONS, A COMPETENT GATE GUARD SHALL BE REQUIRED TO CONTROL ACCESS TO THE AIRFIELD. A \$1,000 FINE SHALL BE ASSESSED FOR ANY OCCURRENCE OF AN UNSECURE GATE THAT IS THE CONTRACTOR'S RESPONSIBILITY. AN UNSECURED GATE SHALL BE DEFINED AS ANY GATE THAT IS NOT WITHIN THE SIGHT AND PHYSICAL CONTROL OF THE CONTRACTOR'S GUARD. IN THE EVENT THAT THE GATE MAY NOT BE SECURED, THE CONTRACTOR WILL BE CHARGED FOR AIRPORT PERSONNEL TO REMAIN AT THE GATE UNTIL SECURED.
- CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND TEMPORARY FASEMENTS FOR THE PUBLIC ACCESS BOAD(S) SHOWN AND SHALL COMPLY WITH ALL REQUIREMENTS. LOAD RESTRICTIONS. & TRAFFIC CONTROL SIGNAGE REQUIRED BY THE CITY, COUNTY, TOWNSHIP, OR I.D.O.T
- THE CONTRACTOR WILL BE BEQUIRED TO PUT AIRPORT FLAGS AND 5 HAVE BEACON (FLASHING YELLOW) LIGHTS ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION.
- THE CONTRACTOR SHALL KEEP A RECORD OF THE NAMES OF ALL 6. EMPLOYEES ENTERING THE JOB SITE ON A DAILY BASIS. A RECORD OF EACH SUBCONTRACTOR ENTERING THE JOB SITE SHALL ALSO BE KEPT BY THE CONTRACTOR
- THE CONTRACTOR'S MATERIAL AND EQUIPMENT, WHEN NOT IN USE, 7. SHALL BE STORED IN THE CONTRACTOR'S STAGING AREA. ALL DELIVERIES, EQUIPMENT REFUELING, EQUIPMENT MAINTENANCE AND EQUIPMENT TRANSFERS SHALL TAKE PLACE WITHIN THE CONTRACTOR'S STAGING AREA
- 8. DURING ADVERSE WEATHER THE CONTRACTOR SHALL MAINTAIN ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF THE CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK SITE.

- THE CONTRACTOR WILL BE PERMITTED TO STORE FOURPMENT AND 10. MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE. EXISTING TURF AREAS DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT.
- 11. ALL CONSTRUCTION TRAFFIC OPERATING ON, OR CROSSING RUNWAYS, TAXIWAYS AND APRONS OPEN TO AIRCRAFT TRAFFIC SHALL BE UNDER CONTROL BY A FLAGMAN OR ESCORT IN RADIO CONTACT WITH THE CONTROL TOWER. THE CONTRACTOR SHALL PROVIDE HIS OWN FLAGMEN.
- 12. IF NECESSARY, THE CONTRACTOR SHALL CONSTRUCT A HAUL BOUTE TO THE STAGING AREA WITHIN THE PROJECT LIMITS HAU ROUTE(S) SHALL BE INCIDENTAL TO THE COST OF MAINTENANCE OF TRAFFIC. ALL HAUL ROUTE(S) INCLUDING EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE ENGINEER AND AIRPORT DIRECTOR OF OPERATIONS. THE COST OF MAINTAINING, REPAIRING SEEDING /MULCHING OR CONSTRUCTING THESE HAUL ROUTE(S) SHALL BE INCIDENTAL TO THE COST OF THE CONTRACT.
- ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS 13. A STAGING AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE ENGINEER AND AIRPORT OPERATION MANAGER. THE COST OF MAINTAINING, REPAIRING SEEDING /MULCHING OR CONSTRUCTING THESE PAVEMENTS / AREAS SHALL BE INCIDENTAL TO THE CONTRACT.
- ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE 14. CONTRACTOR SHALL BE PROPERLY TRAINED BY THE CONTRACTOR.
- THE CONTRACTOR SHALL NOTIFY THE AIRPORT IF CONSTRUCTION 15 ACTIVITY WILL REQUIRE THE BLOCKAGE OF EMERGENCY ACCESS TO THE AIRPORT
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE DUST CONTROL 16. AT ALL TIMES DURING THE PROJECT DURATION. A WATER TRUCK SHALL BE REQUIRED TO BE ON SITE DURING ALL CONSTRUCTION OPERATION WORKING HOURS, UNLESS WAIVED BY THE DEPUTY DIRECTOR OF OPERATIONS. PAYMENT FOR DUST CONTROL SHALL BE INCIDENTAL TO THE CONTRACT.

6. WILDLIFE MANAGEMENT

- THE CONTRACTOR SHALL NOTIFY THE AIRPORT OR THE RESIDENT ENGINEER IF ANY WILDLIFE IS SEEN ENTERING THE AIRPORT.
- CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE 2. CONTRACTOR IS NOT WORKING.
- THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD SCRAPS IN APPROVED CONTRACTOR PROVIDED CONTAINERS.

- 1 SEEN ON THE AIRFIELD PAVEMENTS
- 2. THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES PRIOR TO DRIVING ON AIRFIELD PAVEMENTS
- THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND 3. MATERIALS OFF OF THE EXISTING PAVEMENT OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE ENGINEER. SHOULD THE CONTRACTOR TRACK ANY DEBRIS ONTO EXISTING PAVEMENTS, THIS DEBRIS SHALL BE REMOVED IMMEDIATELY WITH A PICK UP SWEEPER. A PICK UP SWEEPER SHALL BE REQUIRED TO BE ON SITE AND OPERATE DURING ALL CONSTRUCTION OPERATION WORKING HOURS, UNLESS WAIVED BY THE EXECUTIVE DIRECTOR OF OPERATIONS. THE CONTRACTOR SHALL PROVIDE WASTE RECEPTACLES THROUGHOUT THE WORK ZONE AND MAINTAIN SANITABY FACILITIES FOR EMPLOYEES TO USE FACILITIES WITHIN THE HANGARS/AIRPORT BUILDINGS SHALL NOT BE USED.

8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT

THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE

- BARRICADES
- 3
- FNGINFFF

10. INSPECTION REQUIREMENTS

- THE INSPECTIONS.
- 2.

OPENED.

7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

- THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD)
- FNGINFFR 2.

9. NOTIFICATION OF CONSTRUCTION ACTIVITIES

THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER. PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND

THE CONTRACTOR SHALL GIVE A MINIMUM OF 10 DAYS NOTICE TO THE FAA AND AIRPORT PRIOR TO THE CLOSURE OF ANY RUNWAY SO THAT THE FAA MAY DEACTIVATE THE FAA - OWNED NAVAIDS.

THE CONTRACTOR SHALL GIVE A MINIMUM 30 DAYS NOTICE TO THE AIRPORT, AND PRIOR TO THE PRE-CONSTRUCTION CONFERENCE PRIOR TO CLOSING ANY BUNWAY OR TAXIWAY PAVEMENT SO THAT THE PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT FOR COORDINATION WITH THE AIRPORT TENANTS.

FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY. NO EQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.

IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL NOTIFY THE EXECUTIVE DIRECTOR OF OPERATIONS AND THE RESIDENT

THE CONTRACTOR SHALL INSPECT THE JOBISTE DAILY TO ENSURE COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF FAA AC 150/5370-2G OR LATEST EDITION MAY BE USED TO AID IN

THE CONTRACTOR SHALL REQUEST OPERATIONAL INSPECTION OF FACH PHASE WORK AREA PRIOR THE AREA BEING REOPENED. THE AIRPORT WILL DETERMINE IF THE WORK AREA IS ALLOWED TO BE

11. UNDERGROUND UTILITIES

COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. SEE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHAT SO EVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED. THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES. INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY/OWNER OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED. INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER AND THE ENGINEER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE

SHOULD A UTILITY COMPANY OR GOVERNMENT AGENCY BE UNABLE TO LOCATE FACILITIES, THE CONTRACTOR SHALL LOCATE THESE FACILITIES. PAYMENT FOR THIS LOCATION SHALL BE INCIDENTAL TO THE IMPROVEMENTS REQUIRING THE LOCATIONS

IT IS ASSUMED THAT MOST, BUT NOT ALL UTILITIES WITHIN THE PROJECT AREA WILL BE PREVIOUSLY ABANDONED. CONTRACTOR TO VERIFY UTILITIES ARE ABANDONED PRIOR TO REMOVALS TAKING PLACE AT NO ADDITIONAL COST TO CONTRACT.

4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY/OWNER OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER AND THE ENGINEER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE ENGINEER

DU094

CONSULTANTS

FINAL

FEBRUARY 28, 2025

RECONSTRUCT **POWIS ROAD APRON**

DUPAGE AIRPORT Authority

OWNER

DUPAGE AIRPORT WEST CHICAGO, ILLINOIS

MARK DATE DESCRIPTION

AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. DPA-5200 CMT PROJECT NO: 22004901.00 CAD DWG FILE: DESIGNED BY EJR DRAWN BY: JBO CHECKED BY: DKP PPROVED BY: DLP COPYRIGHT

SHEET TITLE

SHEET 7

SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS - 1

OF

20

12. PENALTIES

- NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT RULES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS ALLOWED BY LAW
- THE CONTRACTOR SHALL RESTRICT ALL CONSTRUCTION 2. ACTIVITIES TO THE CONSTRUCTION AREA DETAILED IN THE PHASING PLAN. ANY UNAUTHORIZED MOVEMENTS, PEDESTRIAN OR VEHICULAR, BEYOND THE CONSTRUCTION LIMITS SHOWN SHALL BE CONSIDERED AN AIRFIELD INCURSION. AIRFIELD INCURSIONS, AT THE DISCRETION OF THE AIRPORT DIRECTOR OF OPERATIONS, MAY BE FINED \$1,000.00 PER INCIDENT. INCURSION FINES WILL BE ASSESSED IMMEDIATELY AND TAKEN FROM MONIES DUE THE CONTRACTOR ON THE NEXT CONSTRUCTION PAYMENT.
- LIQUIDATED DAMAGES IN THE AMOUNT OF \$750/DAY MAY BE DEDUCTED FROM THE MONIES OWED TO THE CONTRACTOR FOR З. EACH CALENDAR DAY OVER THE TIMEFRAME ALLOWED FOR EACH PHASE OR WORK AREA UNTIL THE SPECIFIED WORK IS COMPLETED AND ACCEPTED BY THE AIRPORT AND RESIDENT FNGINFFR

13. SPECIAL CONDITIONS

ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL INFORMATION

14. RUNWAY AND TAXIWAY VISUAL AIDS

- ALL RUNWAYS, TAXIWAYS, AND APRONS SHALL BE KEPT OPEN TO AIRPORT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED IN THE CONSTRUCTION SAFETY AND PHASING PLAN.
- IF ANY RUNWAY OR TAXIWAY CLOSURES ARE REQUESTED BY THE 2. CONTRACTOR AND APPROVED BY THE AIRPORT, THE CONTRACTOR SHALL USE MARKING LIGHTING AND SIGNS THAT FOLLOWING THE REQUIREMENTS OF FAA AC 150/5370-2G OR LATEST EDITION.

15. MARKING AND SIGNS FOR ACCESS ROUTES

BARRICADES AND SIGNS SHALL BE USED ALONG THE CONTRACTOR'S ACCESS ROUTE AS DETAILED ON THE CONSTRUCTION SAFETY AND PHASING PLAN.

16. HAZARD MARKING AND LIGHTING

- THE CONTRACTOR SHALL FURNISH ERECT AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT
- ALL CONSTRUCTION EQUIPMENT SHALL BE FLAGGED AND/OR 2 LIGHTED IN ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2G AND 150/5210-5C OR LATEST EDITION AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY. THE MAXIMUM EQUIPMENT HEIGHT IS 25'.
- 3 BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET OR AS DIRECTED BY THE ENGINEER
- THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING 4. EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS AND FLAG PLACEMENT.
- PAYMENT FOR ALL AIRSIDE AND ROADWAY TRAFFIC CONTROL 5. INCLUDING, BUT NOT LIMITED TO. TEMPORARY CONSTRUCTION FENCING, BARRICADES, SIGNING, AIR OPERATIONS AREA (A.O.A.) LATH AND RIBBON, ETC. SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT, BARRICADES USED ON THE AIRFIELD MUST BE INTERLOCKING LOW PROFILE BARBICADES, INTERLOCKING LOW PROFILE BARRICADES WITH STEADY BURN RED LIGHTS SHALL BE INTERLOCKED WITH NO GAPS BETWEEN BARRICADES. BARRICADES SHALL BE PLACED AS SHOWN ON THIS PLAN AND AS DIRECTED BY THE ENGINEER FOR WORK ADJACENT TO THE EXPEDITED WORK AREA. WHEN NOT IN USE, THESE BARRICADES SHALL BE STORED AT THE CONTRACTOR'S STAGING AREA OR OFF SITE. ACCESS TO THE ACTIVE RUNWAY AND TAXIWAY PAVEMENTS (TOWER CONTROLLED AREAS) SHALL BE SIGNED WITH STOP SIGNS MOUNTED ON THE CLOSEST BARRICADES (2 EACH, RIGHT AND LEFT) AT THE ENTRANCE. IN ADDITION TO THE STOP SIGNS, WARNING SIGNS (2 EACH, RIGHT AND LEFT) SHALL BE MOUNTED. WARNING SIGNS SHALL STATE TOWER CONTROL AREA / UNAUTHORIZED ACCESS SUBJECT TO FINE." ALL NON AIRFIELD LOCATIONS REQUIRING BARRICADES SHALL BE TYPE II OR TYPE III BARRICADES AND SHALL CONFORM TO IDOT STANDARD DETAIL 701901-04.

17. WORK ZONE LIGHTING FOR NIGHTTIME CONSTRUCTION

- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL AREA LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTION.
- LIGHTS SHALL CONSIST OF VEHICLE OR MOVABLE POLE 2. MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA, VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS. MENTIONED ABOVE. LIGHTING SHALL NOT INTERFERE WITH AIR OPERATIONS. ANY WORK BEING PERFORMED UNDER INSUFFICIENT ARTIFICIAL LIGHTING, IN THE RESIDENT ENGINEER'S JUDGEMENT, SHALL BE STOPPED UNTIL SUCH TIME AS ADDITIONAL LIGHTING IS PROVIDED. ALL WORK PERFORMED DURING THAT TIME WILL NOT BE ACCEPTABLE UNTIL PROPER INSPECTION AND TESTING CAN BE MADE

18. PROTECTION

- ALL WORK REQUIRED INSIDE OF A RUNWAY SAFETY AREA, WILL REQUIRE THE RUNWAY TO BE CLOSED.
- ALL WORK REQUIRED ON AN ACTIVE TAXIWAY OR INSIDE OF AN ACTIVE TAXIWAY OBJECT FREE AREA, WILL REQUIRE THE TAXIWAY TO BE CLOSED.

19. OTHER LIMITATIONS ON CONSTRUCTION

- IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE AIRPORT, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES, PERSONNEL AND EQUIPMENT
- BROKEN CONCRETE, BROKEN ASPHALT, BUBBISH FROM DEMO. 2. AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS OTHERWISE SPECIFIED.
- THE CONTRACTOR WILL BE RESPONSIBLE FOR COORDINATING З. THE AIRSPACE FOR THE CONSTRUCTION EQUIPMENT THAT IS TALLER THAN THAT SPECIFIED ON THE PLANS WITH THE FAA. THIS PROCESS MAY TAKE UP TO 12 WEEKS TO COMPLETE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEGGAR TESTING ALL EXISTING CIRCUITS PRIOR TO CONSTRUCTION AND FOLLOWING CONSTRUCTION AS SPECIFIED IN THE CONTRACT DOCUMENTS.

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS. WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE STANDARD SPECIFICATIONS SECTION 30-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS. IT IS ANTICIPATED THE FOLLOWING PROJECTS MAY BE UNDER CONSTRUCTION CONCURRENTLY WITH THIS PROJECT. NO ADDITIONAL COMPENSATION SHALL BE CONSIDERED FOR ANY EFFORTS TO COORDINATE AND ACCESS THE WORK SITE DUE TO ADJACENT CONSTRUCTION

• 2025 AIRFIELD PAVEMENT REPAIR AND REMARKING. REHABILITATE AIRFIELD PAVEMENTS/ISOLATED PAVEMENT REPLACEMENTS; RUNWAY 2L/20R AND 2R/20L, TAXIWAY C AND W

DESIGN INFORMATION

APRON TAXILANE = TAXIWAY DESIGN GROUP 2A TAXIWAY A = AIRPORT DESIGN GROUP III



CONSTRUCTION SETBACK LINE DETAIL NOT TO SCALE

CONSTRUCTION SETBACK NOTES

- 1. CONTRACTOR SHALL MARK THE RUNWAY SAFETY AREA, TAXIWAY OBJECT FREE REA AND RUNWAY OBSTACLE FREE ZONE PER THE CONSTRUCTION SETBACK DETAIL AS DIRECTED BY THE RESIDENT ENGINEER
- 2. ALL COST ASSOCIATED WITH THE CONSTRUCTION SETBACK LINE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT

AIRFIELD LIGHTS AND SIGNS NOTES

- CONTRACTOR SHALL COVER ALL AIRFIELD SIGNS AND TAXIWAY LIGHTS ON CLOSED TAXIWAYS UNTIL THE TAXIWAY IS RE-OPENED FOR AIRCRAFT USE. THE METHOD AND MATERIALS USED TO COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL. COST INCIDENTAL TO THE CONTRACT. REMOVING LAMPS FROM ENERGIZED FIXTURES AS A MEANS TO REMOVE THE LIGHTS OR FIXTURES FROM SERVICE SHALL NOT BE ACCEPTABLE
- 2. CONTRACTOR SHALL TURN OFF RUNWAY EDGE LIGHTING REGULATOR AND LOCK-OUT/TAG-OUT CIRCUIT BREAKER AND CUT OUT INSIDE THE ELECTRICAL VAULT. DURING ALL RUNWAY CLOSURES. CONTRACTOR SHALL COORDINATE ACCESS TO THE VAULT WITH THE AIRPORT MANAGER/RESIDENT ENGINEER PRIOR TO RE-OPENING THE RUNWAY, THE CONTRACTOR SHALL COORDINATE WITH AIRPORT MANAGER/RESIDENT ENGINEER TO RE-ENERGIZE THE RUNWAY CIRCUIT.

AND TRUCK SIGNAL FLAG NOT TO SCALE





INTERLOCKING LOW PROFILE BARRICADES

NOTES

- OR AS DIRECTED BY THE RESIDENT ENGINEER. THE BARRICADES SHALL BE INTERLOCKED WITH NO GAPS BETWEEN BARRICADES. BARRICADES SHALL BE OVER
- INTO THE TURF
- 3. LIGHTS SHALL BE BATTERY OPERATED, LENS SHALL BE RED AND BE ABLE TO ROTATE 90°
- 5. ALTERNATE LENSES SO THAT EVERY OTHER LENS IS ROTATED 90°
 - GRADE LEVEL OR AS LOW POSSIBLE, BUT NOT TO EXCEED 3 INCHES ABOVE THE GROUND
 - 7. ALL COST ASSOCIATED WITH THE LOW PROFILE BARRICADES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT

FAA CRITICAL POINT TABLE					
POINT	APPROXIMATE ELEVATION OF GROUND (NAVD 88)	ANTICIPATED EQUIPMENT AND HEIGHT	APPROXIMATE ELEVATION OF EQUIPMENT (NAVD 88)	LATITUDE (NAD 83)	LONGITUDE (NAD 83)
А	753.41	SEMI/DUMP TRUCK - 25'	778.41	N041° 54' 59.72"	W088° 14' 18.03"
В	753.42	SEMI/DUMP TRUCK - 25'	778.42	N041° 54' 59.72"	W088° 14' 18.34"
С	752.97	SEMI/DUMP TRUCK - 25'	777.97	N041° 54' 59.10"	W088° 14' 18.35"
D	752.96	SEMI/DUMP TRUCK - 25'	777.96	N041° 54' 59.10"	W088° 14' 18.03"
E	753.93	SEMI/DUMP TRUCK - 25'	778.93	N041° 54' 53.81"	W088° 14' 22.19"
F	753.15	SEMI/DUMP TRUCK - 25'	778.15	N041° 54' 54.64"	W088° 14' 22.18"
G	753.48	SEMI/DUMP TRUCK - 25'	778.48	N041° 54' 53.92"	W088° 14' 24.12"
Н	754.46	SEMI/DUMP TRUCK - 25'	779.46	N041° 54' 51.69"	W088° 14' 23.79"
I	751.29	SEMI/DUMP TRUCK - 25'	776.29	N041° 54' 56.67"	W088° 14' 24.08"
J	753.49	SEMI/DUMP TRUCK - 25'	778.49	N041° 54' 53.86"	W088° 14' 24.12"

DU094



CONSTRUCTION EQUIPMENT



SAFETY ORANGE

1. LOW PROFILE BARRICADES SHALL BE PLACED AT LOCATIONS SHOWN ON THE PLANS WEIGHTED WITH A MINIMUM OF 6 SAND BAGS TO PREVENT THEM FROM BEING BLOWN

2. THE BARRICADE LINE SHALL EXTEND ONE BARRICADE PAST THE EDGE OF PAVEMENT

4. FACING OF BARRICADE SHALL BE COVERED WITH REFLECTIVE TAPE OR PAINT.

6 BARRICADES SHALL BE OF LOW MASS, FASILY COLLAPSIBLE UPON CONTACT WITH AN AIRCRAFT OR ANY OF IT'S COMPONENTS, AND WEIGHTED OR STURDILY ATTACHED TO THE SURFACE. IF AFFIXED TO THE SURFACE, THE BARRICADE MUST BE FRANGIBLE AT



CONSULTANTS

FINAL

FEBRUARY 28, 2025

RECONSTRUCT **POWIS ROAD APRON**

DUPAGE AIRPORT Authority

OWNER

DUPAGE AIRPORT WEST CHICAGO, ILLINOIS

MARK DATE DESCRIPTION

AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. DPA-5200 CMT PROJECT NO: 22004901.00 CAD DWG FILE: DESIGNED BY: FJB DRAWN BY: JBO CHECKED BY: DKP APPROVED BY: DLP COPYRIGHT

SHEET TITLE

SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS - 2

SHEET 8

OF

20



\22004901-00_ReconPov ary 28, 2025 1:13:23 PM K:\DupageAp\ Friday, Februa

STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEERAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE AT TH CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND JE ANY ADDITIONAL TEMPORARY EBOSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION:

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF RECONSTRUCTION OF AN EXISTING BITUMINOUS AND CONCRETE APRON PAVEMENT AT DUPAGE AIRPORT AUTHORITY. THE PROJECT INCLUDES VARIOUS PAVEMENT ITEMS, PAVEMENT MARKING AND OTHER MISCELLANEOUS CONSTRUCTION WORK.

DESCRIPTION OF CONSTRUCTION ACTIVITY:

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE:

- PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL, SUCH AS
- INLET PROTECTION.
- EXISTING PAVEMENT REMOVAL
- NEW PAVEMENT CONSTRUCTION
- TOPSOILING, SEEDING AND MULCHING
- INSTALLATION OF NEW PAVEMENT MARKING.

REMOVAL AND DISPOSAL OF TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES.

AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE LESS THAN AN ACRE WILL BE DISTURBED BY GRADING AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

THE CONSTRUCTION SITE DRAINS INTO STORM SEWER SYSTEMS THAT OUTLET INTO KRESS CREEK

EROSION AND SEDIMENT CONTROL:

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION:

THE DRAWINGS SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, SOD, PROTECTION OF TREES, PRESERVATION OF NATURAL VEGETATION, AND ALL OTHER APPROPRIATE MEASURES AS DIRECTED BY THE ENGINEER, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE STE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.

AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES.

DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER.

AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, INLET PROTECTIONS SHALL BE INSTALLED AS CALLED OUT IN THE PLAN AND DIRECTED BY THE ENGINEER.

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES.

WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.

EARTH STOCKPILES SHALL BE <u>TEMPORARILY SEEDED</u>, AT THE CONTRACTOR'S EXPENSE, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN SEVEN (7) DAYS.

THE DOWN STREAM SIDE OF ALL STOCKPILES SHALL BE ENCOMPASSED WITH EROSION CONTROL BARRIER

AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER

A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.

CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS WITHIN THE STAGING AREA. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.

THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT PERIODICALLY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2" OF GREATER OR EQUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE RESIDENT ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT THE EROSION AND SEDIMENT CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER EROSION CONTROL WORK IS NECESSARY

SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR UNCLASSIFIED EXCAVATION AND EROSION

THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING SOIL CONTAMINATION FROM BUILDING MATERIALS, FERTILIZERS, CHEMICALS, PAVEMENT MARKING, WASTE PILES, FUEL CONTAINMENT, AND ANY OTHER POTENTIAL HAZARDOUS MATERIALS THAT MAY EXIST ONSITE.

NO DEDICATED CONCRETE OR ASPHALT BATCH PLANTS SHALL BE LOCATED ON THIS SITE.

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

COST OF MAINTAINING THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE INCLUDED INCLUDED IN THE UNIT BID PRICE FOR THE VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RE-SEEDED AND/OR SODDED.

MAINTENANCE AFTER CONSTRUCTION

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE OF TEMPORARY AND PERMANENT EROSION CONTROL SYSTEMS UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.



GENERAL NOTES FOR SOIL EROSION AND SEDIMENT CONTROL

- ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION.
- 2. NO WORK SHALL BE PERFORMED IN FLOWING WATER, WORK IN AND NEAR FLOWING WATER SHALL BE SIGUATED FROM CONCENTRATED FLOWS OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL FOR ISOLATION WILL NOT BE ACCEPTABLE.
- 3. CONSTRUCTION MATERIALS AND/OR OTHER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN THE PATH OF STREAM FLOW
- 4. TEMPORARY EROSION CONTROL DEVICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
- 5. PERMANENT SEEDING SHALL BE USED WHENEVER POSSIBLE, UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG GRADING OR SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY
- 6. THE CONTRACTOR SHALL INSPECT ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN NECESSARY. ADJACENT STREETS SHALL BE KEPT FREE OF SOIL AND DEBRIS.
- 7. SHOULD IT BE NECESSARY TO REMOVE ANY EROSION CONTROL DEVICES FOR CONSTRUCTION REASONS. THE CONTRACTOR SHALL FIRST ORTAIN PERMISSION AND SHALL BEPLACE AND/OR REPAIR THE REMOVED DEVICES THE SAME DAY. THE COST OF REMOVING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 8. ALL OTHER SOIL EROSION AND SEDIMENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE RESIDENT ENGINEER, STEPHENSON COUNTY, FREEPORT-ALBERTUS AIRPORT, IDOT DIVISION OF AERONAUTICS, AND THE IEPA SHALL BE IMPLEMENTED IMMEDIATELY UPON NOTIFICATION OF THE CONTRACTOR
- 9. THE CONTRACTOR SHALL PROVIDE LOCATIONS FOR CONCRETE TRUCK WASHOUT, AS APPROVED BY THE ENGINEER, PRIOR TO ANY CONCRETE POURS, THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY OF WATER. LOCATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. ADDITIONALLY THE CONTRACTOR SHALL PROVIDE ADEQUATE FACILITIES TO WASH OUT PAVING EQUIPMENT AND FINISHING TOOLS, ALL WASTE WATER AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN APPROVED CONCRETE WASHOUT FACILITY.
- MEASURES ARE CONSISTENT BETWEEN ALL PROJECT PHASES AND ALL SUB-CONTRACTORS.
- 11. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY SEDIMENT, CONSTRUCTION EQUIPMENT, OR BY HIS PERSONNEL. THE CONTRACTOR SHALL ASSURE THAT DEBRIS OR ANY CONSTRUCTION MATERIAL IS NOT DISPOSED OF IN THE WETLANDS.
- 12. WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED BY AN APPROVED MEANS.
- SHALL BE DISPOSED OF ON A REGULAR BASIS. SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE DEVICE OR AS RECOMMENDED BY THE MANUFACTURER, WHICHEVER IS LESS.
- 14 ALL EBOSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES ARE OPERATIONAL.
- 15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE TALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER. ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL BECEIVE TEMPORARY EROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND/OR EROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREAS TO BE WORKED BEYOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING
- 16. PERMANENT STABILIZATION SHALL BE COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED



INLET PROTECTION - SILT BASKET

NOTES

- CONTRACTOR SHALL CLEAR DEBRIS PER THE MANUFACTURER'S RECOMMENDATIONS BUT NOT LESS THAN WHEN THE CAPACITY FOR SEDIMENT STORAGE HAS BEEN REDUCED BY HALF.
- FILTER FABRIC SHALL MEET THE MATERIAL REQUIREMENTS OF SPECIFICATION 592, TABLE 1, CLASS 2 OF THE ILLINOIS URBAN MANUAL.

DU094

10. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL

13. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS

(PAVEMENT/TURF)



CONSULTANTS

FINAL

FEBRUARY 28, 2025

RECONSTRUCT POWIS ROAD APRON

DUPAGE AIRPORT Authority

OWNER

DUPAGE AIRPORT WEST CHICAGO, ILLINOIS

MARK DATE DESCRIPTION

AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. DPA-5200 CMT PROJECT NO: 22004901.00 CAD DWG FILE: DESIGNED BY EJR JBO DRAWN BY CHECKED BY: DKP APPROVED BY: DLP

COPYRIGHT

SHEET TITLE

STORM WATER POLLUTION **PREVENTION PLAN NOTES** AND DETAILS

OF

20

_{знеет} 10





Path: Date:

DU094



CONSULTANTS





NEW 2" BITUMINOUS SURFACE COURSE (401)

NEW TWO 2-1/2" LIFTS BITUMINOUS BASE COURSE (403) WITH BITUMINOUS TACK COAT (603) BETWEEN LIFTS

EXISTING 6" CRUSHED AGGREGATE BASE (TO REMAIN)

EXISTING APRON PAVEMENT STRUCTURE:

EXISTING 6" PCC PAVEMENT TO BE REMOVED (501)

EXISTING 5" - 7" BITUMINOUS PAVEMENT TO BE REMOVED (401)

EXISTING 12" SLOTTED DRAIN (TO REMAIN)

NEW 6" CRUSHED AGGREGATE BASE COURSE (209)

NEW 3" BITUMINOUS BASE COURSE (403)

EXISTING 6" CRUSHED AGGREGATE BASE TO BE REMOVED (152)

NEW 6" PERFORATED UNDERDRAIN (750)

NEW AGGREGATE BASE PREPARATION (209)

NEW 4" TOPSOIL PLACEMENT (905), SEEDING (901) AND HEAVY-DUTY HYDRAULIC MULCH (908)

FINAL

FEBRUARY 28, 2025

RECONSTRUCT **POWIS ROAD APRON**

DUPAGE AIRPORT AUTHORITY

OWNER

DUPAGE AIRPORT WEST CHICAGO, ILLINOIS

MARK DATE DESCRIPTION

AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. DPA-5200 CMT PROJECT NO: 22004901.00 CAD DWG FILE:

DESIGNED BY: EJR DRAWN BY: JRO CHECKED BY: DKP

APPROVED BY: DLP COPYRIGHT

SHEET TITLE

TYPICAL SECTIONS - 1

OF

20

SHEET 12



ACK COAT (603) BETWEEN LIFTS	WEST CHICAGO, ILLINOIS
RUSHED AGGREGATE BASE	
ON PAVEMENT STRUCTURE:	
ENT (501) GGREGATE BASE COURSE (209)	
CC PAVEMENT TO BE REMOVED (501)	MARK DATE DESCRIPTION
" BITUMINOUS PAVEMENT TO BE REMOVED (401)	AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. DPA-5200
	CMT PROJECT NO: 22004901.00
UND LINE	CAD DWG FILE:
SLOTTED DRAIN (TO REMAIN)	DESIGNED BY: EJR
CC (TO REMAIN)	DRAWN BY: JRO
AVEMENT (501)	APPROVED BY: DLP
IED AGGREGATE BASE COURSE (209)	COPYRIGHT:
	SHEET TITLE
NOSHED AGGREGATE DASE TO BE REMOVED (152)	TYPICAL SECTIONS - 2
ATE BASE PREPARATION (209)	
DIL PLACEMENT (905), SEEDING (901) JTY HYDRAULIC MULCH (908)	
AR (501)	
501)	SHEET 13 OF 20

MARK DATE DESCRIPTION AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. DPA-5200

DUPAGE AIRPORT WEST CHICAGO, ILLINOIS







CONSULTANTS

DU094



FINAL

FEBRUARY 28, 2025

RECONSTRUCT

POWIS ROAD APRON

DUPAGE AIRPORT



	CONSULTANTS
NEW 15 LF 12" RCP @ 0.47%	
	EINAL
STRUCTURE A1 NEW 4' TYPE A MANHOLE W	
FRAME AND OPEN LID (SEE NOTE 15) NIM = 752 42	FEBRUARY 28, 2025
	RECONSTRUCT POWIS ROAD APRON
CONCLUSION OF EACH DAY. SITE DRAINAGE MAY BE	DuPage Airport
PROXIMATE OVERALL HEIGHT OF THE STRUCTURE. EY ARE LOCATED AS PART OF THE DRAINAGE	AUTHORITY
TIONS.	OWNER
FY THE DEPTH OF EXISTING DOWNSTREAM	
CHES, GUTTERS OR DRAINAGE STRUCTURES SE OF EACH WORKING DAY.	
O THE PROPOSED DRAINAGE SYSTEM SHALL BE	
EMPORARY OUTLETS AND CONNECTIONS FOR ALL E IN ALL STORM WATER WHICH WILL BE RECEIVED BY R RECEIVED FROM THESE TEMPORARY ED WATER MUST BE FILTERED TO THE SATISFACTION Y, BUT WILL BE INCLUDED IN THE COST OF STORM	DUPAGE AIRPORT WEST CHICAGO, ILLINOIS
ATION OF DRAINAGE ITEMS. GRADES OF EXISTING DRAINAGE MAY REQUIRE REVISIONS TO MEET THE . NOT BE PAID FOR SEPARATELY BUT SHALL BE	MARK DATE DESCRIPTION
RUCTURES AFFECTED BY PROJECT LIMIT SHALL BE ES AND STRUCTURES IS CONSIDERED TO BE	AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. DPA-5200
ACCORDANCE WITH THE ILLINOIS STANDARD	CMT PROJECT NO: 22004901.00 CAD DWG FILE: 2200490100 - DPA - GRADING PLAN,DWG DESIGNED BY: ABM
FURNISH A NEW FRAME AND LID, SAME OR EQUAL, AT ISTRUCTED WITH NEW FRAMES AND GRATES.	DRAWN BY: JRO CHECKED BY: DKP APPROVED BY: DLP
NFIRMATION OF CURRENT UTILITY LOCATIONS AND OR IMMEDIATELY ADJACENT TO THE PROJECT 3Y THE CONTRACTOR.	COPYRIGHT:
INSTALLATION OF UNDERGROUND FACILITIES. IN 2 FEET OF THE PAVEMENT, SIDEWALK OR CURB.	
NTS TO REMAIN THAT ARE DAMAGED AS A RESULT OF	
ITS.	14 00
	SHEET 14 OF 20



01-00_2025 2:

+	- FINAL
	FEBRUARY 28, 2025 RECONSTRUCT POWIS ROAD APRON
NEW SEALANT AT HMA/PCC JOINT (TYP.) (SEE DETAIL, COST INCIDENTAL)	DUPAGE AIRPORT AUTHORITY
EXISTING PCC APRON (TO REMAIN)	DUPAGE AIRPORT WEST CHICAGO, ILLINOIS
	JOINTING PLAN



DU094

ETAILS		TIE BAR DETAILS		
	SPACING	BAR SIZE	LENGTH	SPACING
	12"	#4	20"	36"

CONSULTANTS

FINAL

FEBRUARY 28, 2025

RECONSTRUCT **POWIS ROAD APRON**

DUPAGE AIRPORT Authority

OWNER

DUPAGE AIRPORT WEST CHICAGO, ILLINOIS

IARK DATE DESCRIPTION

AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. DPA-5200 CMT PROJECT NO: 22004901.00 CAD DWG FILE: DESIGNED BY: FJB

DRAWN BY:	JRO	
CHECKED BY:	DKP	
APPROVED BY:	DLP	
CORVEICHT		

JOINTING DETAILS

_{знеет} 16

20 OF



Path: Date:





- UNCLASSIFIED EXCAVATION REQUIRED TO INSTALL SIDEWALK SECTIONS AS SHOWN ON THE PLAN SHALL BE CONSIDERED INCIDENTAL TO AR501605 5" PCC SIDEWALK.
- 2. MAXIMUM CROSS SLOPE IS 2% MEASURED PERPENDICULAR TO THE DIRECTION OF PEDESTRIAN TRAVEL.







NOT TO SCALE UNDERDRAIN CONNECTIONS AND FITTINGS, TEES AND ELBOWS USED FOR CONNECTIONS TO EXISTING STRUCTURES AND STORM SEWERS, SHALL BE CONSIDERED INCIDENTAL TO THE PROPOSED UNDERDRAIN.

STORM SEWER/UNDERDRAIN NOTES

- NOTED
- COST OF THE PIPE.







SECTION

12"

CORE ASPHALT FULL DEPTH

ä

PLAN

MOORING EYE INSTALLATION DETAIL FOR HMA PAVEMENT	
NOT TO SCALE	

PLAN PAVEMENT REMOVAL EXISTING SUBGRADE -EXISTING TIE DOWN TO BE REMOVED AND BACKFILLED WITH CLSM MATERIAL

TIE DOWN REMOVAL DETAIL



NOTES:

- THE VOID LEFT BY THE REMOVAL SHALL BE BACKFILLED TO THE BOTTOM OF THE NEW PCC/HMA PAVEMENT WITH CLSM MATERIAL 1. (COST INCIDENTAL)
- SURROUNDING AGGREGATE BASE DISTURBED SHALL BE REMOVED 2 AND REPLACED WITH 6 INCHES OF CRUSHED AGGREGATE BASE. REMOVAL OF THE EXISTING AGGREGATE BASE SHALL BE INCIDENTAL TO 6 INCHES CRUSHED AGGREGATE BASE PAY ITEM





NOT TO SCALE

NOTES

MAXIMUM TRENCH WIDT

3'-9"

4'-9"

5'-7"

7'-1"

10'-0"

INSIDE DIAM OF STORM S (INCHE

6

8

18

27

36

42

54 8'-3"

72

- MOORING CASTINGS SHALL BE NEENAH SEMI-STEEL AIRPORT MOORING EYE CATALOG NO. R3490 OR APPROVED EQUIVALENT.
- 2. ANCHOR RODS TO BE NO. 3 DEFORMED REINFORCING STEEL 15" LONG AND SHALL BE BENT DOWNWARD AT 45°.

PROPOSED BITUMINOUS SURFACE COURSE PROPOSED BITUMINOUS BASE COURSE PROPOSED MOORING EYE



DU094

1. CONTRACTOR SHALL FIELD VERIFY EXISTING STORM SEWER/UNDERDRAIN INVERTS BEFORE INSTALLING PROPOSED PIPE, CONNECTIONS AND ORDERING MATERIALS

2. ALL UNDERDRAIN CONNECTIONS, CORING INTO STRUCTURES, CAPS, TEES, BENDS, STORM SEWER ETC. SHALL BE CONSIDERED INCLUDED IN THE COST OF THE

3. UNDERDRAIN SLOPES FOLLOW EDGE OF PAVEMENT SLOPE UNLESS OTHERWISE

4. UNDERDRAIN CONFLICTS WITH EXISTING CONDITIONS SHALL BE RESOLVED AND COST SHALL BE INCIDENTAL TO UNDERDRAIN.

5. CORING OF DRAINAGE STRUCTURE AND REMOVAL OF EXISTING STORM SEWER MANHOLE/INLET CONCRETE BENCHES TO FACILITATE CONNECTIONS OF PROPOSED STORM SEWER AND UNDERDRAIN PIPE SHALL BE CONSIDERED INCLUDED IN THE

NEW PAVEMENT

UNDERDRAIN DETAIL - PAVED AREAS NOT TO SCALE

NOTES

1. THE 6" UNDERDRAIN SHALL BE INSTALLED AFTER THE SUBGRADE IS COMPACTED.

NCMT

CONSULTANTS

FINAL

FEBRUARY 28, 2025

RECONSTRUCT **POWIS ROAD APRON**

DUPAGE AIRPORT Authority

OWNER

DUPAGE AIRPORT WEST CHICAGO, ILLINOIS

MARK DATE DESCRIPTION

AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. DPA-5200 CMT PROJECT NO: 22004901.00 CAD DWG FILE: DESIGNED BY: EJR DRAWN BY: JRO CHECKED BY: DKP APPROVED BY: DLP COPYRIGHT

SHEET TITLE

SHEET 18

MISCELLANEOUS DETAILS - 1

20

OF



K:\Dupa Fridav. Path: Date:

DU094

- REMOVE MANHOLE FRAME AND ADD OR REMOVE GRADE RINGS AS REQUIRED TO MEET FINISH GRADE. GRADE RINGS SHALL BE SQUARE OR ROUND AS REQUIRED. FOR SQUARE RINGS REMOVE EXISTING ANCHOR RODS AND INSTALL NEW ANCHOR RODS (DRILL AND GROUT) TO REBOLT FRAME TO STRUCTURE -1/2"±1/4" 18 AX EXISTING MANHOLE CONE EXISTING CONCRETE BARREL SECTION

FLAT SLAB TOP REINFORCEMENT

WWR (each direction)		Rebar		
As (min.)	Spacing (max.)	As (min.)	Spacing (max.)	Bar Size
.62 sq. in./ft. 2 sq. mm/m)	6 (150)	See plan view for spacing and this	rebar orientation and table for bar size	#5 (#16)
r of WWR per	mitted to avoid co	ngestion.		

WALL REINFORCEMENT

	Orientation	WWR or Rebar		
Location		As (min,)	Spacing (max.)	
Riser	Circumferential	0.12 sq. in./ft. (254 sq. mm/m)	6 (150)	
	Vertical	0.045 sq. in./ft. (95 sq. mm/m)	8 (200)	
2 0	Circumferential	0.12 sq. in./ft. (254 sq. mm/m)	6 (150)	
sarre	Vertical	0.16 sq. in./ft. (339 sq. mm/m)	4 (100)	

BASE SLAB REINFORCEMENT

ocation	Total Holeba	WWR or Rebar (each direction)				
	rotal Height	As (min.)	Spacing (max.)			
Top	≤ 20 ft, (6,10 m)	0.24 sq. in./ft. (508 sq. mm/m)	10 (250)			
Mat	> 20 ft. (6,10 m)	0.24 sq. in./ft. (508 sq. mm/m)	10 (250)			

PRECAST MANHOLE TYPE A 4' (1.22 m) DIAMETER

STANDARD 602401-07

NCMT

CONSULTANTS

FINAL

FEBRUARY 28, 2025

RECONSTRUCT **POWIS ROAD APRON**

DUPAGE AIRPORT AUTHORITY

OWNER

DUPAGE AIRPORT WEST CHICAGO, ILLINOIS

MARK DATE DESCRIPTION AIP PROJECT NO. 3-17-SBGP-TBD

IL PROJECT NO. DPA-5200 CMT PROJECT NO: 22004901.00 CAD DWG FILE: DESIGNED BY: EJR DRAWN BY: JRO CHECKED BY: DKP APPROVED BY: DLP COPYRIGHT

SHEET TITLE

MISCELLANEOUS DETAILS - 2

SHEET 19

20

OF



Geo Servic Geotechnical Environment 805 kunnetti Cour Naperville, Bibyt 16807 355-bas	Cal Engineering Sard 204 20585						sc	DIL BORIN	G LOG	GEO Job No. <u>24</u> Page <u>1</u> Date <u>1/2</u>	006 of _
PROJECT Du	Page Airport										_
LOCATION	est Chicago, I	-									_
COUNTY Cod	ok DF	RILLING	MET	HOD			Hol	ow Stem Auger	HAMMER TYPE	CME Automat	ic
CLIENTC BORING NO Northing Easting Ground Surface Elev	B-1 1911600 1009827 4. 754.2	ft	D E P T H	B L O W S (/6")	U C S Qu (tsf)	M O I S T (%)	Docy Duizs-++ (pcf)	Surface Water Elev. Stream Bed Elev. Groundwater Elev.: First Encounter Upon Completion After - Hrs.	<u></u>	¥	
5" ASPHALT, 6.0" CR STONE	USHED	750.0	-								
SILTY CLAY-brown to CL-ML)	gray-stiff	/53.2	1 1	3 4 5	2.00 B	25					
SILTY CLAY Loam-gr stiff (CL-ML)	ay-medium	750.7	-5	1 2 2	1.00 B	18					
becoming gray @ -6.0	r		-	4 4 5	0.50 B	19					
SANDY SILT-gray-me (ML)	dium dense	745.7	1	3 7 8		21					
End Of Boring @ -10. ackfilled with cuttings avment patched.	0'. Boring : and		-10								

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206), GP-Geoprobe Hand Auger BBS, from 137 (Rev. 8-99)



COUNTY Cook DR	ILLING MI	ETHO			Hol	ow Stem Auger	HAMMER TYPE	CME Automat
CLIENT CMT 30RING NO. B-2 Northing 1911609 Easting 1009721 Ground Surface Elev. 453.4	D E P T H ft (ff	B L O W S	U C S Qu (tsf)	M O I S T (%)	per ouzw++ fo	Surface Water Elev. Stream Bed Elev. Groundwater Elev.: First Encounter Upon Completion After - Hrs.	<u>n/a</u> ft <u>n/a</u> ft <u>448.4</u> ft <u>n/a</u> ft ft	
.0" ASPHALT, 6.0" CRUSHED		-				-		
ANDY CLAY Loam-brown & ray-stiff (CL)	452.4	3 5 6	1.50 B	19				
		3	1.50	12				
	¥	5 2	В					
ILTY CLAY Loam-grav-stiff	447.4	2						
CL-ML)	-	4	2.75 B	16				
AND-gray-medium dense	444.9	3						
	443.4	6		17				
ind of Boring @ -10.0'. Boring ackfilled with cuttings and avement patched.	. . .	-						
	- F L.	15						
	-							
	-							

The Unconfined Compressive Strength (UCS) Failure Mode is indicate The SPT (N value) is the sum of the last two blow values in each sam

805 N	Amherat Court S operville, Binois ((cao) 355 263	uite 204 50565 SUN
Project: Du	Page Airport	· Reconstruct 3N060 Powie Pood
Location:We	est Chicago,	Illinois
County: <u>Co</u>	pok	
Client: <u>CN</u>	T	
CORE T NO.	HICKNESS (in.)	
		Northing: 1911559 Easting: 100
C-01	6.0 6.0+	CONCRETE-well consolidated CRUSHED STONE-brown
		Northing: 1911700 Easting: 100
C-02	2.5 3.0 5.5+	ASPHALT-well consolidated, fine to r ASPHALT-well consolidated, fine to r CRUSHED STONE-brown
		Northing: 1911873 Easting: 100
C-03	2.5 4.25 6.75+	ASPHALT-well consolidated, fine to r ASPHALT-well consolidated, fine to r CRUSHED STONE-brown

Geotechnical Enviro Boo Ambai Napervil (69)	TVICES, Inc. amplintal & Cult Engineering 16 Court: Surge 204 16, Illuoris 50505 07555-5888						SC	DIL BORIN	GLOG	Page <u>1</u> of Date <u>1/22/2</u>
PROJECT	DuPage Airport									
LOCATION	West Chicago, II									
COUNTY	Cook DR	ILLING	MET	THOE			Hol	ow Stem Auger	HAMMER TYPE	CME Automatic
CLIENT	CMT	_	DE	BL	UCC	MO	DRY	Surface Water Elev. Stream Bed Elev.	n/aft n/aft	
BORING NO. Northing Easting Ground Surfac	B-3 1911792 1009766 ce Elev. 752.8	ft	F T H	W S (/6")	Qu (tsf)	1 S T (%)	y (pcf)	Groundwater Elev.: First Encounter Upon Completion After - Hrs.	745.8_ft.▼ ft ft	
4.0" ASPHALT, STONE	6.0" CRUSHED	754.0	-							
CLAY LOAM-br (CL-ML)	rown & gray- stiff	/51.8	-	11 16 3	2.00 B	27				
CLAY with GRA	VEL-grav-verv soft	749.8	_							
		-	_	3	0.25	11				
		746.8	-5		в					
SAND with GR/ medium dense	AVEL-gray-loose to	3	y –	4	-	16				
				3						
	0.40.0LD	742.8	-10	7		14				
backfilled with c pavement patch	g -10.0°. Bonng uttings and 1.		-							
			-							
			-							
			-15							
			-							
		3	-							
		05	-							

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (15-burge, 5-5780), 7-7690, 5P-Geopolae Hand Auger The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206), GP-Geopolae Hand Auger BBS, from 137 (Rev. 8-99)

LEGEND



€,

- EXISTING HANGAR
- PROPOSED SOIL BORING LOCATION
- PROPOSED CORE LOCATION

THE GEOTECHNICAL INFORMATION (OR ANY PORTIONS THEREOF) ARE PROVIDED ONLY AS AVAILABLE INFORMATION. THE CONTRACTOR MAY DRAW THEIR OWN CONCLUSIONS FROM THE DATA SHOWN. THE SOILS INFORMATION IS NOT REPRESENTATIVE OF ALL SOIL WHICH MIGHT BE ENCOUNTERED WITHIN THE LIMITS OF THE PROJECT. THE CONTRACTOR SHALL BY THEIR OWN MEANS, SATISFY THEMSELVES AS TO THE EXISTING SITE AND GEOTECHNICAL CONDITIONS FOR DETERMINING COST, MEANS, METHODS, TECHNIQUES AND SEQUENCES OF CONSTRUCTION.

BORE/CORE	STATION/OFFSET
C-1	STA. 1+76.80, 67.41' RT. APRON BASELINE
C-2	STA. 0+42.53, 68.34' LT. APRON BASELINE
C-3	STA. 0+47.28, 238.90' LT. APRON BASELINE
B-1	STA. 1+52.89, 26.25' RT. APRON BASELINE
B-2	STA. 0+47.07, 17.16' RT. APRON BASELINE
B-3	STA. 0+90.21, 157.43' LT. APRON BASELINE

DU094



of **20**

SHEET 20

CONSULTANTS

GEO Job No. 24006

SOIL BORING LOG

Page <u>1</u> of <u>1</u>

Date _____1/22/24___

FINAL
FEBRUARY 28, 2025
RECONSTRUCT POWIS ROAD APRON
DuPage Airport Authority
OWNER
DUPAGE AIRPORT WEST CHICAGO, ILLINOIS
MARK DATE DESCRIPTION AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. 22004901.00 CMT PROJECT NO: 22004901.00 CAD DWG FILE: DESIGNED BY: EJR DRAWN BY: JRO CHECKED BY: DKP APPROVED BY: DLP COPYRIGHT: SHEET TITLE GEOTECHNICAL INFORMATION