**APRIL 25, 2025 LETTING ITEM 03A** 

# **CONSTRUCTION PLANS FOR SPARTA COMMUNITY AIRPORT**

# **SPARTA, ILLINOIS**

SUMMARY OF QUANTITIES - BASE BID			
ITEM NO.	ITEM DESCRIPTION	UNITS	QUANTITY
AR150520	MOBILIZATION	L SUM	1
AR620520	PAVEMENT MARKING- WATERBORNE	SQ FT	26,500
AR620525	PAVEMENT MARKING- BLACK BORDER	SQ FT	7,000

**100% SUBMITTAL IL. PROJ. NO. SAR-5184** SBG PROJ. NO: 3-17-SBGP-## **REMARK RUNWAY PAVEMENT** 

02/28/2025



COMMON GROUND ALLIANCE www.call811.com or Phone: 811

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES, PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INFERRENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL MMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAD FOR BY ICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR TOR AT NO ADDITIONAL COST TO TH

CALL 911 IN THE EVENT IN WHICH DAMAGE RESULTS IN THE RELEASE OF NATURAL GAS

**DESIGN INFORMATION** 


GEOMETRIC CRITERIA AIRPLANE DESIGN GROUP II TAXIWAY DESIGN GROUP II


PAVEMENT DESIGN CRITERIA AIRCRAFT SINGLE WHEEL GEAR DEPARTURE WEIGHT = 12,500 LBS 100 ANNUAL DEPARTURES

MAXIMUM EQUIPMENT HEIGHT = 75' **GROUND FREQUENCY 123.075** 

SPARTA COMMUNITY AIRPORT

TOWNSHIP: 4 SOUTH RANGE: 5 WEST SECTION: 31 COUNTY: RANDOLPH





LOCATION MAP

SITE PLAN


# **TOTAL SHEETS:8**

SP026

Sheet List Table			
Sheet No.	Sheet Index	Sheet Title	
1	GI001	COVER SHEET	
2	GI002	SITE PLAN	
3	GC101	CONSTRUICTION ACTIVITY NOTES	
4	GC102	CONSTRUICTION ACTIVITY DETAILS	
5	CM101	MARKING PLAN 1	
6	CM102	MARKING PLAN 2	
7	CM501	PAVEMENT MARKING DETAILS 1	
8	CM502	PAVEMENT MARKING DETAILS 2	







#### GENERAL

- THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE REQUIREMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP) FOR THIS PROJECT, FAA AC 150/5370-2G, AND ALL AIRPORT SAFETY AND SECURITY REQUIREMENTS
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR 2. SHALL SUBMIT TO THE AIRPORT FOR APPROVAL A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2G. NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT HAS APPROVED THE SPCD
- THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER PERSONNEL AND MEETING OSHA REQUIREMENTS.
- A MINIMUM OF 10 DAYS PRIOR TO THE PRECONSTRUCTION MEETING THE CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL SUPPLIERS.
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL SIGN THE STORM WATER POLLUTION PREVENTION PROGRAM (SWPPP) CERTIFICATION STATEMENT
- ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT UNLESS A SPECIFIC PAY ITEM IS PROVIDED.

## 1. COORDINATION

- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A PRECONSTRUCTION CONFERENCE WITH THE AIRPORT, ENGINEER, AND ILLINOIS DIVISION OF AERONAUTICS (IDA). THE COST OF PREPARING FOR AND ATTENDING THE PRECONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT
- ON OR BEFORE THE PRECONSTRUCTION CONFERENCE. THE CONTRACTOR SHALL SUBMIT A PROPOSED SCHEDULE FOR THE PROJECT. THE SCHEDULE SHALL INCLUDE A START AND COMPLETION DATE FOR EACH ITEM OF WORK. THE SCHEDULE SHALL BE LIPDATED ON AS NEEDED BASIS ALL COSTS ASSOCIATED WITH THE SCHEDULE SHALL BE INCIDENTAL TO THE CONTRACT
- DUBING CONSTRUCTION THE CONTRACTOR SHALL ATTEND A З. COORDINATION MEETINGS WITH THE AIRPORT STAFF AND RESIDENT ENGINEER. ALL COSTS ASSOCIATED WITH ATTENDING THE WEEKLY MEETING SHALL BE INCIDENTAL TO THE CONTRACT.

## 2. PHASING

TOTAL CONTRACT TIME SHALL BE 46 CALENDAR DAYS.

- WORK ON THIS PROJECT LOCATED WITHIN 75' OF THE RUNWAY 18-36 CENTERLINE WILL SEVERLY LIMIT OPERATIONS AT THE AIRPORT. PRIOR TO STARTING WORK THE CONTRACTOR SHALL HAVE ON HAND ALL MATERIALS NECESSARY TO COMPLETE ALL WORK LOCATED WITHIN 75' OF THE RUNWAY 18-36 CENTERLINE
- PHASE 1 MAY BE INITIATED BY THE CONTRACTOR WITH THE З. APPROVAL OF THE AIRPORT MANAGER IT CONSIST OF ALL WORK NOT WITHIN 75' OF THE BUNWAY 18-36 CENTERLINE. PHASE 1A IS THE WORK THAT REQUIRES THE PRIMARY RUNWAY TO BE CLOSED. THE CONTRACTOR SHALL EXPEDITE ALL WORK WITHIN THE PHASE 1A WORK AREAS TO MINIMIZE THE CLOSURE TIME OF THE RUNWAY. PHASE 1A WILL BE SCHEDULED BY THE CONTRACTOR (APPROVED BY THE AIRPORT MANAGER) DURING THE PHASE 1 CONSTRUCTION
- PHASING SHALL BE AS NOTED BELOW AND AS SHOWN ON THE 4. CONSTRUCTION ACTIVITY PLAN SHEET.

# PHASE 1 & 2 NOTES

- THIS WORK SHALL CONSIST OF ALL WORK ON THE PROJECT NOT WITHIN 75' OF FITHER SIDE OF THE BUNWAY 18-36 CENTERLINE. DURING THIS PHASE RUNWAY 18-36 WILL REMAIN OPEN. NO PERSONNEL OR EQUIPMENT WILL BE ALLOWED WITHIN 75' OF THE RUNWAY CENTERLINE
- WORK IN THIS PHASE SHALL CONSIST OF THE 2. CONSTRUCTION OF THE EMBANKMENT, STORM DRAINAGE, SUBGRADE AGGREGATE BASE BITUMINOUS PAVEMENT AND LIGHTING IMPROVEMENTS ON THE TAXIWAY.

#### PHASE 1A & 2A NOTES

- THIS WORK SHALL CONSIST OF THE WORK LOCATED WITHIN 75' OF THE RUNWAY CENTERLINE INCLUDING BUT NOT LIMITED TO THE CONSTRUCTION OF PAVEMENT REMOVAL, CONSTRUCTING EMBANKMENT, CABLING AND LIGHTING IMPROVEMENTS
- 10. 2. THE CONTRACTOR SHALL BE ALLOWED TO CLOSE THE RUNWAY TO COMPLETE THE WORK. THE RUNWAY SHALL BE CLEANED AND REOPENED AT THE END OF EACH PHASE. THE SEQUENCE OF CLOSING AND OPENING THE RUNWAY SHALL BE GOVERNED BY THE REQUIREMENTS SET FORTH IN FAA ADVISORY CIRCULAR 5370-2 CURRENT VERSION; IN GENERAL THE SEQUENCE WILL BE:
- 21 COORDINATE CLOSURE WITH THE AIRPORT MANAGER NOTIFY AIR TRAFFIC OF RUNWAY CLOSURE
- 2.2.
- 2.3. DISABLE VISUAL AIDS
- 2.4. PLACE CLOSURE MARKERS
- KEEP EQUIPMENT CLEAR OF THE RUNWAY PROPER AND 2.5. MONITOR UNICOM

- 2.6 COMPLETE WORK
- 2.7. CLEAN PAVEMENTS
- 2.8. COORDINATE OPENING WITH AIRPORT MANAGER 2.9. REMOVE RUNWAY CLOSURE MARKERS
- 2.10. NOTIFY AIR TRAFFIC
- THE CONTRACTOR SHALL BE GIVEN 14 CONSECUTIVE CALENDAR З. DAYS TO COMPLETE THE WORK IN EACH PHASE, STARTING ON A MONDAY SELECTED BY THE CONTRACTOR AND APPROVED BY THE AIRPORT MANAGER TO COMPLETE THE WORK.
- LIQUIDATED DAMAGES OF \$500 PER DAY WILL BE CHARGED FOR ANY DAYS BEYOND THE SPECIFIED AMOUNT THAT THE RUNWAY MUST BE CLOSED
- THE CONTRACTOR MAY CONTINUE TO WORK IN PHASE 1 AREA DURING PHASE 1A AND PHASE 2 DURING PHASE 2A.
- ALL BUNWAYS TAXIWAYS AND APBONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE PHASING PLAN.
- 2. WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND AIRCRAFT OPERATIONS AND SAFETY, AIRCRAFT OPERATIONS AND SAFETY SHALL TAKE PRECEDENCE AND SHALL GOVERN. FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT.
- ALL CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO З. ONCOMING AIRCRAFT AT ALL TIMES
- THE AIRPORT WILL BE HOSTING EVENTS THROUGHOUT THE 4 SUMMER AND RESERVES THE RIGHT TO HALT CONSTRUCTION UNTIL FURTHER NOTICE. KNOWN EVENTS AT THIS TIME ARE: JULY 9-16, 2019
- 4. PROTECTION OF NAVIGATION AIDS (NAVAIDS)
- THE CONTRACTOR SHALL REMAIN CLEAR OF THE RUNWAY 18 END 1. REILS AFTER INSTALLATION, PAPI, WINDCONE AND OTHER NAVAIDS FACILITIES AT ALL TIMES.
- 5. CONTRACTOR ACCESS
- CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS 1. SHOWN ON THE SITE PLAN AND CONSTRUCTION ACTIVITY PLAN SHEETS
- THE CONTRACTOR IS TO ACCESS THE SITE USING THE ENTRANCE 2. SHOWN
- ALL CONTRACTOR EMPLOYEES WHO ARE DESIGNATED AS З. DRIVERS FOR THE CONTRACTOR DRIVERS OF TRUCKS CONTAINING MATERIAL DELIVERIES (AGGREGATE, CONCRETE ETC.) SHALL BE REQUIRED TO SUBMIT THEIR NAME, DRIVER'S LICENSE NUMBER, TRUCK LICENSE PLATE NUMBER AND NAME OF TRUCKING COMPANY TO THE PRIME CONTRACTOR PRIOR TO ENTERING THE JOBSITE
- THE CONTRACTORS STORAGE AND STAGING AREA WILL BE AS 4 SHOWN IN THE SITE PLAN
- 5 THE CONTRACTOR SHALL KEEP A BECORD OF THE NAMES OF ALL EMPLOYEES ENTERING THE JOB SITE ON A DAILY BASIS. A RECORD OF EACH SUBCONTRACTOR ENTERING THE JOB SITE SHALL ALSO BE KEPT BY THE CONTRACTOR
- WHEN THE CONTRACTOR IS NOT WORKING, EQUIPMENT SHALL BE 6. STORED AT THE STAGING AREA.
- THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT 7. AND MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE.
- THE CONTRACTOR SHALL THOROUGHLY CLEAN ALL CONSTRUCTION AREAS AND HAUL ROUTES WHICH WILL BE OPENED TO AIR TRAFFIC TO THE SATISFACTION OF AIRPORT OPERATIONS OR THE RESIDENT ENGINEER. A POWER BROOM AND OPERATOR SHALL BE ON SITE AT ALL TIMES WHEN ACTIVE PAVEMENTS ARE UTILIZED FOR CONSTRUCTION TRAFFIC
- ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS UTILIZED BY THE CONTRACTOR FOR HAUL ROADS OR STORAGE AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR BETTER THAN THEY WERE PRIOR TO BEGINNING CONSTRUCTION, NO ADDITIONAL COMPENSATION WILL BE MADE TO THE CONTRACTOR FOR THIS WORK

ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY THE CONTRACTOR

THE CONTRACTOR SHALL NOTIFY THE AIRPORT IF CONSTRUCTION ACTIVITY WILL REQUIRE THE BLOCKAGE OF EMERGENCY ACCESS TO THE AIRPORT.

#### 6. WILDLIFE MANAGEMENT

- THE CONTRACTOR SHALL NOTIFY AIRPORT OPERATIONS OR THE ENGINEER IF ANY WILDLIEF IS SEEN ENTERING THE AIRPORT
- 2. CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE CONTRACTOR IS NOT WORKING
- THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING 3. FOOD SCRAPS IN APPROVED CONTRACTOR PROVIDED CONTAINERS.
- 7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT
- THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS 1. (FOD) SEEN ON THE AIRFIELD PAVEMENTS.
- THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES 2. PRIOR TO DRIVING ON AIRFIELD PAVEMENTS

## 3. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY 8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT

THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE

#### 9. NOTIFICATION OF CONSTRUCTION ACTIVITIES

- THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT 1 PERSON AND PHONE NUMBER.
- THE CONTRACTOR SHALL GIVE A MINIMUM OF 72 HOURS NOTICE TO AIRPORT OPERATIONS PRIOR TO CLOSING ANY PAVEMENTS SO THAT PROPER NOTICE TO AIRMEN (NOTAMS) MAY BE ISSUED BY THE
- FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT З. GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY. NO EQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.
- 4. IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CALL 911.
- CONTACTS FOR THIS PROJECT ARE AS LISTED BELOW. 5.

#### AIRPORT OPERATOR SCOTT MARQUARDT - AIRPORT MANAGER (618) 443-2002

ENGINEER		
CHRIS GROTH PROJECT ENGINEER	(217) 787-8050	4
CMT - RESIDENT ENGINEER	(217) 787-8050	ч.

#### 10. INSPECTION REQUIREMENTS

- THE CONTRACTOR SHALL INSPECT THE JOBSITE DAILY TO ENSURE 1. COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF FAA AC 150/5370-2G MAY BE USED TO AID IN THE INSPECTIONS.
- THE CONTRACTOR SHALL ATTEND A FINAL INSPECTION OF EACH 2. PHASE WORK AREA PRIOR TO OPENING THE AREA TO AIRPORT OPERATIONS

#### **11. UNDERGROUND UTILITIES**

- IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN 1 FIELD INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE UNDERGROUND LITH ITIES AT CRITICAL POINTS. THE LOCATION OF LINDERGROUND LITILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION.
- BEFORE INITIATING ANY DIGGING, DRILLING OR EXCAVATING ON 2. THE AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL J.U.L.I.E. AND CONTACT THE LOCAL FAA OFFICE TO ARRANGE FOR UTILITY LOCATES. SEE SECTION 50-17 OF THE SPECIAL PROVISIONS FOR UTILITY CONTACT INFORMATION.

#### 12. PENALTIES

1. NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT RULES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS ALLOWED BY LAW

#### 13. SPECIAL CONDITIONS

ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE 1 CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL INFORMATION.

### 14. RUNWAY AND TAXIWAY VISUAL AIDS

- PROJECT WILL REQUIRE THE CLOSURE OF RUNWAY 18-36 FOR A LIMITED DURATION DURING PHASE 1A & 1B. THE CONTRACTOR SHALL USE MARKING, LIGHTING AND SIGNS THAT FOLLOW THE **BEQUIREMENTS OF FAA AC 150/5370-2G**
- BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON 2. THE CONSTRUCTION ACTIVITY PLAN SHEET

# EQUIPMENT HEIGHT IS 25' ENGINEER

LIGHTS AND FLAG PLACEMENT.

# 17. PROTECTION

- 2. BEQUESTED CLOSURE TIME

# 18. OTHER LIMITATIONS ON CONSTRUCTION VEHICLES, PERSONNEL AND EQUIPMENT.

- 2. SPECIFIED
  - З. WEEKS TO COMPLETE.
  - SPECIFIED IN THE CONTRACT DOCUMENTS.

- 16. HAZARD MARKING AND LIGHTING
- 1 STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT
- 2.
- 3.

# 15. MARKING AND SIGNS FOR ACCESS ROUTES

BARRICADES AND SIGNS SHALL BE USED ALONG THE CONTRACTOR'S ACCESS ROUTE AS DETAILED ON THE CONSTRUCTION ACTIVITY PLAN SHEETS.

THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY

ALL CONSTRUCTION FOUIPMENT SHALL BE FLAGGED AND/OB LIGHTED IN ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2G AND 150/5210-5D AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY. THE MAXIMUM

BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE CONSTRUCTION ACTIVITY PLAN SHEET OR AS DIRECTED BY THE RESIDENT

THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED

ALL WORK BEQUIRED INSIDE OF THE BUNWAY 18-36 SAFETY AREAS WHICH EXTENDS 75' FROM THE BUNWAY CENTERI INF. WILL BEQUIRE THE BUNWAY TO BE CLOSED. THE CONTRACTOR SHALL COORDINATE WITH THE AIRPORT A MINIMUM OF 72 HOURS PRIOR TO THE REQUESTED CLOSURE TIME

ALL WORK REQUIRED ON AN ACTIVE TAXIWAY OR INSIDE OF AN AN ACTIVE TAXIWAY SAFETY AREA, WHICH EXTENDS 40' FROM THE TAXIWAY CENTERLINE, WILL REQUIRE THE TAXIWAY TO BE CLOSED. THE CONTRACTOR SHALL COORDINATE WITH THE AIRPORT A MINIMUM OF 72 HOURS PRIOR TO THE

IF. DURING CONSTRUCTION. AN EMERGENCY IS DECLARED BY THE AIRPORT. THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL

BROKEN CONCRETE, BROKEN ASPHALT, AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS OTHERWISE

THE CONTRACTOR WILL BE RESPONSIBLE FOR COORDINATION OF THE AIRSPACE FOR THE CONSTRUCTION EQUIPMENT THAT IS TALLER THAN THAT SPECIFIED ON THE PLANS WITH THE FAA. THIS PROCESS MAY TAKE UP TO 12

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEGGER TESTING ALL EXISTING CIRCUITS PRIOR TO CONSTRUCTION AND FOLLOWING CONSTRUCTION AS



ONSULTANTS

100% SUBMITTAL 02/28/2025

**REMARK RUNWAY PAVEMENT** 

OWNER



# SPARTA COMMUNITY AIRPORT SPARTA, ILLINOIS

MARK	DATE	DESCRIPTION	
AIP P	roj. No	. 3-17-SPGP-XXX	
IL. PROJ. NO. SAR-5184		CONTRACT: SP026	


CMT PROJECT NO:	240071-98-00
CAD DWG FILE:	SAR5184-24007198-GC100.DWG
DESIGNED BY:	CBG
DRAWN BY:	DPA
CHECKED BY:	CBG
APPROVED BY:	CBG
CORVEIGHT	


3



# GC101 OF

8





ath: K:\SpartaAp/24007198-00\_Fwy1836Marking\Draw\Sheets\SAR5184-24007198-CM100.dv Jane: Mondav: March 17: 2025.8-343-56.0.AM

