

SUMMARY OF QUANTITIES		UNIT	CONSTRUCTION CODE					
CODE NO.	ITEM DESCRIPTION		URBAN 90% FED. 10% STATE TOTAL	0003	0010	0021	0031	0040
				RDWY	BRIDGE	SIGNALS LIGHTING	LNDSCP	RET. WALL
50300300	PROTECTIVE COAT	SQ YD	5,641		5,369			272
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1			
50500505	STUD SHEAR CONNECTORS	EACH	22,500		22,500			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	658,060	⚠	610,570			47,490
50800515	BAR SPLICERS	EACH	2,834		2,834			
50800530	MECHANICAL SPLICERS	EACH	504		504			
50901730	BRIDGE FENCE RAILING	FOOT	645		645			
51100100	SLOPE WALL, 4"	SQ YD	562		562			
51201600	FURNISHING STEEL PILES, HP 12X53	FOOT	7,308		7,308			
51202305	DRIVING PILES	FOOT	7,308		7,308			
51203600	TEST PILE STEEL, HP 12X53	EACH	4		4			
51500100	NAME PLATES	EACH	1		1			

• SPECIALTY ITEM

 PATRICK ENGINEERING	PATRICK ENGINEERING INC. 4970 VARSITY DRIVE USLE, IL 60532 patrickengineering.com	USER NAME = skoeppe(Rdw.Lislo)	DESIGNED - CPK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		PLOT CONFIG = POFI0reg.Smal1.plt	DRAWN - MJP	REVISED -						2746	1616B	COOK	404	9
		PLOT SCALE = 1:100	CHECKED - JAH	REVISED -		60J14								
		PLOT DATE = 2/18/2013 4:37:29 PM	DATE - 2/18/2013	REVISED -		SCALE: NA	SHEET	S00-06 OF 36	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
0:\1007\21850.006\CumberlandDrive\Drawings\CADD Sheets\0160J14-S00.01.dgn														

Q:\100T\21850_006_CumberlandAve\Drawings\CADD Sheets\0160J14-S00.01.dgn

Rev. 4-11-13