

## NOTES:

- 1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
- 2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

## SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

- A. ABBAS 04-27-98 - R. BORO 01-01-07 - R. BORO 09-04-07

K. ENG 10-27-08

## SEQUENCE OF CONSTRUCTION (MILLING FIRST)

- 1. MILL HMA FIRST IF THERE IS AT LEAST 41/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
- 2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = bauerdl	DESIGNED - R. SHAH		
c:\projects\diststa22x34\bd22.dgn		DRAWN -		
	PLOT SCALE = 50.000 ' / IN.	CHECKED -		
	PLOT DATE = 10/27/2008	DATE - 10-25-94		

STATE	OF	ILLINOIS
DEPARTMENT	0F	TRANSPORTATION

SCALE: NONE

PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT		F.A RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
		1587	3034-RS-S	соок	48	26
		BD4	400-04 (BD-22)	CONTRACT	NO.	60L82
EET NO. 1 OF 1 SHEETS STA.	TO STA.	FED. ROAD D	DIST. NO. 1 ILLINOIS FED. A	D PROJECT		