

URBAN

SUMMARY OF QUANTITIES

CODE NO

ITEM

UNIT

TOTAL QUANTITIES

0005 100% STATE

21101615

TOPSOIL FURNISH AND PLACE, 4"

SO YD

29

29

25200110

SODDING, SALT TOLERANT

SO YD

29

29

40600200

BITUMINOUS MATERIALS (PRIME COAT)

TON

20

20

40600300

AGGREGATE (PRIME COAT)

TON

96

96

40600400

MIXTURE FOR CRACKS, JOINTS,
AND FLANGEWAYS

TON

36

36

40600827

POLYMERIZED LEVELING BINDER (MACHINE
METHOD), IL-4.75, N50

TON

989

989

40600895

CONSTRUCTING TEST STRIP

EACH

2

2

40600982

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT
JOINT

SO YD

331

331

40601005

HOT-MIX ASPHALT REPLACEMENT OVER
PATCHES

TON

135

135

40603595

POLYMERIZED HOT-MIX ASPHALT SURFACE
COURSE, MIX "F", N90

TON

2350

2350

42001300

PROTECTIVE COAT

SO YD

60

60

42400200

PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH

SO FT

12

12

URBAN

SUMMARY OF QUANTITIES

CODE NO

ITEM

UNIT

TOTAL QUANTITIES

0005 100% STATE

44000159

HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"

SO YD

23966

23966

44000600

SIDEWALK REMOVAL

SO FT

12

12

44002216

HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"

SO YD

590

590

44201765

CLASS D PATCHES, TYPE II, 10 INCH

SO YD

461

461

44201769

CLASS D PATCHES, TYPE III, 10 INCH

SO YD

20

20

44201771

CLASS D PATCHES, TYPE IV, 10 INCH

SO YD

29

29

60300105

FRAMES AND GRATES TO BE ADJUSTED

EACH

5

5

60406000

FRAMES AND LIDS, TYPE I, OPEN LID

EACH

3

3

60406100

FRAMES AND LIDS, TYPE I, CLOSED LID

EACH

4

4

67000400

ENGINEER'S FIELD OFFICE, TYPE A

CAL MO

6

6

67100100

MOBILIZATION

L SUM

1

1

70102625

TRAFFIC CONTROL AND PROTECTION,
STANDARD 701606

L SUM

1

1

70102635

TRAFFIC CONTROL AND PROTECTION,
STANDARD 701701

L SUM

1

1

70300100

SHORT TERM PAVEMENT MARKING

FOOT

2850

2850

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US ROUTE 14 (LUTHER LANE TO EO GREENWOOD AVE.)
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

FILE NAME: c:\pwworking\illinois\road\0230649-D0601-11-plot.dgn

USER NAME: khrdadm

DESIGNED: DRAWN: CHECKED: PLOT DATE: 11/13/2012

REVISED: REVISED: REVISED: REVISED:

F.A. RTE. 1324

SECTION 2010-094-R5

COUNTY COOK

TOTAL SHEETS 22

SHEET NO. 3

CONTRACT NO. 60L93

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT