

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE			SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0004	BRIDGE 0014	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0004	BRIDGE 0014
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	21	21		44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	965	965	
20200100	EARTH EXCAVATION	CU YD	50	50		44002208	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2"	SO YD	126	126	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	347	347		44004250	PAVED SHOULDER REMOVAL	SO YD	672	672	
20400800	FURNISHED EXCAVATION	CU YD	600	600		44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	39	39	
20800150	TRENCH BACKFILL	CU YD	8	8		44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	75	75	
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	4187	4187		48101498	AGGREGATE SHOULDERS, TYPE B 4"	SO YD	412	412	
25000310	SEEDING, CLASS 4	ACRE	0.9	0.9		48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	639	639	
25100630	EROSION CONTROL BLANKET	SO YD	4187	4187		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	90	90		50102400	CONCRETE REMOVAL	CU YD	3.2		3.2
28000305	TEMPORARY DITCH CHECKS	FOOT	348	348		50104000	BRIDGE RAIL REMOVAL	FOOT	128		128
28000400	PERIMETER EROSION BARRIER	FOOT	1357	1357		50105220	PIPE CULVERT REMOVAL	FOOT	24	24	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SO YD	639	639		50300225	CONCRETE STRUCTURES	CU YD	27.8		27.8
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	66	66		50300255	CONCRETE SUPERSTRUCTURE	CU YD	125.0		125.0
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1		50300260	BRIDGE DECK GROOVING	SO YD	611		611
40600300	AGGREGATE (PRIME COAT)	TON	5	5		50300300	PROTECTIVE COAT	SO YD	611		611
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	2	2		50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SO FT	2800		2800
40600635	LEVELING BINDER (MACHINE METHOD) N70	TON	45	45		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	38,180		38,180
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SO YD	26	26		50800515	BAR SPLICERS	EACH	292		292
40600990	TEMPORARY RAMP	SO YD	49	49		50901050	STEEL RAILING, TYPE SM	FOOT	128		128
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	15	15		51500100	NAME PLATES	EACH	1		1
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	92	92		52000110	PREFORMED JOINT STRIP SEAL	FOOT	45		45
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	35	35		54215559	METAL END SECTIONS 24"	EACH	2	2	
44000100	PAVEMENT REMOVAL	SO YD	93	93		58700300	CONCRETE SEALER	SA FT	280		280
						59000200	EPOXY CRACK INJECTION	FOOT	130		130

* SPECIALTY ITEMS