



EROSION CONTROL GENERAL NOTES

1. TEMPORARY EROSION CONTROL SEEDING IS TO BE PROVIDED AT ALL ERODIBLE BARE EARTH AREAS, REFER TO SPECIAL PROVISIONS.
2. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN INLET FILTERS AT ALL PROPOSED DRAINAGE STRUCTURES AND AT OTHER LOCATIONS DIRECTED BY THE ENGINEER AND/OR SHOWN ON THE PLANS.
3. EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND OF THE APPLICABLE STATE STANDARDS FOR THE DURATION OF THE PROJECT, OR UNTIL SUCH TIME AS DIRECTED BY THE ENGINEER
4. AT ANY AREA WHERE THERE IS NO PROPOSED EARTH GRADING, THE EXISTING GROUND COVER SHALL REMAIN.
5. THE CONTRACTOR SHALL PROVIDE A PLAN TO AVOID EROSION/SEDIMENT DURING STORM SEWER INSTALLATION
6. STATION EQUATION:
STA. 1154+64.66 BK = STA. 40+00.00 AH
7. THE DEPARTMENT HAS NO OBTAINED ANY PERMITS FOR OFFSITE BORROW OR WASTE/USE (BWU) AREAS. PRIOR TO WORKING IN BWU AREAS, IF THE CONTRACTOR CHOOSES TO USE ACTIVITIES REQUIRING PERMITS, IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE THE PROPER PERMITS. IN ADDITION TO THE BORROW REVIEW (BDE 2289) AND USE/WASTE REVIEW (BDE 2290) SUBMITTALS, THE CONTRACTOR WILL NEED TO SUBMIT AN EROSION AND SEDIMENT CONTROL (ESC) PLAN FOR EVERY BWU SITE TO THE DEPARTMENT FOR ACCEPTANCE. THE COST OF ALL MATERIALS AND LABOR NECESSARY TO COMPLY WITH THE ABOVE PROVISIONS TO PREPARE AND IMPLEMENT ESC PLANS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

LEGEND

- TEMPORARY DITCH CHECK**
- PERIMETER EROSION BARRIER •
- INLET FILTERS AND PIPE PROTECTION **
- PROP. TEMP. EROSION CONTROL SEEDING
PROP. EROSION CONTROL BLANKET
- ITEM TO BE INSTALLED PRIOR TO STARTING ANY CONSTRUCTION IN THE ADJACENT AREA
- ** ITEM TO BE INSTALLED AFTER THE AREA IS DISTURBED

FILE NAME =	USER NAME = ledezmar	DESIGNED -	REVISED - RL 3/15/2013
et:\pw\work\p1dot\ledezmar\d0315650\131911-sht-plan.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
\$MODELNAME\$	PLOT DATE = 3/15/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL. ROUTE 83 (BUSSE/KINGERY) DEVON AVE - MARK AVE
EROSION CONTROL PLAN**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	540R-RS-2	DUPAGE&COOK	49	21
CONTRACT NO. 60N49				
ILLINOIS FED. AID PROJECT				