



8" (200) P.C.C. DRIVEWAY PAVEMENT CURB AND GUTTER SECTION B-B FLOW LINE OF GUTTER CURB AND GUTTER



P.C.C. DRIVEWAY PAVEMENT DETAIL



SIDEWALK Y4" (20) PREFORMED EXPANSION JOINT FILLER


SLOPE FOR SIDEWAL(
1" (25) IN 3'-0" (0.9 m) IN CHICAGO


NOTES:

- ONE-HALF INCH THICK EXPANSION JOINTS SHALL BE PLACED BETWEEN THE SIDEWALK AND ALL STRUCTURES SUCH AS LIGHT STANDARDS, TRAFFIC LIGHT STANDARDS, MANHOLES, WHICH EXTEND THROUGH THE SIDEWALK.
- 2. ¾" (20) THICK EXPANSION JOINTS SHALL BE PLACED AT INTERVALS OF NOT MORE THAN 100 FEET (30 METERS) IN THE SIDEWALK. WHERE THE SIDEWALK IS CONSTRUCTED ADJACENT-TO PAVEMENT OR CURB HAVING EXPANSION JOINTS, THE EXPANSION JOINTS IN THE SIDEWALK SHALL BE PLACED OPPOSITE THE EXISTING EXPANSION JOINTS AS NEARLY AS PRACTICABLE. EXPANSION JOINTS SHALL ALSO BE PLACED WHERE THE SIDEWALK ABUTS EXISTING SIDEWALKS, BETWEEN DRIVEWAY PAVEMENT AND SIDEWALK, AND BETWEEN SIDEWALK AND CURBS WHERE THE-SIDEWALK ABUTS A CURB.

PORTLAND CEMENT CONCRETE SIDEWALK DETAILS

NOTES: NO EXTRA COMPENSATION SHALL BE ALLOWED FOR THE GUTTER FLARE





ALLEY RETURN DETAIL

ALL DIMENSIONS ARE IN INCHES (MILLINETERS) UNLESS OTHERWISE SHOWN

HRGreen.com
Illinois Professional Desi
#184-001322

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TED: 1/2/2013 10:18:24 PM 86100196.15-det-03o.dgn R: pdf.pt standard-trans.tbl

reen.com Professional Design Firm 01322

 P.C. CONCRETE DRIVEWAYS SHALL BE CONSTRUCTED AT LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
 ¾" (20) PREFORMED EXPANSION JOINTS WILL NOT BE

PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO P.C.C. DRIVEWAY PAVEMENT 8" (200).

 COMBINATION CONC. CURB AND GUTTER SHALL BE MEASURED STRAIGHT ACROSS THE DRIVEWAY. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR

THE TRANSITION CURB AND GUTTER.

DEPART

00196.15 100196.15 100196.15 100196.15-det-03a.dgn