

MATCH LINE
STA. 949+00

MATCH LINE
STA. 963+00

IL RTE 83 (KINGERY HWY)


LANDSCAPING LEGEND

-  CONCRETE MEDIAN SURFACE REMOVAL AND REPLACEMENT WITH TOPSOIL AND SEED (SEE NOTE 3)
-  CONCRETE MEDIAN SURFACE REMOVAL AND REPLACEMENT WITH STAMPED COLORED PCC MEDIAN SURFACE 5 INCH (SPECIAL)
-  PROPOSED TREE AT 30' CENTER TO CENTER SPACING (SEE PROPOSED TREE SCHEDULE)

LANDSCAPING NOTES:

1. PROPOSED TREES LOCATED IN THE MEDIAN SHALL BE SPACED AT 30' INTERVALS IN AN ALTERNATING PATTERN FOR THE TREE SPECIES LISTED IN THE LANDSCAPING SCHEDULE.
2. COLORED STAMPED CONCRETE MEDIAN SHALL BE POURED MONOLITHICALLY AND STAMPED WITH HERRINGBONE BRICK PATTERN AS SHOWN IN THE PLANS (SEE DETAIL).
3. EROSION CONTROL BLANKET AND FERTILIZER NUTRIENTS (NITROGEN, PHOSPHORUS AND POTASSIUM) TO BE APPLIED TO ALL SEEDING AREAS
4. CONCRETE MEDIAN SURFACES TO BE REMOVED AND REPLACED WITH LANDSCAPED MEDIANS AT STA. 944+42 TO STA. 976+75 WILL BE REQUIRED TO HAVE SAME DAY STABILIZATION

COLORED STAMPED CONCRETE MEDIAN DETAIL:



MATCH LINE
STA. 963+00

MATCH LINE
STA. 977+00

IL RTE 83 (KINGERY HWY)

FILE NAME =	USER NAME = Bilgrmise	DESIGNED -	REVISED - SB 3/14/13
et:\pw_work\pwidot\bilgrmise\d0315608\DI00313-shit-plan.dgn		DRAWN -	REVISED -
\$MODELNAME\$	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/15/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 83 (IL 19 TO IL 64)
LANDSCAPING PLANS**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	540R-RS-3	DUPAGE	38	20
CONTRACT NO. 60V54				
ILLINOIS FED. AID PROJECT				