SCHEDULE OF QUANTITIES

Z0028415

GEOTECHNICAL REINFORCEMENT

This item is a contingency to be used as directed by the Engineer.

A quantity of 1120 SQ YD is estimated. Based on 10% replacement.

<u>R.I.</u>	<u>Henry</u>	<u>TOTA</u>	<u>L</u>	
SQ YD	SQ YD		<u>LOCATION</u>	COMMENTS
820	515	1335	VARIES LOCATIONS E.B. & W.B.	
820		820	SUB-TOTAL ROCK ISLAND COUNTY	
	515	515	SUB-TOTAL HENRY COUNTY	
820	515	1335	TOTAL	

Z0040530 <u>PIPE UNDERDRAIN REMOVAL</u>

E.B.	W.B.												
RT SIDE	LT SIDE		ROCK ISLAND										
<u>F00T</u>	<u> F00T</u>	TOTAL	LOCATION				<u>COMMENTS</u>						
	458	458	275	+	25	_ 27	9 +	22	WB NORTH SHOULDER, WEST OF COAL CREEK				
458		458	275	+	25	_ 27	9 +	24	EB NORTH SHOULDER, WEST OF COAL CREEK				
	535	535	281	+	1	_ 28	5 +	75	WB NORTH SHOULDER, EAST OF COAL CREEK				
535		535	280	+	99	_ 28	5 +	75	EB NORTH SHOULDER, EAST OF COAL CREEK				
993	993	1986	TOTAL	ROCK	ISLAND	COUNT	Υ						

Z0062456 <u>TEMPORARY PAVEMENT</u>

E.B.	W.B.												
RT SIDE	LT SIDE	ROCK ISLAND											
SQ YD	SQ YD	TOTAL	TOTAL <u>LOCATION</u>							COMMENTS			
974		974	266	+	62.00	TO	275	+	25.00	PRE-STAGE,	EB		
	801	801	268	+	00.00	T0	275	+	25.00	PRE-STAGE,	WB		
	645	645	271	+	77.00	T0	279	+	82.76	PRE-STAGE,	WB		
582		582	273	+	60.00	T0	279	+	83.17	PRE-STAGE,	EB		
	667	667	280	+	40.00	T0	287	+	96.00	PRE-STAGE,	WB		
718		718	280	+	39.60	T0	288	+	52.00	PRE-STAGE,	EB		
	938	938	285	+	75.00	T0	294	+	38.00	PRE-STAGE,	WB		
837		837	285	+	75.00	T0	293	+	04.00	PRE-STAGE,	EB		
3110	3050	6160	TOTAL	ROCK	(ISLAN	ID CO	UNTY						

* 74/280 & 80 ** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR *** ROCK ISLAND/HENRY COUNTY

FILE NAME = USER NAME = hensonke DESIGNED - REVISED - COUNTY SHEETS NAME = hensonke NAME = hen