

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS, GENERAL NOTES, HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
4. I-64 GROUP LOCATION MAP
5. I-70 GROUP LOCATION MAP
6. I-55/70 GROUP LOCATION MAP
7. I-255/IL 255 GROUP LOCATION MAP
8. I-64 SCHEDULE OF QUANTITIES
- 9.-10. I-70 SCHEDULE OF QUANTITIES
- 11.-12. I-55/70 SCHEDULE OF QUANTITIES
- 13.-14. I-255/IL 255 SCHEDULE OF QUANTITIES
15. IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3
16. EROSION CONTROL PLAN

GENERAL NOTES

1. EXISTING PIPE UNDERDRAIN OUTLETS AND DRAINAGE STRUCTURES IN THE MEDIAN SLOPES SHALL BE PRESERVED AND PROTECTED DURING CONSTRUCTION. ANY DAMAGE TO AN UNDERDRAIN OUTLET RESULTING FROM CONSTRUCTION ACTIVITY SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
2. IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 107.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
3. ONE APPLICATION OF TEMPORARY EROSION CONTROL SEEDING HAS BEEN INCLUDED. THE ACTUAL QUANTITY, LOCATIONS AND APPLICATIONS SHALL BE AS DIRECTED BY THE ENGINEER. THE APPLICATION RATE SHALL BE AS PER ARTICLE 280.04(f).
4. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 14 DAYS IN ADVANCE OF STARTING ANY CONSTRUCTION WORK. THIS ADDITIONAL INFORMATION IS REQUIRED SO THAT THE PUBLIC CAN BE NOTIFIED OF THE PENDING CONSTRUCTION.
5. EXISTING PIPE UNDERDRAINS AFFECTED BY CONSTRUCTION SHALL BE ADJUSTED, EXTENDED AND/OR INCORPORATED INTO THE PIPE CULVERTS TO PROVIDE DRAINAGE AS DIRECTED BY THE ENGINEER. PIPE UNDERDRAIN HEADWALLS MAY NEED TO BE REMOVED AND RELOCATED. THE COST OF THIS WORK SHALL BE ACCORDING TO ARTICLE 109.04.
6. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. (1-800-892-0123 OR 811) OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY.
7. UTILITY INTERFERENCES ARE NOT ANTICIPATED ON THIS CONTRACT. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE HIS CONSTRUCTION ACTIVITIES WITH THE VARIOUS UTILITY OWNERS. ALL POTENTIAL CONFLICTS SHALL BE INVESTIGATED AND REMEDIAL ACTION TAKEN PRIOR TO INTERRUPTION OF THE CONTRACTOR'S PROGRESS. NO ADDITIONAL COST SHALL BE ADDED TO THE CONTRACT RESULTING FROM UTILITY CONFLICTS.
8. EARTHWORK QUANTITIES WERE CALCULATED BY DESIGN STAFF FROM FIELD SURVEY DATA. CONTRACTOR SHALL FIELD VERIFY QUANTITIES PRIOR TO BEGINNING WORK.
9. IT HAD BEEN ASSUMED 1 INLET/PIPE PROTECTION PER ATTENUATOR.

HIGHWAY STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 280001-07 TEMPORARY EROSION CONTROL SYSTEMS
- 643001-01 SAND MODULE IMPACT ATTENUATORS
- 701101-03 OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
- 701400-06 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701406-06 LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
- 701901-02 TRAFFIC CONTROL DEVICES

COMMITMENTS

NONE

- VARIOUS
- DIST 8 ATTENUATOR 2013-1

FILE NAME *	USER NAME * wadmonejb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES, HIGHWAY STANDARDS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pvidot\wadmonejb\d032272b\d076g13-sht-plan.dgn	DRAWN -	REVISED -	•			••	VARIOUS	16	2	
PLOT SCALE * 100.0000 "/ in.	CHECKED -	REVISED -	CONTRACT NO. 76C13							
PLOT DATE * 2/8/2013	DATE -	REVISED -	SCALE: NONE			SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	