

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	130BB-4	BOONE	147	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

BITUMINOUS SCHEDULE

PAY CODES:

STATIONING	REMARKS	LENGTH FEET	AVG. WIDTH FEET	MAINLINE AREA SQ. YD.	SHOULDER AREA SQ. YD.	31100300	31100910	31100935	31100965	21001000	20600310	42001165	40701851	40701921	40603310	48203021	48101300	48101200	
						SUBBASE GRANULAR MTL TYPE A 4" SQ. YD.	SUBBASE GRANULAR MTL TYPE A 12" SQ. YD.	SUBBASE GRANULAR MTL TYPE A 18" SQ. YD.	SUBBASE GRANULAR MTL TYPE A 24" SQ. YD.	** GEOTECHNICAL FABRIC FOR GROUND STABILIZATION SQ. YD.	** QUARRY RUN GRANULAR EMBANKMENT VARIABLE THICKNESS 24" - 42" THICKNESS (in.) CU. YD.	BRIDGE APPROACH PAVEMENT CONCRETE SQ. YD.	HMA PAVEMENT FULL-DEPTH 8.50" SQ. YD.	HMA PAVEMENT FULL DEPTH 12" SQ. YD.	HMA SURFACE COURSE MIX C, N50 2" TON	HMA SHOULDERS 6" SQ. YDS	AGG. SHLDERS TYPE B (SPECIAL) 6" TON	AGG. SHLDERS TYPE B 6" TON	
IL RTE 173																			
429 + 0 to 432 + 96	IL 173 - LT	396	26.00	1144.00	253.00														
432 + 96.00 to 436 + 86.24	IL 173 LT	390.24	13.00	563.68	303.62				917.80										
436 + 86.24 to 437 + 50	IL 173 LT	63.76	13.00	93.89	63.76				173.67										
437 + 50.00 to 438 + 92.96	IL 173 LT	142.96	13.00	206.50	174.73														
432 + 96.00 to 435 + 16.68	IL 173 RT	220.68	13.00	318.76	171.64				519.30										
435 + 16.68 to 437 + 50	IL 173 RT	233.32	13.00	337.02	233.32				625.80										
437 + 50.00 to 438 + 92.96	IL 173 RT	142.96	13.00	206.50	174.73														
438 + 92.96 to 439 + 22.96	W. APPROACH PAVEMENT - LT & RT	30	40.50	135.00		145.0													
439 + 22.96 to 440 + 83.04	PROPOSED BRIDGE	130.08																	
440 + 83.04 to 440 + 83.04	E. APPROACH PAVEMENT - LT & RT	30	40.50	135.00		145.0													
440 + 83.04 to 442 + 0	IL 173 LT	116.96	13.00	168.94	259.91				303.70										
442 + 0.00 to 443 + 71.81	IL 173 LT	171.81	13.00	248.17	190.90														
443 + 71.81 to 446 + 96.00	IL 173 LT	324.19	13.00	468.27															
446 + 96.00 to 450 + 0.00		304																	113
440 + 83.04 to 442 + 0.00	IL 173 RT	116.96	13.00	168.94					319.91										
442 + 0.00 to 443 + 2.27	IL 173 RT	102.27	13.00	147.72															
443 + 2.27 to 446 + 96.00	IL 173 RT	393.73	13.00	568.72															
TEMPORARY RUNAROUND																			
100 + 85 to 104 + 50		365		568.35						623.72									
104 + 50 to 105 + 50		100		244.40															
105 + 50 to 106 + 50		100		244.60															
106 + 50 to 107 + 0		50		122.25															
107 + 0 to 107 + 50		50		122.25															
107 + 50 to 108 + 0		50		122.25															
108 + 0 to 110 + 50		250		611.15															
110 + 50 to 111 + 0		50		122.25															
111 + 0 to 112 + 0		100		244.60															
112 + 0 to 114 + 0		200		489.00															
114 + 0 to 114 + 50		50		122.25															
114 + 50 to 115 + 0		50		122.25															
115 + 0 to 116 + 0		100		244.50															
116 + 0 to 120 + 50		450		1024.10															
GRAND TOTAL				4404		290	3932	8409	534	11142		3550	270	4404	3489	253	2256	253	671

PLT DATE = Fri Feb 23 09:45:54 2007
 FILE NAME = c:\p\projects\view\p23082\ad03082evr.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = dtz@psd

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. / HORIZ. / DATE DRAWN BY / CHECKED BY

BITUMINOUS SCHEDULE