

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
 ** (X1-6-2)WB-2, (X1-6)HBK-2

SUMMARY OF QUANTITIES

		WILLIAMSON URBAN											
		F. A. I. 57					FAU 9629 (OLD IL 13)						
		90% FEDERAL/ 10% STATE-ACIM					90% FED 10% STATE	100% STATE	90% FED 10% STATE	90% FED 10% CITY			
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	SIGNALS	SIGNALS	ROADWAY	ROADWAY
				STA 1500+00 TO STA 1556+85	100-0084 TO 100-0085	100-0086 TO 100-0087	100-0008 TO 100-0009	100-0005		SB I57 RAMP ACIM	VA & NB I57 RAMP	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM
				I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A
X0300203	CLEAN AND FILL EXPANSION JOINTS	EACH	8.0										8.0
X0300471	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SQ YD	17,159.0	17,159.0						1.0	1.0		
X0300737	RADIO TRANSCEIVER	EACH	2.0										
X0322066	PROTECTIVE SHIELD (PERMANENT)	SQ YD	878.0				878.0						
X0322662	TEMPORARY SIGNING	EACH	3.0				3.0						
X0322729	MATERIAL TRANSFER DEVICE	TON	2,362.0	2,362.0									
X0322879	GRADING AND SHAPING FORESLOPES	SQ YD	431.0	431.0									
X0323991	SURFACE MOUNT LANE SEPARATOR	FOOT	792.0									792.0	
51202305	DRIVING PILES	FOOT	8,079.0		2,739.0	5,340.0							
X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	34.0										
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	3,116.0	3,116.0									
X7050169	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (FLARED)	EACH	1.0	1.0									
X7240205	REMOVE SIGN COMPLETE	EACH	21.0	17.0									
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	57.0	57.0									
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	14.0	14.0									
X7340100	CONCRETE FOUNDATIONS, GROUND MOUNT	CU YD	24.4	17.8									
X8420220	REMOVE EXISTING HIGH MAST LIGHT TOWER	EACH	10.0						10.0				
X8420300	LIGHTING FOUNDATION REMOVAL, LIGHT TOWER	EACH	6.0						6.0				
XX003813	ELECTRIC CABLE IN CONDUIT, NO. 10 3/C	FOOT	1,529.0							497.0	1,032.0		
XX006661	UNINTERRUPTIBLE POWER SUPPLY	EACH	2.0							1.0	1.0		
Z0006600	BRIDGE DECK CONCRETE OVERLAY	SQ YD	2,007.0										
Z0006601	BRIDGE DECK HYDRO GRANIT FORTION 1/2"	SQ YD	1,953.0										
Z0016001	DECK SLAB RPAIR (FULL DEPTH, TYPE I)	SQ YD	115.1				84.0						
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	300.0				200.0						
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD											
Z0017202	DOWEL BARS 1 1/2"	EACH	1,768.0										1,768.0
X0325744	STATE FURNISHED BORROW (SELECT)	CU YD	33,200	33,200									
X0325745	STATE FURNISHED BORROW (RESTRICTED)	CU YD	44,700	44,700									

** HSIP FUNDING
 90% FED, 10% STATE
 * SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES 1 OF 12

SCALE: VERT.
 DATE: HORIZ.

DRAWN BY JCK
 CHECKED BY

Rev. 4-16-07
 Rev. 4-10-07