F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(32, 47-4)K	KENDALL/GRUNDY	243	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

CONTRACT NO. 66294

SUMMARY OF QUANTITIES

← 90% FED 10% STATE →

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE: ROADWAY J000-2A (KENDALL)	ROADWAY J000-2A (GRUNDY)	TRAFFIC SIGNALS Y031-1F (KENDALL)	TRAFFIC SIGNALS Y031-1F (GRUNDY)	HIGHWAY LIGHTING Y030-1E (KENDALL)	HIGHWAY LIGHTING Y030-1E (GRUNDY)
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	28.1	14.1	14.0				
* 78008300	POLYUREA PAVEMENT MARKING, TYPE II - LETTERS AND SYMBOLS	SQ FT	546	265	281				
* 78008310	POLYUREA PAVEMENT MARKING, TYPE II - LINE 4"	FOOT	15,598	8,484	7,114				
* 78008330	POLYUREA PAVEMENT MARKING, TYPE II - LINE 6"	FOOT	2,629	1,324	1,305				
* 78008340	POLYUREA PAVEMENT MARKING, TYPE II - LINE 8"	FOOT	11,322	5,391	5,931				
* 78008350	POLYUREA PAVEMENT MARKING, TYPE II - LINE 12"	FOOT	2,965	1,427	1,538				
* 78008370	POLYUREA PAVEMENT MARKING, TYPE II - LINE 24"	FOOT	336	185	151				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100	54	46				
78200410	GUARDRAIL MARKERS, TYPE A	EACH	26	8	18				
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	2	3				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,170	267	903				
[redacted]									
[redacted]									
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1					1	
[redacted]									
81012400	CONDUIT IN TRENCH, 1 1/4 " DIA., PVC	FOOT	293			148	145		
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1,777			862	915		
81012700	CONDUIT IN TRENCH, 2 1/2 " DIA., PVC	FOOT	315			119	196		
X0325242	CONDUIT IN TRENCH, 2 1/2 " DIA., PVC, SCHEDULE 80	FOOT	558			485	73		
X0933900	PVC CONDUIT IN TRENCH 3" (SCHEDULE #80)	FOOT	56			56			
X0934000	PVC CONDUIT IN TRENCH 4" (SCHEDULE #80)	FOOT	20			10	10		
X0325243	CONDUIT PUSHED, 3" DIA., PVC, SCHEDULE 80	FOOT	352			264	88		
X0325244	CONDUIT PUSHED, 4" DIA., PVC, SCHEDULE 80	FOOT	408			177	231		
[redacted]									
81400400	CONCRETE HANDHOLE	EACH	20			11	9		
81400500	CONCRETE HEAVY-DUTY HANDHOLE	EACH	1			1			
81400600	CONCRETE DOUBLE HANDHOLE	EACH	2			1	1		
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	16,390			1520	1255	8,395	5,220
[redacted]									

* SPECIALTY ITEM

REVISED 4-11-2006 PER ADDENDUM

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 80 (I-80 AT MINOOKA INTERCHANGE)

SUMMARY OF QUANTITIES

SCALE: NONE
DRAWN BY: NJS
DATE: 2/10/06
CHECKED BY: JJC

PATRICK ENGINEERING INC. LISLE, ILLINOIS

nschilling@lisle.pat
02/13/2006 9:54:07 AM G:\5001-939\ACad\Roadway Drawings\RDWY\sht's Part\S_500.dgn