

SUMMARY OF QUANTITIES

CONTRACT NO. 70537				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
717	1091-1	LOGAN	5	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION OF WORK: F. A. P. 717
IL RTE. 10
RURAL
STATION 304+72.00
TO
STATION 309+58.00
FUNDING BREAKOUT: 100% STATE

CONSTRUCTION TYPE CODE: I000

CODE NO. ITEM	UNIT	TOTAL QUANTITY	QUANTITY
40600100 BITUMINOUS MATERIALS (PRIME COAT)	GAL	143.0	143.0
40600300 AGGREGATE (PRIME COAT)	TON	3.0	3.0
40600980 BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1,423.0	1,423.0
40600990 TEMPORARY RAMP	SQ YD	95.0	95.0
67100100 MOBILIZATION	L SUM	1.0	1.0
70100460 TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0
70300100 SHORT-TERM PAVEMENT MARKING	FOOT	144.0	144.0
70301000 WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24.0	24.0
• 78001120 PAINT PAVEMENT MARKING - LINE 5"	FOOT	1,094.0	1,094.0
• 78100100 RAISED REFLECTIVE PAVEMENT MARKER	EACH	6.0	6.0
78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5.0	5.0
X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	160.0	160.0

• SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

FAP 717
SECTION 1091-1
LOGAN COUNTY

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY