

PLOT DATE = 2/18/2006
 USER NAME = dstr-101
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = dstr-101

SUMMARY OF QUANTITIES			100% STATE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
				SFTY-2A
20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	79	79
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	690	690
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	40	40
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	672	672
50102400	CONCRETE REMOVAL	CU YD	16.1	16.1
50200100	STRUCTURE EXCAVATION	CU YD	79	79
50300225	CONCRETE STRUCTURES	CU YD	16.5	16.5
50300260	BRIDGE DECK GROOVING	SQ YD	671.5	671.5
50300300	PROTECTIVE COAT	SQ YD	672	672
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6	6
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6	6
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2080	2080
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1820	1820
51205200	TEMPORARY SHEET PILING	SQ FT	88	88
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	94	94
67100100	MOBILIZATION	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1730	1730
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1700	1700
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	330	330
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	330	330
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1780	1780
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12
78300100	PAVEMENT MARKING REMOVAL	SQ FT	580	580
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	12

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
				SFTY-2A
X0300136	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	40	40
X0320887	POLYMER CONCRETE	CU FT	7.4	7.4
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	43	43
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	43	43
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	31.8	31.8
X7011420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	L SUM	1	1
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	672	672
Z0001500	APPROACH SLAB REMOVAL & REPLACEMENT	SQ YD	60	60
Z0002600	BAR SPLICERS	EACH	108	108
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	672	672
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1	1
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	66	66
Δ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
Δ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1

Δ SFTY-3N
 * SPECIALTY ITEMS

Rev.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SUMMARY OF QUANTITIES	
SCALE:	VERT. HORIZ.	DRAWN BY	
DATE		CHECKED BY	

CONTRACT NO. 74119				
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	EFFINGHAM	17	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• D-7 JOINT REPAIRS 2006-2