

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1 - 1	ROCK ISLAND	239	5
STA.	75+60.93	TO STA.	116+00.00	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
		CONTRACT #	84986	

← URBAN →

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITIES	2 - LANE 75+61 - 86+07	4 - LANE 86+07 - 116+00	90% STATE 10% CITY Y031 - 1F	100% CITY OF ROCK ISLAND Y060	50% STATE 50% CITY SFTY-1B	
				100% STATE 1000 - 2A	100% STATE 1000 - 2A				
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	136		136				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	575	36	539				
20100500	TREE REMOVAL, ACRES	ACRE	2.00	1.00	1.00				
20200100	EARTH EXCAVATION	CU YD	34455	9030	25425				
20800150	TRENCH BACKFILL	CU YD	1737	354	1383				
20900110	POROUS GRANULAR BACKFILL	CU YD	12	12					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	31916	6474	25442				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	26757	5773	20984				
25000400 *	NITROGEN FERTILIZER NUTRIENT	POUND	472	125	347				
25000500 *	PHOSPHORUS FERTILIZER NUTRIENT	POUND	472	125	347				
25000600 *	POTASSIUM FERTILIZER NUTRIENT	POUND	472	125	347				
25000910 *	SEEDING, CLASS 1 (MODIFIED)	ACRE	4.79	0.29	4.50				
25100115 *	MULCH, METHOD 2	ACRE	4.79	0.29	4.50				
25100630	EROSION CONTROL BLANKET	SQ YD	2797	564	2233				
25200100 *	SODDING	SQ YD	14483	3323	11160				
25200200	SUPPLEMENTAL WATERING	UNIT	130.4	28.5	101.9				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1200	300	900				
28000300	TEMPORARY DITCH CHECKS	EACH	18		18				
28000400	PERIMETER EROSION BARRIER	FOOT	2185	570	1615				
28000500	INLET AND PIPE PROTECTION	EACH	68	18	50				
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	155	11	144				
28200200	FILTER FABRIC	SQ YD	155	11	144				
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	28638	5902	22736				
35101400	AGGREGATE BASE COURSE, TYPE B	TON	2931	402	2529				
35500100	BITUMINOUS BASE COURSE 4"	SQ YD	359		359				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	669	243	426				
40500300	BITUMINOUS MIXTURE COMPLETE	TON	535	140	395				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.0	2.2	2.8				
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1				
42300100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH	SQ YD	320	320					
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	1235	112	1123				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	18578					18578	
42400800	DETECTABLE WARNINGS	SQ FT	140	20	120				
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	9556	2508	7048				
44000100	PAVEMENT REMOVAL	SQ YD	15805	3802	12003				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1196	72	1124				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3145	1004	2141				
44002805	ISLAND REMOVAL	SQ FT	626		626				
50100300 *	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1				
50100400 *	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1				
50100500 *	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		1				

* SPECIALTY ITEM Δ REVISED 4-6-06 PER ADDENDUM