

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	104 RS-4	UNION	24	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAVEMENT SCHEDULE

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS SURFACE COURSE, SUPERPAVE, MIX D, N105, 1-1/2"	PCC BASE COURSE, 9"	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N105	SUB-BASE GRANULAR MATERIAL TYPE A, 4"	AGGREGATE PRIME COAT	BIT. MATERIAL PRIME COAT	TEMP RAMP	PCC DRIVEWAY PAVEMENT 7"	PCC SIDEWALK, 4"	PROTECTIVE COAT
	TON	SQYD	TON	SQYD	TON	TON	SQYD	SQYD	SQFT	SQYD
STA 0+00 TO STA 0+53	20		10		1	21				
STA 0+48 TO STA 0+53							23			
STA 100+00 TO STA 104+85	166		80		2	178				
STA 101+00 TO STA 104+50 (RIGHT)		90		144						
STA 101+23(RIGHT)				24				24		24
STA 102+55(RIGHT)				52				36		36
STA 103+44(RIGHT)				18				12		12
104+22 (LEFT)									52	
104+22 (RIGHT)									38	
STA 104+80 TO STA 104+85							19			
SPRING STREET	4	42	2	42	1	4				
TOTALS	190	132	92	280	4	203	42	72	90	72

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	PAINT 4 INCH			THERMOPLASTIC		LETTERS AND SYMBOLS
	WHITE	YELLOW	DOUBLE YELLOW	6 INCH WHITE	12 INCH YELLOW	
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT
STA 0+00 TO STA 0+53 (EDGE LINE)	53					
STA 0+00 TO STA 0+53 (DOUBLE YELLOW)			53			
STA 100+00 TO STA 101+03 (EDGE LINE)	103					
STA 100+00 TO STA 100+59 (DOUBLE YELLOW)			59			
STA 100+59 TO STA 102+46 (LT TAPER)			146		184	
STA 100+59 TO STA 102+46 (RT TAPER)			187			
STA 102+05 TO STA 104+19 (LT)		215				
STA 102+05 TO STA 104+19 (LT SKIP DASH)		51				
STA 102+46 TO STA 104+19 (RT)		174				
STA 102+46 TO STA 104+19 (RT SKIP DASH)		49				
STA 103+25 (TWO-WAY LEFT TURN ARROWS)						18
STA 104+19 (CROSSWALK)				68		
SUBTOTAL	156	489	890	68	184	18
TOTAL		1535		68	184	18