

SUMMARY OF QUANTITIES

URBAN
80% FED.
20% STATE

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005 ROADWAY	0040 DRAINAGE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8		8
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18		18
20101100	TREE TRUNK PROTECTION	EACH	28		28
20101200	TREE ROOT PRUNING	EACH	4		4
20200100	EARTH EXCAVATION	CU YD	1,065	1,065	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,089	1,089	
20800150	TRENCH BACKFILL	CU YD	107		107
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,022		4,022
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	449		449
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	449		449
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	449		449
25200110	SODDING, SALT TOLERANT	SQ YD	4,022		4,022
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	37		37
28000305	TEMPORARY DITCH CHECKS	FOOT	54		54
28000400	PERIMETER EROSION BARRIER	FOOT	3,530		3,530
28000510	INLET FILTERS	EACH	53		53
28100107	STONE RIPRAP, CLASS A4	SQ YD	13		13
28200200	FILTER FABRIC	SQ YD	13		13
31101200	SUB BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	3,082	3,082	
35501323	HOT-MIX ASPHALT BASE COURSE, 9 3/4"	SQ YD	2,551	2,551	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8	
40600300	AGGREGATE (PRIME COAT)	TON	39	39	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	29	29	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	252	252	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,637	1,637	
42001300	PROTECTIVE COAT	SQ YD	3,104	3,104	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAYPAVEMENT, 6 INCH	SQ YD	196	196	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAYPAVEMENT, 8 INCH	SQ YD	285	285	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	17,131		17,131
42400800	DETECTABLE WARNINGS	SQ FT	88		88
44000100	PAVEMENT REMOVAL	SQ YD	44	44	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	11,885	11,885	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	726	726	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	320	320	
44000600	SIDEWALK REMOVAL	SQ FT	14,755		14,755
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	656	656	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	266	266	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	50	50	
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	309		309
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	171	171	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4		4
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	4		4
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	320		320
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	125		125
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	307		307
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	104		104

*DENOTES SPECIALTY ITEM

n:\jobs\2009\20093023-32\CAD\Site\ dgn\00\0160487-ant--S0001.dgn
 2/14/2011 11:46:37 AM

FILE NAME =	USER NAME = .USER.	DESIGNED - WS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LOOMIS AVENUE FROM THORNTON RD. TO 150TH ST. SUMMARY OF QUANTITIES			SBI	SECTION	COUNTY	TOTAL	SHEET	
#FILE#		DRAWN - WS	REVISED -					52	521-X-RS-1	COOK	44	3	
PLOT SCALE = 20.0000' / IN.		CHECKED - RS	REVISED -		SCALE: 20			SHEET NO. 1	OF 2	SHEETS	STA.	TO STA.	CONTRACT NO. 60K87
PLOT DATE = 2/14/2011		DATE - 01-21-2011	REVISED -		ILLINOIS FED. AID PROJECT								