

EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
ILLINOIS 13 EB 587+50 TO 634+00	8129	6097	2609	3488
ILLINOIS 13 WB 592+50 TO 633+50	9204	6903	1987	4916
ILLINOIS 148 LEFT 34+50 TO 60+00	3750	2813	209	2604
ILLINOIS 148 RIGHT 44+00 TO 60+00	3424	2568	3865	-1297
COX RD 0+00 TO 11+00	10527	7895	2159	5736
AIRWAY DR 0+00 TO 9+00	5486	4115	5655	-1541
AIRWAY 1 10+00 TO 13+50	31	23	96	-73
AIRWAY 2 20+00 TO 20+60	6	5	0	5
AIRWAY 3 30+00 TO 31+00	31	23	2	21
TOTALS	40588	30441	16582	13859

25% Shrinkage Factor for Earth Excavation

PIPE UNDERDRAIN SCHEDULE

LOCATION	PIPE UNDERDRAIN REMOVAL (SPECIAL)	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS
	FOOT	EACH	FOOT	FOOT	EACH
ILLINOIS 13 (EB LANES) 587+78 RT TO 617+00 RT	2922		2922		
590+40	17	1		17	1
594+00	17	1		17	1
600+00	17	1		17	1
604+00	17	1		17	1
608+00	17	1		17	1
612+00	17	1		17	1
617+00	17	1		17	1
ILLINOIS 13 (WB LANES) 592+90 LT TO 612+00 LT	1910		1910		
594+00	17	1		17	1
600+00	17	1		17	1
604+00	17	1		17	1
608+00	17	1		17	1
612+00	17	1		17	1
AIRWAY DRIVE 1+40 RT 1+90 RT					3 3
TOTAL	5036	12	4832	204	18