
DOUTT			TOTAL	SHEET
ROUTE	SECTION	COUNTY	SHEETS	NUMBER
VARIOUS	2009-075 I	VARIOUS	21	14.


Contract 60H88



Wall is comprised of a series of panels, stacked on top. Wall height ranges from 12' to 17' in height. The beginning of the wall is stepped up to full 17' height in the middle.

## **DETAIL LOCATION: 6** (DURISOL WALL)

LOCATION 6		
ITEM	UNIT	QUANTITY
Removal of Noise Abatement Wall Panels	SQ:FT.	90
Noise Abatement Wall, Ground Mounted (Absorptive)	SQ.FT.	90
FOR INFORMATION ONLY		



Vertical Displacement / Alignment Notice The Edge Of The Panels Exposure Relative To The Steel "H" Post. Looks Like a Post Spacing Problem During The Construction / Erection Of The Noisewall.

## **DETAIL LOCATION: 7** (DURISOL WALL)

LOCATION 7		
ITEM	UNIT	QUANTITY
Removal of Noise Abatement Wall Panels	SQ.FT.	45
Noise Abatement Wall, Ground Mounted (Absorptive)	SQ.FT.	45
FOR INFORMATION ONLY		· · · · · · · · · · · · · · · · · · ·

ILLINOIS DEPARTMENT OF TRANSPORTATION

LOCATION: 6 AND 7 IL 59

FOR INFORMATION ONLY

SHEET 3 OF 3