INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, AND COMMITMENTS
3	SUMMARY OF QUANTITIES
4-7	TYPICAL SECTIONS
* 8	SCHEDULE OF QUANTITIES
9-13	PLAN SHEETS
14-18	PAVEMENT MARKING DETAILS
19-21	SPECIAL DETAILS

*8A INCLUDED

HIGHWAY STANDARDS

000001-05
001006
482001-02
482006-03
606301-04
610001-04
630001-08
630301-05
701421-02
701901-01
780001-02
781001-03
701401-05

GENERAL NOTES

1. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

   - •AMEREN IP (GAS AND ELECTRIC)
   - •AMEREN UE (GAS AND ELECTRIC)
   - •AT&T ILLINOIS (COMMUNICATIONS)
   - •CHARTER COMMUNICATIONS, INC. (CABLE T.V.)
   - •ILLINOIS AMERICAN WATER COMPANY (WATER)
   - •METRO (COMMUNICATIONS)
   - •STOOKEY TOWNSHIP (SANITARY SEWER)

   MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY •. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

2. THE THICKNESS OF HOT-MIX ASPHALT SURFACE MIXTURES SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS MAY OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.

3. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.

4. THE WIDTHS OF HMA SURFACE REMOVAL SHOWN ON THE PLANS ARE THE NOMINAL WIDTHS. IRREGULARITIES IN THE SURFACE WIDTH MAY OCCUR THROUGHOUT THE LENGTH OF THE SECTION. HMA SURFACE REMOVAL WILL BE PAID FOR IN SQUARE YARDS BASED UPON THE NOMINAL WIDTHS INDICATED.

5. NO OVERNIGHT CLOSURES WILL BE PERMITTED

6. FLAGGERS SHALL BE REQUIRED AT ALL TIMES DURING PATCHING OPERATIONS

7. THE RESIDENT ENGINEER SHALL VERIFY THE EXISTANCE OF HIGHWAY LIGHTING AND/OR ITS EXISTS WITHIN THE PROJECT LIMITS, AND IF THESE ITEMS REQUIRE LOCATING, THE CONTRACTOR SHALL BE DIRECTED TO DO SO ACCORDING TO SECTION 803 OF THE STANDARD SPECIFICATIONS. IF LOCATING UNDERGROUND CABLE IS NOT INCLUDED AS PART OF THE PLANS, THIS WORK SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.

8. PROPOSED PAVEMENT MARKING SHALL MATCH EXISTING AS DIRECTED BY THE RESIDENT ENGINEER

9. SHORT TERM PAVEMENT MARKINGS SHALL BE APPLIED TO MILLED SURFACE, PRIMED SURFACE, LEVELING BINDER, AND FINAL SURFACE. ONLY REMOVAL FROM FINAL SURFACE TO BE PAID AS WORK ZONE PAVEMENT MARKING REMOVAL.

COMMITMENTS

NONE