

# TRANSPORTATION BULLETIN



Illinois Department of Transportation

## ADDENDUM NO. 1

Dated: June 2, 2010

For: Transportation Bulletin  
Letting Date: June 11, 2010  
Volume 13 No. 19r

Dated: May 7, 2010 REVISED: May 12, 2010

### Item No. 7A - Rehabilitate Runway 16/34.

Vermilion Regional Airport  
Danville, Illinois  
Vermilion County  
IL Project No.: DNV-4009  
AIP Project No.: 3-17-0032-B13  
Contract No.: VE047

### REASON FOR ADDENDUM:

Special Provision clarification. Specified material (ISAC) discontinued.

### TO ALL PLAN HOLDERS:

Delete reference to ISAC in Item 201671 – Crack Control Fabric in the Special Provision (page 12). Reflective crack control fabric shall meet the material requirements and construction methods specified in the Illinois Standard Specifications for Construction of Airports (Effective Date April 1, 2010), Item 201671 201-2.1 Reflective Crack Control System A.

When installed as part of the “Remove and Replace Bituminous Pavement” pay item, the crack control fabric shall be considered incidental to this pay item and will not be measured for payment.

Method of measurement is per linear feet as marked in the field for installation over transverse cracks. Payment shall be as specified in the Schedule of Prices for Item AR201671 – Crack Control Material.