## ROUTE: NE Frontage Rd.(I-55) (Lorenzo Rd. to 0.2 Mile S/O Lorenzo Rd.) - HMA SURFACE

CROSS	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR				
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA			
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)			
Lorenzo Road	0.1 mi. South of Lorenzo	SB	1	NONE		0	0			
	**This section was resurface	d when the inte	rchange wa	s reconstructe	ed, and is in go	ood condition				
0.2 mi. South of Lorenzo	0.3 mi. South of Lorenzo	SB - HMA	1	4	500	2,000	222			
	**This 0.1 mile long section	is HMA								
0.3 mi. South of Lorenzo	0.2 mi. South of Lorenzo	NB - HMA	1	4	500	2,000	222			
	**This 0.1 mile long section									
0.1 mi. South of Lorenzo	Lorenzo Road	NB	1			0	0			
	**This section was resurfaced when the interchange was reconstructed, and is in good condition									
·										

TOTALS:

1000 FT

444 SY

FILE NAME =	USER NAME = WILGREENDP	DESIGNED ~	REVISED ~		PATCHING SCHEDULE					F.A. RTF	SECTION	COUN	TOTAL SHEETS	SHEET NO.
c:\pw_work\PWIDOT\WILGREENDP\d0125109\D	esign,agn	DRAWN -	REVISED -	STATE OF ILLINOIS	I-55 FRONTAGE RD.				VAR.	2009-027		WILL 20	7	
i 1		CHECKED - DATE -	REVISED - REVISED ~	DEPARTMENT OF TRANSPORTATION	SCALE: SHEET NO. OF SHEETS STA. TO STA.			FED. ROAD DIST. NO. 1  ILLINOIS FED. AID PROJECT				J0026		