

## TREE REPLACEMENT SCHEDULE

COMMON NAME	SIZE	UNIT	QUANTITY	
Swamp White Oak	1-3/4"	EACH	20	
Bur Oak	1-3/4"	EACH	24	
merican Linden/Basswood	1-3/4"	EACH	20	
Grey Dogwood	4'	EACH	25	
ailey Redosier Dogwood	4'	EACH	25	
American Cranberry	4'	EACH	25	

Layout Shall be performed by the District Landscape Architect Each Plant shall receive a five foot diameter of hardwood chip mulch, four inches thick with weed barrier fabric The alternate planting site can be at the I-74 Krisdala Baka Westbound Rest Area located in Henry County

## TREE REPLACEMENT SCHEDULE **90.4**

STANDARD		F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		1188	118T	Henry	52	28	
				CONTRACT	NO. 6	54D13	
STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					