

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES		SAFETY CODE		2A	1F
CODE NO.	ITEM	CONSTRUCTION CODE		J000	Y031
		UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	379	379	
44000600	SIDEWALK REMOVAL	SQ FT	2,199	2,199	
* 44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	453	453	
44200929	CLASS B PATCHES, TYPE I, 8 INCH	SQ YD	23	23	
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	120	120	
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	102	102	
* 50105210	REMOVE EXISTING CULVERTS	FOOT	83	83	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1	
* 54248515	CONCRETE COLLAR	EACH	5	5	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	92	92	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	101	101	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	103	103	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	457	457	
* 55100700	STORM SEWER REMOVAL 15"	FOOT	47	47	
* 55101200	STORM SEWER REMOVAL 24"	FOOT	18	18	
* 59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	95	95	
* 60224600	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	
* 60224700	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	
* 60225400	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	3	3	
60500040	REMOVING MANHOLES	EACH	1	1	
60500060	REMOVING INLETS	EACH	1	1	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1,348	1,348	
* 66700095	PERMANENT SURVEY MARKERS	EACH	1	1	
* 67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	599	599	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	400	400	
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	36	36	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	204	204	
△* 78008300	POLYUREA PAVEMENT MARKING TYPE II - LETTERS AND SYMBOLS	SQ FT	156	156	
△* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	3,348	3,348	

*SEE SPECIAL PROVISIONS △ SPECIALTY ITEMS

FILE NAME = p:\00010461\Plans\sheets\summary.dgn PLOT DATE = 2/9/2009 1:17:24 PM	DESIGNED - R.L.H.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - J.L.B.	REVISED -				7170	08-00277-00-PV	CHAMPAIGN	44	5
	CHECKED - J.T.P.	REVISED -				CONTRACT NO. 91397				
DATE - 2-09		REVISED -	SCALE : NONE		SHEET NO. 5 OF 44 SHEETS	STA.	TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT HD-5181 (044)	