

78008300 POLYUREA PAVEMENT MARKING TYPE II - LETTERS AND SYMBOLS		
LOCATION	SYMBOLS (SQ FT)	COMMENTS
FIRST STREET		
100+82.5 ¢	15.6	LEFT TURN ARROW
100+82.5 LT.	15.6	RIGHT TURN ARROW
101+62.5 ¢	15.6	LEFT TURN ARROW
101+62.5 LT.	15.6	RIGHT TURN ARROW
102+42.5 ¢	15.6	LEFT TURN ARROW
102+42.5 LT.	15.6	RIGHT TURN ARROW
103+22.5 ¢	15.6	LEFT TURN ARROW
103+22.5 LT.	15.6	RIGHT TURN ARROW
104+02.5 ¢	15.6	LEFT TURN ARROW
104+02.5 LT.	15.6	RIGHT TURN ARROW
TOTAL	156.0	

78008370 POLYUREA PAVEMENT MARKING TYPE II - LINE 24"	
LOCATION	STOP BAR WHITE (FOOT)
WINDSOR ROAD	
99+55.5 LT. TO 99+90.6 LT.	37
100+10.4 RT. TO 100+42.4 RT.	34
FIRST STREET	
99+40.6 RT.	26
100+64.5 LT. & RT.	34
TOTAL	131

78008310 POLYUREA PAVEMENT MARKING TYPE II - LINE 4"				
LOCATION	DOUBLE YELLOW NARROW (FOOT)	SKIP-DASH WHITE (FOOT)	SOLID WHITE (FOOT)	LANE LINE EXTENSIONS WHITE (FOOT)
WINDSOR ROAD				
99+89.5 LT. TO 99+92.2 LT.	56			
100+09.0 RT. TO 100+11.5 RT.	56			
FIRST STREET				
100+64.5 TO 108+03.3 LT. & RT.	1877			
101+01.0 RT. TO 107+91.0 RT.		180		
105+01.0 LT. TO 107+91.0 LT.		80		
100+37.7 RT. TO 102+60.7 RT.			232	
100+64.5 LT. TO 104+78.0 LT.			829	
104+78.0 LT. TO 105+99.0 LT.				38
SUBTOTAL	1989	260	1061	38
TOTAL			3348	

78300100 PAVEMENT MARKING REMOVAL		
LOCATION	DOUBLE YELLOW (SQ FT)	SOLID WHITE (SQ FT)
WEST LEG OF WINDSOR RD.		
EAST LEG OF WINDSOR RD.	43	
100+46.0 TO 108+03.3 LT. & RT.	501	
STOP BAR - WEST LEG		73
STOP BAR - EAST LEG		75
STOP BAR - SOUTH LEG		62
STOP BAR - NORTH LEG		68
CROSS WALK - SOUTH LEG		78
CROSS WALK - EAST LEG		93
101+03.4 LT. TO 105+97.6 LT.		163
101+03.0 RT. TO 109+0.0 RT.		264
SUBTOTAL	571	876
TOTAL		1447

78008330 POLYUREA PAVEMENT MARKING TYPE II - LINE 6"	
LOCATION	CROSSWALK WHITE (FOOT)
WINDSOR ROAD	
99+49.9 LT. TO 100+38.2 LT.	173
99+67.9 RT. TO 100+54.6 RT.	167
FIRST STREET	
99+46.7 TO 99+54.7 LT. & RT.	142
100+50.5 TO 100+58.5 LT. & RT.	154
TOTAL	636

78008350 POLYUREA PAVEMENT MARKING TYPE II - LINE 12"		
LOCATION	DIAGONAL YELLOW (FOOT)	DIAGONAL WHITE (FOOT)
FIRST STREET		
104+78.0 TO 106+98.0 LT. & RT.	43	
100+69.8 RT. TO 102+60.7 RT.		104
SUBTOTAL	43	104
TOTAL		147

FILE NAME = p:\c0010461\plans\sheets\pavtmarking.dgn PLOT DATE = 2/6/2009 11:05:59 AM	DESIGNED - R.L.H.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS	SHEET NO.
	DRAWN - J.L.B.	REVISED -					7170	08-00277-00-PV	CHAMPAIGN	44	25
	CHECKED - J.T.P.	REVISED -		SCALE : NONE			SHEET NO. 25 OF 44 SHEETS			CONTRACT NO. 91397	
	DATE - 2-09	REVISED -		STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT HD-5181 (044)				