CONTRACT NO. 91397

FINAL SURVEY	SURVEYED	BY	DATE
NOTE BOOK	PLOTTED		
NO.	TEMPLATE		
	AREAS		
	AREAS CHECKED		

ORIGINAL SURVEY	SURVEYED	BY	DATE
NOTE BOOK	PLOTTED		
NO.	TEMPLATE		
	AREAS		
	AREAS CHECKED		

TEMPORARY PAVEMENT

PROPOSED ℄ FIRST STREET

101 + 75.00 — PROP. ROW — EXIST. ROW — 1:2 MAX. — 8' — 4.0% — 717.64 — STAGE 1 RT. C=4 F=2

101 + 44.50 — PROP. ROW — EXIST. ROW — 8' — 717.59 — STAGE 1 RT. C=5 F=1

101 + 00.00 — PROP. ROW — EXIST. ROW — VARIES — 717.42 — STAGE 1 RT. C=7 F=0

100 + 70.00 — 4.0% — VARIES — 717.28 — STAGE 1 RT. C=13 F=0

TEMPORARY PAVEMENT SHALL CONSIST OF HOT-MIX ASPHALT (8" THICK) AND SHALL BE CONSTRUCTED DURING STAGE 1. SEE THE STAGE CONSTRUCTION AND MAINTENANCE OF TRAFFIC PLANS FOR ADDITIONAL INFORMATION.

100 + 50.00 — VARIES — 717.26 — STAGE 1 RT. C=32 F=0

BEGIN EARTHWORK STAGE 1 RT. STA. 100+38.8 RT.

SECTION LINE — EXIST. ROW — PROP. ROW — T.C.E. — P.E.

FILE NAME = p:\c0010461\plans\sheets\stage1firstxssht.dgn	DESIGNED - R.L.H.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
PLOT DATE = 2/6/2009 11:06:04 AM	DRAWN - J.L.B.	REVISED -	
	CHECKED - J.T.P.	REVISED -	
	DATE - 2-09	REVISED -	

CROSS SECTIONS - TEMPORARY PAVEMENT

SCALE : 1" = 10' HOR, 1" = 5' VERT | SHEET NO. 36 OF 44 SHEETS | STA. 100+50.00 TO STA. 101+75.00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7170	08-00277-00-PV	CHAMPAIGN	44	36
		CONTRACT NO. 91397		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT HD-5181 (044)		

CITY OF CHAMPAIGN SECTION NO. 08-00277-00-PV CHAMPAIGN COUNTY

C0010461