#### INDEX OF SHEETS 06-12-2015 LETTING ITEM 063 STATE OF ILLINOIS

- COVER SHEET
- GENERAL NOTES
- SUMMARY OF QUANTITIES
- TYPICAL SECTIONS
- TRAFFIC CONTROL AND PROTECTION STANDARD 701402 (SPECIAL)

OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' (4.5 m) AWAY

TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY/EXPRESSWAY

APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY

PAVEMENT MARKING STRUCTURE PLANS

## **STANDARDS**

000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS 001001-02

001006

AREAS OF REINFORCEMENT BARS DECIMAL OF AN INCH AND OF A FOOT

TRAFFIC CONTROL DEVICES

635011-02

0

0

0

0

REFLECTOR MARKER AND MOUNTING DETAILS OFF-ROAD OPERATIONS MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM

701101-04

701106-02 701400-0ව

701428

701901-04

701011-04

701402-10 701-424-07

70(431-10

DEPARTMENT OF TRANSPORTATION **DIVISION OF HIGHWAYS** 

# **PROPOSED** HIGHWAY PLANS


FAI 180 (I-180) (06-3, 078-1)MBPM-2

STRUCTURAL STEEL CLEANING AND PAINTING **BUREAU COUNTY** 

C-93-148-14

## PROJECT LOCATION

STRUCTURE NUMBER 078-0001 **CARRYING FAI RT. 180 (1-180) OVER THE ILLINOIS RIVER** 1.82 MILES EAST OF IL 26 AT HENNEPIN




FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123

DISTRICT 3 (815) 434-6131

PROJECT ENGINEER JOE KANNEL P.E. UNIT CHIEF RON WOODSHANK TOWNSHIP LEEPERTOWN

CONTRACT NO. 66E12



POINT LOCATION LOCATION MAP NOT TO SCALE

(06-3, 078-1)MBPM-2 BUREAU 9

#### D-93-092-14



RURAL INTERSTATE FAI 180 (I-180) 2013 ADT 2600 75% P.V. S.U. 8,65% 16.35% M.U.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

### **GENERAL NOTES**

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENT PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY FURNISHED BASED UPON THE UNIT BID FOR THE WORK.

AS PER ARTICLE 107.20 OF THE STANDARD SPECIFICATIONS WHENEVER PUBLIC OR PRIVATE PROPERTY IS DAMAGE OR DESTROYED DUE TO THE OPERATIONS OF THE CONTRACTOR, THE CONTRACTOR SHALL, AT NO ADDITIONAL COST TO THE DEPARTMENT, RESTORE SUCH PROPERTY TO A CONDITION EQUAL TO THE EXISTING BEFORE SUCH DAMAGE OR INJURY WAS DONE BY REPAIRING, REBUILDING, OR REPLACING IT AS MAY BE DIRECTED, OR THE CONTRACTOR SHALL OTHERWISE MAKE GOOD SUCH DAMAGE OR DESTRUCTION IN AN ACCEPTABLE MANNER.

THE CONTRACTOR SHALL NOT CLOSE A LANE IN THE EASTBOUND AND WESTBOUND TRAFFIC LANES AT THE SAME TIME UNLESS APPROVED IN WRITING BY THE ENGINEER.

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE "JULIE" NUMBER IS 1-800-892-0123. A MINIMUM OF FORTY-EIGHT (48) HOURS ADVANCE NOTICE IS REQUIRED.

WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED. THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

SUITABLE ON-SITE SANITARY FACILITIES MEETING FEDERAL, STATE AND LOCAL HEALTH DEPARTMENT REQUIREMENTS SHALL BE PROVIDED AND MAINTAINED CLEAN AND IN GOOD WORKING CONDITION AND SHALL BE STOCKED WITH LAVATORY AND SANITARY SUPPLIES AT ALL TIMES DURING THE PERIOD OF THE CONTRACT.

THE FURNISHING, MAINTENANCE AND LAVATORY SUPPLIES SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE PAY ITEMS INVOLVED UNDER THIS CONTRACT.

THE EXISTING STRUCTURAL STEEL CONTAINS LEAD. THE CONTRACTOR SHOULD TAKE APPROPRIATE PRECAUTIONS TO DEAL WITH LEAD PAINT ON THIS PROJECT.

## COMMITMENTS

VAICE	11/11/2/2
PREPARED BY:	8 Banic
	DISTRICT STUDIES & PLANS ENGINEER
EXAMINED BY:	pistpict construction engineer
	May Whelly
	Pruce a. Jack
	DISTRICT OPERATIONS ENGINEER

DIE A 2 7 7015

FILE HAME =	USER NAME = patety) .	DESIGNED - ZJL	REVISED ~
cr\p=_work\pwidot\patelyj\d0491777\03660	12-shz-datasla.dgo	DRAWN - ZJL	REVISED -
	PLOT SCALE = 100,0000 17 pm,	CHECKED - RLW	REVISED -
	PLOT DATE > 3/23/2015	DATE - 8/6/14	REVISED -


SCALE

TO STA.

				CONSTR. CO
				мврм
				100% STA
		ar-northolog		BRIDGE
CODE		**********	TOTAL	0014
NO.	ITEM	UNIT	QUANTITY	S. N. 078-0
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1
67100100	MOBILIZATION	L SUM	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	275	275
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	825	825
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE). TEST LEVEL 3	EACH	1	1
70600350	IMPACT ATTENUATORS. RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1
	•			
78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	5325	5325
78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	1040	1040
70700100				
78300100	PAVEMENT MARKING REMOVAL	SO FT	2295	2295
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	1	l l
X7010410	SPEED DISPLAY TRAILER	CAL MO	1	1
Z0007/01	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. /	L SUM	1	1
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	21	21


<sup>\*</sup>SPECIALITY ITEMS

ŧ	<del></del>	<del></del>	*******************************	<del></del>			· ·		,	
1	FILE HARE =	USER MANE s pately;	DESTONED - ZJL	REVISED -			F.A.I. SECTION	COUNTY	TOTAL	SHEET
-	c1\p*. +ork\p+idot\potaly;\d9481777\03666	IZ-sht-detaile.dgn	DRAWN - ZJL	REVISED -	STATE OF ILLINOIS	SUMMARY OF QUANTITIES	RTE. SECTION	BUREAU	SHEETS	NO.
		PLOT SCALE = 100.0020 1/ in.	CHECKED - RLW	REVISED -	DEPARTMENT OF TRANSPORTATION	SOMMAN OF COMMITTES	180 (06-3, 078-1)MBPM-2	CONTRACT	<u>9</u>	3
ı		PLOT DATE = 3/23/2015	DATE - 8/6/14	REVISED -		SCALE: SHEET 1 OF 2 SHEETS STA TO STA	ILLINOIS FED. AI	PROJECT	140. 6	OE 12




## TYPICAL SECTION


EAST OF THE ILLINOIS RIVER



## TYPICAL SECTION WEST OF THE ILLINOIS RIVER


File Hare :	USER NAME 2 potely)	DESIGNED - ZJL	REVISEO -			F.A.I. SECTION	COUNTY TOTAL SHEET
st\pu,vork\puidqt\patalijj\d0401777\03668	lZ-sht-datails,dga	DRAWN - ZJL	REVISEO -	STATE OF ILLINOIS	TYPICAL SECTIONS	180 (06-3, 078-1)MBPM-2	BUREAU 9 4
	PLOT SCALE = 180.0000 '/ m.	CHECKED - RLW	REVISEO -	DEPARTMENT OF TRANSPORTATION			CONTRACT NO. 66E12
L	PLOT DATE · 3/23/2015	DATE 8/6/14	REVISEO -		SCALE: SHEET 1 OF 1 SHEETS STA, TO STA	ILLINOIS FEO. AI	D PROJECT







## TYPICAL PAVEMENT MARKINGS

FILE MAME =	USER NAME = pately;	DESIGNED - ZJL	REVISED -			F.A.I. SECTION CO	COUNTY TOTAL SHEET
ci\px_work\pxidot\patelyj\d0401777\03660	iZ-aht-datasia.dgn	DRAWN - ZJL	REVISED -	STATE OF ILLINOIS	PAVEMENT STRIPING	+115 C + 1	SHEETS NO.
	PLOT SCALE = 100.0020 1/ m.	CHECKED - RLW	REVISED -	DEPARTMENT OF TRANSPORTATION		CO	ONTRACT NO. 66E12
	PLOT DATE = 3/23/2815	DATE - 8/6/14	REVISED -		SCALE: SHEET 1 OF 1 SHEETS STA, TO STA,	ILLINOIS FEO. AID PRO.	



### **ELEVATION**





## **CROSS SECTION**

AIR MONITORS

RELOCATED AIR MONITORS

## TOTAL BILL OF MATERIAL

ITEM	UNIT	078-0001	TOTAL
CLEANING AND PAINTING STEEL BRIDGE NO. I	L SUM	1	1
CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. I	L SUM	1	1

#### GENERAL NOTES

- 1. STRUCTURE NO. 078-0001 SHALL BE DESIGNATED AS "LOCATION 1".
- 3. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF WORK; HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
- 4. THE SSPC-OP1 AND SSPC-OP2 "PAINTING CONTRACTOR CERTIFICATIONS" WILL BE REQUIRED FOR THIS PROJECT.
- A MINIMUM OF TWO AIR MONITORS SHALL BE REQUIRED FOR THIS PROJECT.
  THE SHALL FURNISH AND INSTALL THE MONITORS AS SHOWN ON PLAN
  DETAILS. (SEE THE SPECIAL PROVISION FOR "CONTAINMENT AND DISPOSAL
  OF LEAD PAINT CLEANING RESIDUES".)
- 6. CLEANING AND PAINTING OF EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISION FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES" AND AS SPECIFIED BELOW.
  - ALL EXISTING STRUCTURAL STEEL, INCLUDING BEAMS, DIAPHRAGMS, CROSS/LATERAL FRAMING WHEN PRESENT, BEARINGS, AND OTHER ASSOCIATED STEEL COMPONENTS WITHIN TEN FEET OF ABUTMENTS SHALL BE CLEANED PER NEAR WHITE BLAST CLEANING, SSPC-SPIO.
  - ALL STEEL TO BE CLEANED SHALL BE PAINTED PER THE REQUIREMENTS OF "PAINT SYSTEM 1- 0Z/E/U."
  - THE FINAL FINISH COAT FOR ALL INTERIOR STRUCTURAL STEEL BE "GRAY, MUNSELL NO. 5B 7/1".
  - 2) FINISH COAT FOR EXTERIOR FACE, BOTTOM FLANGE AND BEARING ASSEMBLIES OF THE FASCIA BEAMS SHALL BE "BLUE, MUNSELL NO. 10B 3/6.
- 7. THE CONTRACTOR SHALL BE REQUIRED TO SEQURE WASTE CONTAINERS THAT REMAIN ON THE JOB SITE. THIS WILL ENTAIL THAT ALL WASTE CONTAINERS CAN NOT BE MOVED OR OPENED DURING NON-WORKING HOURS.
- 8. WORKING DAYS SHALL BE CHARGED UNTIL THE CONTRACTOR/SUBCONTRACTOR LISCENSED TO DISPOSE OF LEAD PAINT RESIDUES HAS REMOVED THE WASTE MATERIAL FROM THE JOB SITE ACCORDING TO ALL FEDERAL, STATE AND LOCAL LAWS AND ORDINANCES. IF THE LISCENSED CONTRACTOR OR SUBCONTRACTOR FAILS TO DISPOSE OF THE LEAD PAINT RESIDUES ON OR BEFORE THE SPECIFIED COMPLETION DATE, LIQUIDATED DAMAGES SHALL BE CHARGED PER CALENDAR DAY ACCORDING TO ARTICLE 109.09 OF THE STANDARD SPECIFICATIONS UNTIL SUCH TIME THAT ALL PAINT RESIDUE MATERIALS HAVE BEEN PROPERLY REMOVED AND DISPOSED OF.

				<del></del>		
FILE NAME :	USER NAME :	DESIGNED	- :	ŽJL	REVISED	
		ORAWN	-	ZJL	REVISED	+
	PLOT SCALE : 106.0000 '/ in.	CHECKED	-	RL#	REVISED	-
	PLOT DATE = 3/26/2015	DATE	-	8/6/14	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE: \_

EXISTING	STRU	CTUR	E PLANS	FOR	F.A.I. RTE.	SECTION
CTD!!	CTUDE	NIO :	078-0001		180	(06-3, 078-11MBPM-
JINU	UIUN	. IVU.	0/0-0001			
SHEET 1	OF 3	SHEETS	STA, 50+17	TO STA, 80+97		ILLINOIS FE

RTE.	SECTION	COUNTY	SHEETS	NO.
180	(06-3, 078-11MBPM-2	SUREAU	9	7
		CONTRACT	NO. 6	6E12
	ILLINOIS FED. AIC	PROJECT		

