



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2008

SUBJECT: FAP Route 573
Section 61 HB-I-6
Kane County
Contract No. 60E17
Item No. 278, June 13, 2008 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 1 of the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provisions.
3. Revised pages 11 – 14 of the Special Provisions.
4. Revised sheets 3, 9 & 10 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm
Interim Bureau Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

TABLE OF CONTENTS

LOCATION OF IMPROVEMENT	1
DESCRIPTION OF IMPROVEMENT.....	1
MAINTENANCE OF ROADWAYS.....	1
TRAFFIC CONTROL PLAN.....	2
FINE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (DISTRICT ONE)	2
RECLAIMED ASPHALT PAVEMENT (RAP) (DISTRICT ONE).....	2
GENERAL ELECTRICAL REQUIREMENTS.....	8
GROUND ROD	10
ELECTRIC UTILITY SERVICE CONNECTION (COMED).....	14
ELECTRIC SERVICE INSTALLATION.....	15
TEMPORARY WOOD POLE, INSTALL ONLY.....	15
WIRE AND CABLE	16
CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL STRUCTURES.....	18
CLEANING AND PAINTING NEW METAL STRUCTURES.....	23
BEAM STRAIGHTENING	29
EPOXY INJECTION.....	30
STRUCTURAL STEEL REMOVAL.....	31
TEMPORARY SHORING AND CRIBBING	31
TEMPORARY SLAB SUPPORT SYSTEM.....	32
TEMPORARY PAVEMENT.....	33
TEMPORARY INFORMATION SIGNING FOR LANE CLOSURES.....	33
TRAFFIC SIGNAL SPECIFICATIONS.....	36
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC.....	81
ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE)	82
CEMENT (BDE)	85
ENGINEER'S FIELD OFFICE TYPE A (BDE)	87
EQUIPMENT RENTAL RATES (BDE).....	88
IMPACT ATTENUATORS, TEMPORARY (BDE).....	89
NOTIFICATION OF REDUCED WIDTH (BDE)	91
PAYMENTS TO SUBCONTRACTORS (BDE)	91
POLYUREA PAVEMENT MARKING (BDE).....	92
PORTLAND CEMENT CONCRETE PLANTS (BDE)	99
REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE)	100
SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE).....	101
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	104
WORKING DAYS (BDE)	105
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	105

Where ground conditions, such as rock, preclude the installation of the ground rod, the ground rod may be deleted with the approval of the Engineer.

Where a ground field of "made" electrodes is provided, such as at control cabinets, the exact locations of the rods shall be documented by dimensioned drawings as part of the Record Drawings.

Ground rod connection shall be made by exothermic welds. Ground wire for connection to foundation steel or as otherwise indicated shall be stranded uncoated bare copper in accordance the applicable requirements of ASTM Designation B-3 and ASTM Designation B-8 and shall be included in this item. Unless otherwise indicated, the wire shall not be less than No. 2 AWG.

Where connections are made to epoxy coated reinforcing steel, the epoxy coating shall be sufficiently removed to facilitate the exothermic weld.

Method Of Measurement. Ground rods shall be counted, each. Ground wires and connection of ground rods at poles shall be included in this pay item.

Basis Of Payment. This item shall be paid at the contract unit price each for **GROUND ROD**, of the diameter and length indicated which shall be payment in full for the material and work described herein.

Revised 06/05/2008

Revised 06/05/2008

Revised 06/05/2008

ELECTRIC UTILITY SERVICE CONNECTION (COMED)

Effective: January 1, 2002

Revised February 1, 2005

Description. This item shall consist of payment for work performed by ComEd in providing or modifying electric service as indicated. THIS MAY INVOLVE WORK AT MORE THAN ONE ELECTRIC SERVICE. For summary of the Electrical Service Drop Locations see the schedule contained elsewhere herein.

CONSTRUCTION REQUIREMENTS

General. It shall be the Contractor's responsibility to contact ComEd. The Contractor shall coordinate his work fully with the ComEd both as to the work required and the timing of the installation. No additional compensation will be granted under this or any other item for extra work caused by failure to meet this requirement. **Please contact ComEd, New Business Center Call Center, at 866 NEW ELECTRIC (1-866-639-3532) to begin the service connection process. The Call Center Representatives will create a work order for the service connection. The representative will ask the requestor for information specific to the request. The representative will assign the request based upon the location of project.**

The Contractor should make particular note of the need for the earliest attention to arrangements with ComEd for service. In the event of delay by ComEd, no extension of time will be considered applicable for the delay unless the Contractor can produce written evidence of a request for electric service within 30 days of execution.

Method Of Payment. The Contractor will be reimbursed to the exact amount of money as billed by ComEd for its services. Work provided by the Contractor for electric service will be paid separately as described under ELECTRIC SERVICE INSTALLATION. No extra compensation shall be paid to the Contractor for any incidental materials and labor required to fulfill the requirements as shown on the plans and specified herein.

For bidding purposes, this item shall be estimated as \$6000.

Revised 06/05/2008