

GENERAL NOTES

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

FOR NEW CONSTRUCTION, PLACE CURB RAMPS FOR SIDEWALKS (STANDARD 424001) AT ALL LOCATIONS WHERE PROPOSED SIDEWALK ABUTS CURB AT STREET ENTRANCES.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

GRANULAR MATERIALS	2.05	TONS / CU YD
SHORT TERM PAVEMENT MARKING	10	FT /100 FT OF APPLICATION

SUMMARY OF QUANTITIES		100x5T 5000	
Code No.	Item	Unit	Total
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	434
42400500	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQ FT	115
42400800	DETECTABLE WARNING	SQ FT	116
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1303
44000600	SIDEWALK REMOVAL	SQ FT	434
44003100	MEDIAN REMOVAL	SQ FT	630
44003800	MEDIAN SURFACE REMOVAL	SQ FT	4067
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	2
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1303
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3530
60624600	CORRUGATED MEDIAN	SQ FT	630
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2000
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	667
78008300	POLYUREA PAVEMENT MARKING TYPE II - LETTERS ^{AND} SYMBOLS	SQ FT	183.6
78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	1890
78008330	POLYUREA PAVEMENT MARKING TYPE II - LINE 6"	FOOT	360
78008340	POLYUREA PAVEMENT MARKING TYPE II - LINE 8"	FOOT	45
78008350	POLYUREA PAVEMENT MARKING TYPE II - LINE 12"	FOOT	1002
78008370	POLYUREA PAVEMENT MARKING TYPE II - LINE 24"	FOOT	217
78200300	PRISMATIC CURB REFLECTOR	EACH	80
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2151
X0323622	AGGREGATE BACKFILL	TON	89
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

• SPECIALTY ITEMS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: [Signature]
DISTRICT STUDIES & PLANS ENGINEER

DATE: 3-19-08

EXAMINED BY: [Signature]
DISTRICT CONSTRUCTION ENGINEER

[Signature]
DISTRICT MATERIALS ENGINEER

[Signature]
DISTRICT OPERATIONS ENGINEER

FILE NAME = c:\projects\ed03208\details.dgn	USER NAME = cororanlm	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & SUMMARY OF QUANTITIES	F.A.P. RTE. 41	SECTION (152)	COUNTY LIVINGSTON	TOTAL SHEETS 10	SHEET NO. 2
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 66764
PLOT DATE = Mar 19, 2008 - 10:46:25 AM	DATE	REVISED -								