CONTRACT NO. 68608

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	*	TAZEWELL	82	2
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

*13R-1;(9)TS;(12B)L,1-1

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS, COMMITMENTS & UTILITY STATUS
3–4. GENERAL NOTES
5–8. SUMMARY OF QUANTITIES
9–16. TYPICAL SECTIONS
17–22. SCHEDULE OF QUANTITIES
23. BENCHMARKS & RECOVERY TIES
24. LINE DIAGRAM
25. REMOVAL PLAN
26. EXISTING PLAN VIEW
27. PROPOSED PLAN VIEW
28–30. PLAN & PROFILE
31–33. STAGING
34–35. JOINT DETAIL
36. PROPOSED ISLAND DETAIL
37. PROPOSED INTERSECTION DETAIL
38–39. PROPOSED BRIDGE IMPROVEMENTS (NOT COMPLETED)
40. PAVEMENT MARKING DETAIL
41–51. TRAFFIC SIGNALS
52–62. CADD STANDARDS
63–82. X-SECTIONS STANDARDS

COMMITMENTS

COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN APPROVAL OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE. NO COMMITMENTS WERE MADE ON THIS PROJECT.

STATUS OF UTILITIES

ILLINOIS AMERICAN WATER COMPANY

OFFSET	LOCATION	TYPE OF UTILITY	TYPE OF CONFLICT	DISPOSITION
10' RT. TO 10' RT.	SECOND ST. 8+20 TO 14+85	6" WATER MAIN	RECONSTRUCTION	CAUTION
10' RT. TO 16' RT.	IL 9 /MARGARET ST 109+07 TO 113+21	6" WATER MAIN	RECONSTRUCTION	CAUTION
8' RT. TO 8' LT.	IL 9 /ANN ELIZA 109+07 TO 112+14	6" WATER MAIN	RECONSTRUCTION	CAUTION

CILCO (GAS)

OFFSET	LOCATION	TYPE OF UTILITY	TYPE OF CONFLICT	DISPOSITION
16.5' LT. TO 16.5' LT.	IL 29 /SECOND ST. 8+20 TO 13+48.1	4" GAS LINE	RECONSTRUCTION	CAUTION
4' RT. TO 16.5' LT	IL 29 /SECOND ST. 13+48.1	4" GAS LINE	RECONSTRUCTION	CAUTION
4' RT. TO 4' RT.	IL 29 /SECOND ST. 13+48.1 TO 14+51.1	4" GAS LINE	RECONSTRUCTION	CAUTION
1' RT. TO 1' RT.	IL 9 /MARGARET ST. 109+19.52 TO 113+21	2" GAS LINE	RECONSTRUCTION	CAUTION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX, COMMITMENTS & UTILITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 3/20/2008
FILE NAME = S:\GENDRAFT\STDPLNS\SQUAD9-NEW\Active Contracts\68608\IL 9 Pekin - plan01.dgn
PLOT SCALE = 185.9697 ' / IN.
USER NAME = bvcadm