- ALL ELEVATION REFER TO USGS MEAN SEA LEVEL DATUM.
- WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED. THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER AND AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. IF THE ENGINEER DECIDES TO HAVE THE CONTRACTOR RESET THE MONUMENT, THIS WORK WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04.
- THE CONTRACTOR SHALL CONTACT J.U.L.I.E. PRIOR TO ANY EXCAVATION TO HAVE ALL PUBLIC AND PRIVATE UTILITIES LOCATED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.26 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS (800) 892-0123. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED. SEE SPECIAL PROVISIONS FOR STATUS OF UTILITIES. WITH UTILITY
- ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
- THE COST OF REMOVAL OF ANY EXISTING OBSTRUCTIONS THAT INTERFERE WITH THE CONSTRUCTION WILL BE CONSIDERED INCLUDED WITH THE UNIT BID PRICE FOR EARTH EXCAVATION. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- ALL DETAILS IN THE PLANS SHALL GOVERN CONSTRUCTION OF THIS PROJECT. AND IN CASE OF CONFLICT WITH ANY STANDARD DRAWINGS INCLUDED, THE SAID DETAILS SHALL TAKE PRECEDENCE AND GOVERN.
- THE ONLY, SO-CALLED, PERMANENT SEEDING THAT SHALL BE COMPLETED IN THIS CONTRACT IS SEEDING, CLASS 2 AND CLASS 7. CLASS 2 SHALL BE USED ON ALL DISTURBED AREAS ALONG THE ACCESS ROAD / PARKING AREA EMBANKMENTS. CLASS 7 SHALL BE USED ON THE TOP OF THE ACCESS ROAD EMBANKMENTS AND AT ALL OTHER DISTURBED LOCATIONS IN THE PROJECT (DRAINAGE DITCH DEACTIVATION AND LAKE RE-ESTABLISHMENT / POND ESTABLISHMENT AREAS). DO NOT USE AG LIMESTONE, FERTILIZER, OR MULCH ON CLASS 7 SEEDING AREAS.

DRAINAGE DITCH DEACTIVATION AND LAKE RE-ESTABLISHMENT / POND ESTABLISHMENT AREAS SHALL BE NATURALLY REVEGITATED; THEREFORE, WE DO NOT WANT TEMPORARY SEEDING (HEAVY APPLICATIONS) OR PERMANENT SEEDING TO INTERFERE WITH THE NATURAL REVEGITATION PROCESS OF THE PROPOSED WETLAND AREAS. TEMPORARY EROSION CONTROL SEEDING (AT A VERY LIGHT APPLICATION - 40 LBS / ACRE) SHALL BE COMPLETED ONLY ON DISTURBED AREAS WITHIN THE SITE TO GIVE MINIMAL GROUND COVER.

PLANS HAVE BEEN DESIGNED TO TRY TO UTILIZE ALL THE EXCAVATED MATERIAL IN PROPOSED EMBANKMENT AREAS. IF EXCESS MATERIAL REMAINS AFTER THE REQUIRED EMBANKMENT IS COMPLETED, THE CONTRACTOR SHALL WASTE THE EXCESS MATERIAL ON SITE AT LOCATIONS DESIGNATED BY THE ENGINEER UNTIL ALL EXCAVATED MATERIAL IS USED.
IF NO EXCESS MATERIAL EXIST OR MATERIAL IS SHORT OF COMPLETING THE
PLAN EMBANKMENT, ADDITIONAL EXCAVATION SHALL BE COMPLETED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER TO FINISH PROPOSED EMBANKMENTS. ALL EARTHWORK IN THIS CONTRACT WILL BE PAID FOR AT THE CONTRACT UNIT BID PRICE PER CUBIC YARD FOR "EARTH EXCAVATION." NO OTHER ADDITIONAL COMPENSATION WILL BE ALLOWED IN ABIDING TO THESE LISTED REQUIREMENTS.

- DISTURBANCE TO THE SITE SHALL BE KEPT TO A MINIMUM OUTSIDE THE SHOWN CONSTRUCTION LIMITS. VEHICLES AND EQUIPMENT SHALL BE PARKED WITHIN THE PROPOSED WORK AREAS OR AT THE EXISTING BUILDING LOCATION (AT THE SW CORNER OF THE SITE NEAR THE TOWNSHIP ROAD) WHEN NOT IN USE. WE DO NOT WANT THE EXISTING WETLAND VEGITATION DISTURBED OUTSIDE THE CONSTRUCTION LIMITS. IF THE CONTRACTOR FAILS TO KEEP HIS/HER WORKERS FROM OBEYING THE ABOVE REQUIREMENT, THE RESIDENT ENGINEER WILL DETERMINE AND DEDUCT AGREED DAMAGES OF \$2,000 PER OCCURANCE FROM THE FINAL PAYMENT (PAY ESTIMATE TO DATE) AS PART OF THE UNDERSTANDING IN THIS CONTRACT. UNDERSTANDING IN THIS CONTRACT.
- 11) THE CONTRACTOR SHALL CORDINATE AND PROVIDE ACCESS TO THE TENANT FARMER OF THE SITE AT ALL TIMES. THE COST ASSOCIATED WITH THIS REQUIREMENT WILL BE CONSIDERED AS PART OF THE CONTRACT UNIT BID PRICE FOR "EARTH EXCAVATION."
- THE FIELD/RESIDENT ENGINEER SHALL CONTACT STUDIES & PLANS CONCERNING ANY MAJOR PLAN CHANGES TO MAKE SURE NO COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN, AND ALLOW IMPROVEMENTS IN THE DESIGN FOR FUTURE PROJECTS.
- ALL SEEDING IS REQUIRED TO BE COMPLETED BY OCTOBER 1ST OF EACH YEAR OF CONSTRUCTION OR BY THE CONTRACT COMPLETION DATE (WHICH EVER COMES FIRST).
- SWPPP.
- APPROVED WETLAND MITIGATION PLAN.
- DISTURBANCE TO THE SITE SHALL BE KEPT TO A MINIMUM.
- 404 PERMIT

DISTRICT SIX
EXAMINED Feb 29 2008
OPERATIONS ENGINEER
EXAMINED MAR 13 2008
PROGRAM IMPLEMENTATION ENGINEER
EXAMINED Mar 20 08
PROGRAM DEVELOPMENT ENGINEER

 LAGRANGE WETLAND BANK .. D6 WETLAND MITIGATION 3

SECTION

FILE NAME = USER NAME = woodse.i DESIGNED REVISED DRAWN - KPG REVISED CHECKED - JCN REVISED PLOT SCALE = 100.0000 '/ IN. PLOT DATE = Mar-11-2008 10:35:264M DATE REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

SCALE:

COUNTY TOTAL SHEE SHEETS NO. **GENERAL NOTES & COMMITMENTS** BROWN 174 2 CONTRACT NO. 72968 SHEET NO. OF SHEETS STA. FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT