

COUNTY	SECTION	HWY. NO.	SHEET NO.
LASALLE	08-00323-00-RS	44	5 of 6

PAVING SCHEDULE									
STA. to STA.	SURFACE WIDTH	LENGTH	AREA	BIT. MAT. (PR. CT.)	AGG. (PR. CT)	HEATER SCARIFIER	HMA ASPHALT SURF. CSE. MIX C N50	AGG. SHLDS, TY-B	SHORT-TERM PAVT
	FEET	FEET	SQ. YD.	0.1Gal/SY GAL	4#/Sq Yd TON	SQ. YD.	1 1/2" TON	2.05Ton/CuYd TON	FOOT
10+45 to 290+16	24	27,971	74,589	7458.93	149.2	74536 *	6266	2128	5594.2
290+16 to 647+82	22	35,766	87,428	8742.8	174.9	85916 *	7344	2721	7153.2
PRIVATE ENTRANCES			1,843	184.3	3.7		155 **		
FIELD ENTRANCES			581	58.14	1.2		49	465 ***	
INTERSECTIONS			2,788	278.8	5.6		234 **		
MAILBOX TURNOUTS			241	24.1	0.5		20		
PAVED SHOULDERS			352	35.214	0.7		30		
<b>TOTAL</b>			<b>167,823</b>	<b>16782</b>	<b>336</b>	<b>160452</b>	<b>14097</b>	<b>5314</b>	<b>12747</b>

MAIL BOX TURNOUT			
STATION	SIDE	WIDTH	SQ YD
51+48	LT	6'	27
98+20	LT	6'	27
157+03	RT	6'	27
197+03	RT	6'	27
205+38	RT	4'	15
280+80	RT	8'	43
296+68	RT	3'	10
297+93	RT	3'	10
345+85	RT	3'	10
415+98	LT	3'	10
547+30	LT	3'	10
573+41	LT	4'	15
590+74	LT	3'	10
<b>TOTAL</b>			<b>241</b>

HMA SURF. REM. - BUTT. JOINT		
STATION	SIDE	SQ YD
10+45 to 10+58	CL	35
271+79	LT	8
274+17	RT	139
279+47	LT	8
279+83	RT	37
283+50	LT	9
283+50	RT	9
285+55	LT	8
286+16	LT	8
286+52	RT	7
286+58	RT	7
287+14	LT	3
288+00	RT	5
425+51 to 426+51	CL	244
427+26 to 428+26	CL	244
494+63 to 495+63	CL	244
496+29 to 497+29	CL	244
528+72 to 528+97	CL	64
529+35 to 529+60	CL	64
647+42 to 647+72	CL	80
<b>TOTAL</b>		<b>1468</b>

\* SQUARE YARDAGE REFLECTS BEGINNING AND ENDING OMISSION AS WELL AS BRIDGE OMISSIONS  
 \*\* PAID FOR AS INCIDENTAL HMA SURFACE  
 \*\*\* 5 TON PER STANDARD FIELD ENTRANCE

PAVEMENT MARKING			
PAINT		PREFORMED PLASTIC PVT MRK	
YELLOW LINE 4"	WHITE LINE 4"	WHITE LINE 24"	LTR & SYM
FOOT	FOOT	FOOT	SQ FT
31714	127659	80	125

GUARDRAIL								
STATION	SIDE	SPBGR				TRAFFIC BAR TERM		FURNISHED EXCAVATION CY
		REMOVE & RE ERECT TY A	REMOVE & RE ERECT TY B	VERTICAL ADJUST TY A	VERTICAL ADJUST TY B	REMOVE & RE-ERECT TBT	GUARDRAIL REFLECTORS	
61+65 to 63+65	RT			87.5	62.5	2.0	2.0	
62+15 to 64+40	LT			87.5	62.5	2.0	2.0	
138+46 to 140+96	RT	62.5	52.5		25.0	2.0	0.0	44.0
139+34 to 143+21	LT	287.5	25.0		25.0	2.0	2.0	44.0
158+00 to 161+62	RT			237.5	85.0	2.0	2.0	
158+80 to 162+55	LT			225.0	85.0	2.0	2.0	
424+88 to 427+88	RT	150.0				2.0	2.0	200.0
425+11 to 428+86	LT	225.0				2.0	2.0	200.0
493+00 to 496+22	RT	250.0				2.0	2.0	550.0
495+00 to 496+22	LT	50.0				2.0	0.0	150.0
637+94 to 640+69	LT	183.0			42.0	2.0	2.0	300.0
638+02 to 640+77	RT	183.0			42.0	2.0	2.0	300.0
<b>TOTAL</b>		<b>1391.0</b>	<b>77.5</b>	<b>637.5</b>	<b>429.0</b>	<b>24.0</b>	<b>20.0</b>	<b>1788.0</b>

HMA SURF. REM. - 1 1/2"		
STATION	SIDE	SQ YD
426+51 to 427+26	CL	267
495+63 to 496+29	CL	220
<b>TOTAL</b>		<b>487</b>

# SCHEDULES