CO053

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108108	1/C #8 5KV UG CABLE	L.F.	13,858	
AR108158	1/C #8 5KV UG CABLE IN UD	L.F.	3,544	
AR110014	4" DIRECTIONAL BORE	L.F.	160	
AR110204	4" PVC DUCT, DIRECT BURY	L.F.	181	
AR110214	4" STEEL DUCT, DIRECT BURY	L.F.	26	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	377	
AR110506	6-WAY CONCRETE ENCASED DUCT	L.F.	1,006	
AR110610	ELECTRICAL HANDHOLE	EA.	2	
AR110710	ELECTRICAL MANHOLE	EA	2	
AR110715	ELECTRICAL MANHOLE-SPECIAL	EA	4	
AR110901	CONCRETE DUCT REMOVAL	L.F.	387	
AR110907	REMOVE ELECTRICAL MANHOLE	EA	2	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	259	
AR501910	REMOVE & REPLACE PCC PAVEMENT	S.Y.	24	
AR510510	TIE DOWN	EA.	2	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	95	
AR754924	REPLACE COMB. CURB & GUTTER	L.F.	8	
AR800405	INSTALL TEMPORARY LIGHTING	L.S.	1	
AR800439	DUCT INTERFACE TO EXISTING MANHOLES	L.S.	1	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	EXISTING UTILITY PLAN
5	PROPOSED PAVEMENT PREPARATION PLAN
6	PROPOSED PAVEMENT PREPARATION PLAN NOTES
7	PROPOSED ELECTRICAL DUCT REMOVAL PLAN
8	PROPOSED ELECTRICAL DUCT REMOVAL NOTES
9	PROPOSED ELECTRICAL DUCT PLAN
10	PROPOSED ELECTRICAL DUCT DETAILS
11	PROPOSED ELECTRICAL DUCT DETAILS AND NOTES
12	PROPOSED HOMERUNS FOR RUNWAY 11-29, TAXIWAY LIGHTING CIRCUITS 1, 2, & 4
13	PROPOSED HOMERUNS FOR TAXIWAY LIGHTING CIRCUITS 3, 5, & 6
14	PROPOSED HOMERUNS FOR RUNWAY 6-24, TAXIWAY LIGHTING CIRCUITS 3A & 7
15	ELECTRICAL MANHOLE, HANDHOLE, DUCT, AND CABLING NOTES
16	PROPOSED ELECTRICAL DETAILS SHEET 1
17	PROPOSED ELECTRICAL DETAILS SHEET 2
18	PROPOSED ELECTRICAL DETAILS SHEET 3
19	4'x4'x4' AIRPORT MANHOLE
20	4'x4'x4' ELECTRICAL MAHHOLE
21	ELECTRICAL NOTES SHEET 1
22	ELECTRICAL NOTES SHEET 2

DATE	REVISION	BY

COLES COUNTY AIRPORT AUTHORITY

COLES-CUMMINS MEMORIAL AIRPORT

A.I.P. PROJ.: 3-17-0066-B20

IL PROJ.: MTO-3762

Hi Project No. 07A0101D 0800

Filename R-002FLP.DWG

Scale NOT TO SCALE

Date 04/04/08

LAYOUT	KNL	03/31/08
DRAWN	MV	03/31/08
REVIEWED	CAH	04/03/08

HANSON

Hanson Professional Services Inc.
1525 S. Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

REPLACE ELECTRICAL DUCT IN FRONTAL AREA

SUMMARY OF QUANTITIES AND INDEX TO SHEETS

2

MAY 14, 2008 10:44 AM KINCA00394
I:\AIRPORTS\COLES\07A0101\CAD\SHEETS\R-002FLP.DWG - Layout1