

| CODE NO. | ITEM                                                        | UNIT   | TOTAL QUANTITY | URBAN                   |
|----------|-------------------------------------------------------------|--------|----------------|-------------------------|
|          |                                                             |        |                | CONSTR. CODE            |
|          |                                                             |        |                | 100% STATE              |
|          |                                                             |        |                | ROADWAY<br>0014<br>S.N. |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT)                           | TON    | 0.5            | 0.5                     |
| 40600300 | AGGREGATE (PRIME COAT)                                      | TON    | 2              | 2                       |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT       | SQ YD  | 614            | 614                     |
| 40600990 | TEMPORARY RAMP                                              | SQ YD  | 123            | 123                     |
| 40603540 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70<br>POLYMERIZED | TON    | 61             | 61                      |
| 50102400 | CONCRETE REMOVAL                                            | CU YD  | 17             | 17                      |
| 50157300 | PROTECTIVE SHIELD                                           | SQ YD  | 65             | 65                      |
| 50300255 | CONCRETE SUPERSTRUCTURE                                     | CU YD  | 19             | 19                      |
| 50300260 | BRIDGE DECK GROOVING                                        | SQ YD  | 721            | 721                     |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED                            | POUND  | 2800           | 2800                    |
| 50800515 | BAR SPLICERS                                                | EACH   | 24             | 24                      |
| 52000110 | PREFORMED JOINT STRIP SEAL                                  | FOOT   | 123            | 123                     |
| 67100100 | MOBILIZATION                                                | L SUM  | 1              | 1                       |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601             | L SUM  | 1              | 1                       |
| 70106800 | CHANGEABLE MESSAGE SIGN                                     | CAL MO | 6              | 6                       |
| 70200100 | NIGHTTIME WORK ZONE LIGHTING                                | L SUM  | 1              | 1                       |
| 70300100 | SHORT TERM PAVEMENT MARKING                                 | FOOT   | 100            | 100                     |

| CODE NO.   | ITEM                                                                    | UNIT  | TOTAL QUANTITY | URBAN                   |
|------------|-------------------------------------------------------------------------|-------|----------------|-------------------------|
|            |                                                                         |       |                | CONSTR. CODE            |
|            |                                                                         |       |                | 100% STATE              |
|            |                                                                         |       |                | ROADWAY<br>0014<br>S.N. |
| 70301000   | WORK ZONE PAVEMENT MARKING REMOVAL                                      | SQ FT | 34             | 34                      |
| 70400100   | TEMPORARY CONCRETE BARRIER                                              | FOOT  | 530            | 530                     |
| 70400200   | RELOCATE TEMPORARY CONCRETE BARRIER                                     | FOOT  | 530            | 530                     |
| 70600255   | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2 | EACH  | 1              | 1                       |
| 70600322   | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2  | EACH  | 1              | 1                       |
| * 78001120 | PAINT PAVEMENT MARKING - LINE 5"                                        | FOOT  | 750            | 750                     |
| 78300200   | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL                               | EACH  | 2              | 2                       |
| X6030205   | FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)                              | EACH  | 1              | 1                       |
| X7010222   | TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21 (SPECIAL)               | L SUM | 1              | 1                       |
| X7010228   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 (SPECIAL)               | L SUM | 1              | 1                       |
| X7200201   | WIDTH RESTRICTION SIGNING                                               | L SUM | 1              | 1                       |
| Z0012130   | BRIDGE DECK SCARIFICATION, 3/4"                                         | SQ YD | 728            | 728                     |
| Z0012164   | BRIDGE DECK MICROSILICA CONCRETE OVERLAY, 2-1/2"                        | SQ YD | 728            | 728                     |
| Z0016001   | DECK SLAB REPAIR (FULL DEPTH, TYPE I)                                   | SQ YD | 2              | 2                       |
| Z0016002   | DECK SLAB REPAIR (FULL DEPTH, TYPE II)                                  | SQ YD | 43             | 43                      |

\* SPECIALTY ITEM

|             |                                                                                   |            |           |                                                   |                       |                           |            |          |                 |              |
|-------------|-----------------------------------------------------------------------------------|------------|-----------|---------------------------------------------------|-----------------------|---------------------------|------------|----------|-----------------|--------------|
| FILE NAME * | USER NAME * dudleybm                                                              | DESIGNED - | REVISED - | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.P.<br>RTE.            | SECTION    | COUNTY   | TOTAL<br>SHEETS | SHEET<br>NO. |
|             | D:\OPERATIONS\Bridges\Plans\CAD\72685 - B548198 overlay\Complete Plans and TC.dgn | DRAWN -    | REVISED - |                                                   |                       | 67                        | (1072) BDR | SANGAMON | 23              | 3            |
|             | PLOT SCALE * 40.0000' / in.                                                       | CHECKED -  | REVISED - |                                                   |                       | CONTRACT NO. 72685        |            |          |                 |              |
|             | PLOT DATE * Apr-09-2014 02:01:44PM                                                | DATE -     | REVISED - |                                                   |                       | ILLINOIS FED. AID PROJECT |            |          |                 |              |
| Default     |                                                                                   |            |           |                                                   | SCALE:                | SHEET                     | OF         | SHEETS   | STA.            | TO STA.      |