

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
				100% STATE	100% STATE	100% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0005	0021	0005
				URBAN		
70300241	TEMPORARY PAVEMENT MARKING - LINE 6"- PAINT	FOOT	4512	4512	0	0
70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	FOOT	4224	4224	0	0
70300281	TEMPORARY PAVEMENT MARKING - LINE 24"- PAINT	FOOT	690	690	0	0
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	1905	1905		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	64.1	64.1	0	0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1905	1905	0	0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1504	1504	0	0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1408	1408	0	0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	230	230	0	0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	90	90	0	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	90	90	0	0
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	3312	3312	0	0
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA	FOOT	96	0	96	0
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	0	2	0
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1226	0	1226	0
						0
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	198	0	198	0
* 87900200	DRILL EXISTING HANDHOLE	EACH	8	0	8	0
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1750	0	1750	0
						0
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	0	2	0
89502376	REBUILD EXISTING HANDHOLE	EACH	1		1	
X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1	0	0
						0
X1400378	PEDESTRIAN POST, 5 FT.	EACH	8		8	1
* X1400367	PEDESTRIAN SIGNAL POST, 10 FT.	EACH	12	0	12	

[illegible]

MODEL: SOQ 2A-1 [Sheet]
FILE NAME: c:\pw work\pwwork\abebawa\d1037488\d105425-sht-SOQ.dgn

USER NAME = Addis_Abebew	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 3/21/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES				
SCALE:	SHEET SOQ 2A-10F	SHEETS	STA.	TO STA.

1 REVISED SHEET 6/2/2025

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3520	2024-1022-RS	COOK	25	4
CONTRACT NO. 62X62				
ILLINOIS		FED. AID PROJECT		