



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 27th, 2025

SUBJECT FAI Route 80(I-80)
Section 2024-1057-DM
Will County
Contract No. 62X99

Item No. 025, June 13th, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised pages 1, 11, and 14 of the Special Provisions.
3. Revised sheets 1-6, 8-9, 15-21, and 26 of the plans.
4. Added sheets 21A-B and 32A-B to the plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1 2022, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of FAI Route 80(I-80), Section 2024-1057-DM, Will County, Contract No. 62X99 and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

FAI Route 80(I-80)
Section 2024-1057-DM
Will County
Contract No. 62X99

LOCATION OF IMPROVEMENT

The project removal buildings are located in the City of Joliet, in the vicinity of FAI Route 80 (Interstate 80) and Des Plaines River.

DESCRIPTION OF IMPROVEMENT

The work consists of building demolition for eleven (11) residential and/or commercial parcels and out buildings as shown on the plans. Each parcel removal will include removing any structure above and below the ground, including the main building frames, attached and detached buildings, facilities, and filling of basements. It will also include the removal of fences, sidewalks and driveways, utilities, and trees within the parcels' limits. Interim grading and seeding will also take place in preparation for the final Des Plaines River contract.

BUILDING REMOVAL WITH ASBESTOS ABATEMENT (BDE)

Effective: September 1, 1990

Revised: August 1, 2022

Description. This work shall consist of the removal and disposal of building(s), including all foundations, retaining walls, and piers, down to a plane 1 ft (300 mm) below the ultimate bottom of building elevation or proposed bottom of construction elevation. The building(s) are identified as follows:

<u>Bldg. No.</u>	<u>Parcel No.</u>	<u>Location</u>	<u>Description</u>
1	1P10053	603 S Raynor Ave, Joliet, IL 60436	1 Story Frame Residence
2	1P10100	610 Jasper St, Joliet, IL 60436	1 Story Frame Residence and Frame Garage
3	1P10102	606 Jasper St, Joliet, IL 60436	1 Story Frame Residence and Frame Garage
5	1P10109	511 Market St, Joliet, IL 60436	1 Story Frame Residence and Concrete Block Garage
6	1P10130	613 Kiep Ave, Joliet, IL 60436	1-1/2 Story Brick Residence and Frame Garage
7	1P10132	208 Lucas St, Joliet, IL 60436	1-1/2 Story Frame Residence and Frame Garage
8	1P10138	601 Water St, Joliet, IL 60436	1 Story Frame/Masonry Residence
9	1P10158	521 S Joliet St, Joliet, IL 60436	2 Story Brick Residence and 2 Masonry Garages
10	1P10104	504 Rock St, Joliet, IL 60436	1 Story Frame and Masonry Residence and Frame Shed
11	1P10142	611 Water St, Joliet, IL 60436	1 Story Frame Residence and Concrete Block Garage with Basement
12	1P10145	602 Water St, Joliet, IL 60436	2 Story Frame Residence and Frame Garage with Basement

Submittals that shall be made upon completion of abatement work:

- (f) Copies of waste chain-of-custodies, trip tickets, shipping manifests, or disposal receipts for asbestos waste materials removed from the work area.
- (g) Copies of each day's work site entry logbook with information on worker and visitor access.
- (h) Logs documenting filter changes on respirators, HEPA vacuums, negative pressure ventilation units, and other engineering controls.
- (i) Test results of any bulk material analysis and air sampling data collected during the abatement including results of any on-site testing by any federal, state, or local agency.

Any holes, such as basements, shall be backfilled according to Article 502.10.

Basis of Payment. This work will be paid for at the contract lump sum unit price for BUILDING REMOVAL NO. 1, 2, 3, 5, 6, 7, 8, 9, 10, 11, and 12.

Removal and disposal of friable ACBM will be paid for at the contract lump sum unit price for REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1, 2, 3, 11, and 12

Removal and disposal of non-friable ACBM will be paid for at the contract lump sum unit price for REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO 1, 2, 3, 5, 6, 7, 8, 9, 10, 11, and 12.