

MODEL: SQQ-3 [Sheet]
FILE NAME: c:\pw_work\pwid\card.johnson@illinois.gov\d0858453\D67263 Sht- SQQ.dgn

				6-60130-0000	6-60130-0000	6-60130-0100	6-60130-0200
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	BRIDGE	SAFETY
				0005	0047	0047	0021
				RURAL	069-0017	069-0065	RURAL
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	26,600	26,600			
60624600	CORRUGATED MEDIAN	SQ FT	2,297	2,297			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	69	69			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8			
63200310	GUARDRAIL REMOVAL	FOOT	522	522			
					1		
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	30,290				30,290
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	11			1
67100100	MOBILIZATION	L SUM	1	0.8			0.2
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1			1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			

* SPECIALTY ITEM

* - INDICATES PAY ITEM REQUIRES A SPECIAL PROVISION

1 REVISED 5-28-2025

USER NAME = carl.johnson	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 4/3/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 3 OF 6 SHEETS STA TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(1115BDR, 116SR)RS-5, 124RS-8	MORGAN	69	5
CONTRACT NO. 72263				
ILLINOIS FED. AID PROJECT				

MODEL: SQO 5 [Sheet]
FILE NAME: c:\paw_work\pawidolcard.johnson@illinois.gov\d0858453\D67263 Sht- SQO.dgn

					6-60130-0000	6-60130-0000	6-60130-0100	6-60130-0200
					80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	BRIDGE	SAFETY
				0005		0047	0047	0021
				RURAL		069-0017	069-0065	RURAL
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	640		640			
* 78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	23		23			
* 78200020	CURB REFLECTORS	EACH	211		211			
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	632	632			
	78300201	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	871	871			
* X0325748	ACRYLIC COATING	SQ YD	68			68		
* X0325749	FIBER WRAP	SQ FT	304			304		
* X2020060	EXCAVATING AND GRADING EXISTING SHOULDER, (SPECIAL)	UNIT	299					299
* X2020110	GRADING AND SHAPING SHOULDERS	UNIT	299					299
* X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	26,600		26,600			
* X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	2,297		2,297			
* * X6310214	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	2		2			
* X6320100	GUARDRAIL REMOVAL (SPECIAL)	FOOT	164		164			
* * X6330725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	50		50			

* SPECIALTY ITEM

* - INDICATES PAY ITEM REQUIRES A SPECIAL PROVISION

 REVISED 5-28-2025

	USER NAME = carl.johnson	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					*	(1115BDR, 116SR)RS-5, 124RS-8	MORGAN	69	7
		CHECKED -	REVISED -					CONTRACT NO. 72263				
	PLOT DATE = 4/3/2025	DATE -	REVISED -		SCALE:	SHEET 5	OF 6	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	

MODEL - Schedule of Quantities-15 [Sheet]
FILE NAME: c:\p\work\pilot\carl.johnson@illinois.gov\d0584531D672263 Sht - Schedule of Quantities.dgn

STATIONING			SIDE	GUARDRAIL										
				63000001	63100045	63100085	63100167	63200310	64300260	72501000	X6310214	X6320100	X6330725	X6331007
				STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	GUARDRAIL REMOVAL	IMPACT ATTENUATORS (FULLY REDIRECTIVE), TEST LEVEL 3	TERMINAL MARKER - DIRECT APPLIED	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	GUARDRAIL REMOVAL (SPECIAL)	STELL PLATE BEAM GUARDRAIL (SHORT RADIUS)	REMOVAL & REPLACEMENT OF STEEL PLATE BEAM GUARDRAIL, RAIL ELEMENT
				(FOOT)	(EACH)	(EACH)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)	(FOOT)	(FOOT)	(FOOT)
US 67														
RT STA 658+96.1	TO	RT STA 659+46.1	RT				1	50		1				
RT STA 659+46.1	TO	RT STA 659+58.5	RT	12.5				11.9						
RT STA 659+58.5	TO	RT STA 660+08.5	RT				1	50		1				
RT STA 660+35.1	TO	RT STA 660+85.4	RT				1	42.5		1				
LT STA 660+59.6	TO	LT STA 661+02.3	LT								44			
LT STA 660+62.6	TO	LT STA 660+98.3	LT						1					
LT STA 660+79.4	TO	LT STA 661+02.3	LT							1				
RT STA 660+85.4	TO	RT STA 661+22.8	RT			1					37.5			
LT STA 662+05.4	TO	LT STA 662+48.1	LT								45.4			
LT STA 662+05.4	TO	LT STA 662+38.5	LT							1				
RT STA 662+18.1	TO	RT STA 662+62.7	RT			1					37.5			
LT STA 662+19.6	TO	LT STA 662+55.3	LT						1					
RT STA 662+62.7	TO	RT STA 662+71.1	RT	8.4				8.4						
RT STA 662+71.1	TO	RT STA 663+21	RT				1	50		1				
LT STA 662+72.4	TO	LT STA 663+42.3	LT					50						
LT STA 662+83.7	TO	LT STA 663+32.3	LT				1			1				
LT STA 663+42.3	TO	LT STA 663+53.6	LT					11.3						
LT STA 663+33.6	TO	LT STA 663+83.6	LT				1	50		1				
RT STA 663+51.4	TO	RT STA 664+01.4	RT				1	50		1				
RT STA 664+01.4	TO	RT STA 664+49.4	RT	48				48						
LT STA 664+12.2	TO	LT STA 664+28.7	LT		1			50				25		
LT STA 664+28.7	TO	LT STA 664+69.7	LT										40	
RT STA 664+49.4	TO	RT STA 664+62.5	RT										13.5	
RT STA 664+62.5	TO	RT STA 665+12.9	RT				1	50		1				
LT STA 664+69.7	TO	LT STA 664+88.1	LT		1			50				25		
TOTAL				68.9	1	2	8	522.1	2	8	2	164.4	50	53.5

CONCRETE PAD FOR CRASH ATTENUATORS				
STATIONING			LENGTH	48300300
				PORTALND CEMENT
				CONCRETE SHOULDERS, 8" (SQ YD)
LT STA 660+62.1	TO	LT STA 660+99.1	37	25.1
LT STA 662+18.8	TO	LT STA 662+55.8	37	25.1
TOTAL				50.2

 REVISED SHEET 5-28-2025

	USER NAME = carl.johnson	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES					F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -							*	(1115BDR, 116SR)RS-5, 124RS-8	MORGAN	138	29
		CHECKED -	REVISED -							CONTRACT NO. 72263				
	PLOT DATE = 4/29/2025	DATE -	REVISED -		SCALE:	SHEET 6	OF 6	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			