

MODEL: SQO 6 [Sheet]
FILE NAME: c:\pwworking\adamsc594546372AMT_SQO.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	6-01106-0000	6-01106-0000	6-00869-0000
				ADAMS	PIKE	ADAMS
				ROADWAY	ROADWAY	BOX CULVERT
				0005	0005	0004
				RURAL	RURAL	001-7193
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1		
60500060	REMOVING INLETS	EACH	1	1		
60600095	CLASS 51 CONCRETE (OUTLET)	CU YD	340	107.7	232.3	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1,656	618	1,038	
* 63000360	LONG-SPAN GUARDRAIL OVER CULVERT, 18 FT 9 IN SPAN	FOOT	19			19
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	11	5	6	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	5	11	2
67100100	MOBILIZATION	L SUM	1	0.3	0.4	0.3
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	9	2	7	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1			1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.3	0.7	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.3	0.7	

* - INDICATES PAY ITEM REQUIRES A SPECIAL PROVISION

* SPECIALTY ITEM

REV - MS

USER NAME = eed\kem	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN -	REVISED -						745	(107RS-8,CR, 108RS-5)DR	**	119	9
	CHECKED -	REVISED -						CONTRACT NO. 72M61				
PLOT DATE = 3/27/2025	DATE -	REVISED -						ILLINOIS FED AID PROJECT				
				SCALE:	SHEET 5	OF 8	SHEETS	STA.	TO STA.			

** ADAMS, PIKE

GUARDRAIL TREATMENT

STATION TO STATION	OFFSET	63000001	63100087	63100167	X6320100	72501000	78200005
		SPBGR TY A 6' POSTS (FOOT)	TRAFFIC BARRIER TERMINAL TY 6A (EACH)	TRAFFIC BARRIER TERMINAL TY 1, SP, TAN (EACH)	GUARDRAIL REMOVAL (SPECIAL) (FOOT)	TERMINAL MARKER (EACH)	GUARDRAIL REFLECTORS TY A (EACH)
1421+05.25 TO 1422+26.71	LT	34.0	1	1	123.00	1	2
1421+23.25 TO 1422+51.15	RT	40.4	1	1	127.00	1	2
1422+65.17 TO 1423+92.75	LT	40.1	1	1	128.40	1	2
1422+89.02 TO 1424+10.75	RT	34.2	1	1	121.00	1	2
STA EQ 1464+83.78 BK = 1464+91.92 AH							
1461+85.92 TO 1466+55.66	RT	469.7		1	464.00	1	6
ADAMS/PIKE COUNTY LINE 1509+60.71							
1511+24.75 TO 1513+12.25	RT	100.00	1		187.50		2
1511+87.51 TO 1513+12.53	LT	37.52	1		125.00		2
1514+91.00 TO 1516+16.00	RT	37.50	1	1	187.50	1	2
1514+91.00 TO 1516+78.50	LT	100.00	1	1	125.00	1	3
STA EQ 1625+64.93 BK = 1625+78.75 AH							
1639+60.58 TO 1641+48.08	RT	187.50		1	187.50	1	3
1640+51.92 TO 1642+39.42	LT	187.50		1	187.50	1	3
1786+56.00 TO 1788+56.00	RT	200.00		1	200.00	1	3
1786+97.00 TO 1788+84.50	LT	187.50		1	187.50	1	3
ADAMS CO. TOTAL		618	4	5	963	5	14
PIKE CO TOTAL		1,038	4	6	1,388	6	21
TOTALS		1,656	8	11	2,351	11	35

MISC SCHEDULE

IL 104 (FAP 745)		21400100	28100201	28100205	542D0217	Z0012500	Z0021904	59300100
LOCATION		GRADING & SHAPING DITCHES (FOOT)	STONE RIPRAP, CLASS A1 (TON)	STONE RIPRAP, CLASS A3 (TON)	PIPE CULVERTS CLASS D TYPE 1 - 12" (FOOT)	CONCRETE CURB REPAIR (FOOT)	SILICONE JOINT SEALER (FOOT)	CONTROLLED LOW-STRENGTH MATERIAL (CU YD)
STA. 1426+14 LT to STA. 1428+50 LT		236						
* STA. 1472+55	20' LT	100	1.00	1.00				
* STA. 1488+50	28' LT	100	1.00	1.00				
* STA. 1490+70	28' LT	100	1.00	1.00				
ADAMS/PIKE COUNTY LINE 1509+60.71								
* STA. 1541+88	40' LT	100	1.00	1.00				
* STA. 1573+30	85' LT	100	1.00	1.00				
* STA. 1574+50	55' LT	100	1.00	1.00				
* STA. 1582+05	29' LT	100	1.00	1.00				
* STA. 1641+20	20' LT	100	1.00	1.00				
* STA. 1695+00	20' LT	100	1.00	1.00				
STA. 1946+81 LT SN 075-0512				10.00	20.00	2.50	5.00	3.00
STA. 1946+81 RT SN 075-0512						2.50	5.00	
SUBTOTAL ADAMS CO. =		536	3	3				
SUBTOTAL PIKE CO. =		600	6	16	20	5	10	3
TOTALS =		1,136		19	20	5	10	3

* AT THESE LOCATIONS, RR1 IS TO BE USED FOR EROSION AREAS AT HEADWALL. THE FLOWLINE SHALL BE RE-ESTABLISHED AND RR3 IS TO BE PLACED IN THE FLOWLINE. ALL QUANTITIES ESTIMATED.

USER NAME = eadkern	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 3/27/2025	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET 7 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
745	(107RS-8,CR, 108RS-5)DR	**	119	29
CONTRACT NO. 72M61				
ILLINOIS FED. AID PROJECT				

** ADAMS, PIKE