KANKAKEE VALLEY AIRPORT AUTHORITY KANKAKEE, ILLINOIS

CONSTRUCTION PLANS FOR GREATER KANKAKEE AIRPORT

REHABILITATE TAXIWAY A - PHASE 1

ILLINOIS PROJECT: IKK-5198 S.B.G. PROJECT: 3-17-SBGP-TBD

APRIL 18, 2025



RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO A D D I T I O N A L C O S T T O T H E C O N T R A C T . CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811 Copyright CMT, Inc 24007098-00 CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS License No. 184-000613 D. Ryle Pealody SUBMITTED BY D. KYLE PEABODY, P.E. APRIL 18, 2025 DATE ____ ANKAKEE VALLEN APPROVED BY JEFF BENOIT - AIRPORT MANAGER DATE

JULIE

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUNU UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES, PRIOR TO CONSTRUCTION, THE

CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS, OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING

SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED ANY SUCH UTILITY OR SERVICES SHALL RE

JOINT UTILITY LOCATING

www.illinois1call.com

INFORMATION FOR EXCAVATORS

8f

what's below

Call before you dig.

KA054 TOTAL SHEETS = 26

RUNWAY 4/22

DESIGN AIRCRAFT APPROACH CATEGORY D

RUNWAY 16/34

DESIGN AIRCRAFT APPROACH CATEGORY B

TAXIWAY A, A2, B, A3, A4, A5, D, H

TAXIWAY DESIGN GROUP 2A AND 2B

KANKAKEE VALLEY AIRPORTY AUTHORITY GREATER KANKAKEE AIRPORT

SECTION: 21 RANGE: R 12 E TOWNSHIP: T 30 N COUNTY: KANKAKEE TOWNSHIP: OTTO

UNICOM RADIO FREQUENCY - 123.0

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS AND SUMMARY OF QUANTITIES
- 3 SITE PLAN AND PROJECT CONTROL PLAN
- 4 SEQUENCE OF CONSTRUCTION 1
- 5 SEQUENCE OF CONSTRUCTION 2
- 6 SEQUENCE OF CONSTRUCTION 3
- 7 SEQUENCE OF CONSTRUCTION PLAN NOTES AND DETAILS 1
- 8 SEQUENCE OF CONSTRUCTION PLAN NOTES AND DETAILS 2
- 9 STORM WATER POLLUTION PREVENTION PLAN
- 10 SWPPP NOTES AND DETAILS
- 11 TYPICAL SECTIONS AND PAVEMENT REMOVAL DETAILS
- 12 EXISTING CONDITIONS AND REMOVALS TAXIWAY A SHEET 1
- 13 EXISTING CONDITIONS AND REMOVALS TAXIWAY A SHEET 2
- 14 EXISTING CONDITIONS AND REMOVALS TAXIWAY A SHEET 3
- 15 EXISTING CONDITIONS AND REMOVALS TAXIWAY B
- 16 PLAN AND PROFILE TAXIWAY A SHEET 1
- 17 PLAN AND PROFILE TAXIWAY A SHEET 2
- 18 PLAN AND PROFILE TAXIWAY A SHEET 3
- 19 PLAN AND PROFILE TAXIWAY B
- 20 PLAN AND PROFILE TAXIWAY A2 AND TAXIWAY B
- 21 INTERSECTION GRADING DETAILS 1
- 22 INTERSECTION GRADING DETAILS 2
- 23 PAVEMENT MARKING PLAN 1
- 24 PAVEMENT MARKING PLAN 2
- 25 PAVEMENT MARKING DETAILS
- 26 PAVING TABLES

SUMMARY OF QUANTITIES				
ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
AR150510	ENGINEER'S FIELD OFFICE	L SUM	1	
AR150520	MOBILIZATION	L SUM	1	
AR152480	SHOULDER ADJUSTMENT	SQ YD	5,275	
AR152511	SUBGRADE REPAIR	SQ YD	310	
AR208910	REMOVE & REPLACE AGGREGATE BASE	SQ YD	470	
AR401610	BITUMINOUS SURFACE COURSE	TON	3,300	
AR401620	BIT. SURFACE COURSE, LEVELING	TON	930	
AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1	
AR401650	BITUMINOUS PAVEMENT MILLING	SQ YD	28,135	
AR401915	REM & REP BIT PAVEMENT - TYPE A	SQ YD	800	
AR401916	REM & REP BIT PAVEMENT - TYPE B	SQ YD	1,030	
AR403673	REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	800	
AR603510	BITUMINOUS TACK COAT	GALLON	3,440	
AR620520	PAVEMENT MARKING-WATERBORNE	SQ FT	8,850	
AR620525	PAVEMENT MARKING-BLACK BORDER	SQ FT	8,210	
AR620900	PAVEMENT MARKING REMOVAL	SQ FT	920	
AR901510	SEEDING	ACRE	1.0	
AR908515	HEAVY-DUTY HYDRAULIC MULCHING	ACRE	1.0	



CONSULTANTS

IL. CONTRACT: KA054 IL. LETTING ITEM: 08A IL. PROJECT: IKK-5198 S.B.G. PROJECT: 3-17-SBGP-TBD

REHABILITATE TAXIWAY A -PHASE 1

FINAL

APRIL 18, 2025

OWNER



	_		
MADIZ	DATE	DESCRIPTION	
WIARK	DATE	DESCRIPTION	
AIP PF	ROJECT	NO. 3-17-SBGP-TBD	
IL PRO	DJECT N	O. IKK-5198	
CMT F	ROJEC	NO: 24007098-00	
CAD D	WG FILI	3:	
DESIG	NED BY	: EJR	
DRAW	DRAWN BY: JRO		
CHEC	KED BY:	DKP	
APPR	OVED B	/: DKP	
COPY	RIGHT:		
SHEE	T TITLE		
IN	DE	OF SHEETS	
A٨	1D (SUMMARY OF	

of 26

QUANTITIES

SHEET





tath: K:\KankakeeAp/24007039-00_RehabTxyAPh1\Draw\Sheets\IKK Rehab Txy A - Sequence of Construction.dw





GENERAL NOTES

- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS WHILE MAINTAINING AIBCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT MANAGER AND RESIDENT ENGINEER AND BE APPROVED BY THE DIVISION OF AERONAUTICS AND FEDERAL AVIATION ADMINISTRATION.
- 2. ALL OPERATIONS SHALL BE IN CONFORMANCE WITH AC 150/5370-2G (LATEST EDITION) OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION
- 3. CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE/STAGING AREA WHEN CONSTRUCTION IS NOT IN PROGRESS.
- THE AIRPORT MANAGER IN CONSULTATION WITH THE RESIDENT ENGINEER SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING SEQUENCE AS IT RELATES TO PEDESTRIAN, VEHICULAR AND AIRCRAFT SAFETY.
- 5. ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A HAUL BOAD OR STORAGE AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER. THE COST OF MAINTAINING, REPAIRING OR CONSTRUCTING THESE PAVEMENTS AND AREAS SHALL BE INCIDENTAL TO THE CONTRACT. EXISTING AREAS OUTSIDE THE PROJECT LIMITS WHICH ARE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT MANAGER.
- 6. THE CONTRACTOR SHALL KEEP ALL TRUCKS, FOUIPMENT AND MATERIALS OFF OF THE EXISTING TAXIWAYS, APPONS AND RUNWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE RESIDENT ENGINEER.
- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE LIGHTING SHALL BE AS APPROVED BY THE RESIDENT ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGH SAFETY. CONTRACTOR'S WORK HOURS SHALL BE IN ACCORDANCE WITH LOCAL ORDINANCES.
- 8. THE CONTRACTOR WILL BE REQUIRED TO HAVE A SWEEPER AVAILABLE FOR USE AT ALL TIMES. WHEN ACTIVE AIRFIELD PAVEMENTS ARE UTILIZED AS HAUL ROADS BY THE CONTRACTOR, MATERIAL TRACKED ON TO THE PAVEMENT SHALL BE CONTINUALLY REMOVED WITH SAID SWEEPER. THIS SWEEPING SHALL NOT BE PAID FOR SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 9. MATERIALS REMOVED FROM THE PROJECT WILL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED
- 10. PAYMENT FOR TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO BARRICADES, SIGNING, RUNWAY CLOSED MARKERS, AIR OPERATIONS AREA (A.O.A.) LATHE AND RIBBON, ETC. SHALL NOT BE PAID SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. BARRICADES WITH TWO ORANGE FLAGS (20° x 20°) ON EACH BARRICADE SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. BABBICADES SHALL BE WEIGHTED TO PREVENT BLOWING OVER BABBICADES SHALL HAVE A STEADY BUBN OR FLASHING RED LIGHT, BARRICADE INSTALLATION WILL BE REQUIRED PRIOT TO ACCESS TO THE A.O.A. BY CONTRACTOR'S WORKERS, EQUIPMENT OR MATERIAL. SIGNS SHALL BE PLACED AT EACH TAXIWAY/RUNWAY CLOSURE LOCATION AND SHALL BE ATTACHED TO THE BARRICADES. EACH BARRICADE LOCATION SHALL CONSIST OF ONE "DO NOT ENTER" SIGN AND ONE "AIRCRAFT MOVEMENT AREA" SIGN SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR SHALL SUPPLY AND USE AS DIRECTED BY THE AIRPORT, REFLECTIVE LOW PROFILE TYPE BARRICADES. ALL BARRICADES SHALL BE PLACED OUTSIDE OF ACTIVE SAFETY AREAS
- 11. THE CONTRACTOR SHALL CONTACT THE AIRPORT MANAGER THROUGH THE RESIDENT ENGINEER FOURTEEN (14) WORKING DAYS IN ADVANCE OF THE START OF CONSTRUCTION SO THAT THE APPROPRIATE NOTAMS MAY BE ISSUED
- 12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ALL CONSTRUCTION ACCESS GATES CLOSED DURING NON WORKING HOURS, THE CONTRACTOR SHALL PROVIDE A SIGN AT THE ACCESS GATE SAYING "AUTHORIZED PERSONNEL ONLY" THE CONTRACTOR SHALL CLOSE AND LOCK THE ACCESS GATE LIPON LEAVING THE SITE THROUGHOUT THE DURATION OF THE CONTRACT, ANY DAMAGES TO THE ACCESS ROAD, ACCESS GATE OF FENCING ADJACENT TO THE PROJECT SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE RESIDENT ENGINEER. ALL COST RELATING TO CONTRACTOR'S ACCESS AND SECURITY SHALL BE THE RESPONSIBILITY OF THE
- 13. CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS AND HAVE BEACON LIGHTS ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION. SEE FLAG DETAIL.
- 14. IN THE CASE OF AN EMERGENCY, CONTRACTOR SHALL NOTIFY AIRPORT MANAGER AND THE RESIDENT ENGINEER IMMEDIATELY
- 15. DURING ADVERSE WEATHER, THE CONTRACTOR SHALL MAKE PROVISIONS FOR ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK
- 16. THE TALLEST PIECE OF CONSTRUCTION EQUIPMENT IS ANTICIPATED TO BE AN ASPHALT/STONE TRUCK WHICH HAS A MAXIMUM HEIGHT OF 25 FEET IN A DUMP POSITION.
- 17. IF RUNWAY NUMERALS ARE PRESENT DURING CONSTRUCTION THEN CONTRACTOR SHALL PLACE CLOSED RUNWAY MARKER OVER NUMERALS AS DETAILED, OTHERWISE PLACE RUNWAY CLOSED MARKER IN TURF AT ENDS OF BUNWAY AS DETAILED.
- 18. THE AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF WORK WITH THE AIRPORT IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS.
- 19. APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT AND THE PHASING PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS, COUNTY ROADS OR CITY STREETS) WITH THE APROPRIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE ROADS USED AS HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE BESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION LIPON COMPLETION OF BEING USED AS A HAUL ROUTE. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OF ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S TOTAL RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE WORK. ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES.
- 20. MOBILIZATION/EQUIPMENT STORAGE AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS. THIS AREA SHALL BE RESTORED TO THE ORIGINAL CONDITION UPON COMPLETION OF THE PROJECT AT THE CONTRACTOR'S EXPENSE.
- 21. LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE OR FACILITY, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE ON FACILITY, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE FROM PREVIOUS EXISTING TERMINATION POINT TO NEXT EXISTING TERMINATION POINT IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS.
- 22. COORDINATION MEETINGS THE CONTRACTOR SHALL CONDUCT WEEKLY COORDINATION MEETINGS TO DISCUSS WORK AREAS AND SCHEDULING ETC. WITH THE RESIDENT ENGINEER AIRPORT OPERATIONS FAA AND OTHER APPROPRIATE OFFICIALS. MINUTES FROM THE WEEKLY MEETINGS SHALL BE PREPARED BY THE CONTRACTOR, FURNISHED TO ALL ATTENDEES PRIOR TO THE SUBSEQUENT MEETING, AND KEPT ON FILE AT THE FIELD OFFICE. THE COORDINATION MEETING COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT

- 23 THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL INCLUDING THE PROJECT SUPERINTENDENT, WHO MAY BE CONTACTED IN AN EMERGENCY. PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES.
- 24. DRAINAGE MODIFICATIONS SHALL BE SEQUENCED TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES AT NO ADDITIONAL
- 25. CONTRACTOR PERSONNEL VEHICLES, EQUIPMENT AND BARRICADES SHALL NOT BE ALLOWED WITHIN THE TAXIWAY TAXILANE OBJECT FREE AREA (TOFA) OF ACTIVE TAXIWAYS / TAXILANES AND THE RUNWAY'S AIRCRAFT
- 26. CONTRACTOR SHALL STORE EQUIPMENT AND MATERIALS IN SUCH A MANNER AS NOT TO VIOLATE FEDERAL AVIATION ADMINISTRATION PART 77 IMAGINARY SURFACES OR RUNWAY AND TAXIWAY SAFETY AREAS
- 27. ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER ELECTRICAL CABLES SHALL REMAIN IN SERVICE AT ALL TIMES, ALL EXISTING LIGHTING AND VAULT EQUIPMENT SHALL REMAIN IN SERVICE UNTIL PROPOSED IMPROVEMENTS ARE INSTALLED AND OPERATIONAL, UNLESS OTHERWISE APPROVED BY THE RESIDENT ENGINEER. ANY CABLES DAMAGED BY THE CONTRACTOR SHALL BE IMMEDIATELY REPAIRED AT HIS EXPENSE. ANY NECESSARY TEMPORARY JUMPER CABLES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 28. COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. CONTRACTOR IS REFERRED TO SECTION 50-17 OF THE STANDARD SPECIFICATIONS AND THE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAVE BEEN OBTECHTO REQUIREMENTS. THE LOCATION OF OWDER ANOUND ON THE DESIGN ENGINEET OF THE PLANS HAVE BEEN OBTINED FROM EXISTING RECORDS. NEITHER THE OWNER OR THE DESIGN ENGINEER ASSUME ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND TYPE MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY OF HIS OPERATIONAL PLANS THE CONTRACTOR SHALL MAKE ABBANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING TUTLITIES, IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE RESIDENT ENGINEER AND THE AIRPORT MANAGER, ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT
- 29. ALL AIRFIELD LIGHTING AND LIGHTING GUIDANCE SYSTEMS (NAVAIDS) LOCATED WITHIN AND IMMEDIATELY ADJACENT TO THE CONTRACTORS WORK ZONE SHALL BE CHECKED FOR OPERATIONAL CONDITION PRIOR TO THE DEPARTURE FROM THE AIRPORT WITH THE AIRPORT MANAGER. ANY DEFECIENCIES IN THESE SYSTEMS DUE TO THE ACTS OF CONTRACTOR OR HIS SUBCONTRACTORS, SUPPLIERS OR CONSULTANTS SHALL BE REPAIRED IMMEDIATELY

CONTRACTOR CROSSING RUNWAY/TAXIWAY/TAXILANE/APRON AIR OPERATIONS AREA (A.O.A.)

- ANYTIME THE CONTRACTOR IS BEOLIJBED TO LITILIZE OR CROSS ACTIVE AIREIELD PAVEMENTS FOR ACCESS TO AND THE WORK ZONE, A FULL TIME CROSSING GUARD IN RADIO CONTACT WITH AIR TRAFFIC SHALL BE FURNISHED BY THE CONTRACTOR FOR MOVEMENTS OF VEHICLES OR EQUIPMENT TO AND FROM THE WORK ZONE. THE RADIO OPERATOR SHALL BE FAMILIAR WITH AIRPORT GROUND CONTROL PROCEDURES AND DEMONSTRATE KNOWLEDGE OF SAME TO THE AIRPORT. THE AIRPORT THE AIRPORT RESERVES THE RIGHT TO APPROVE THE CROSSING GUARDS. THE CONTRACTOR SHALL PROVIDE THEIR OWN RADIOS. THIS COST SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. <u>THE</u> CONTRACTOR SHALL BE RESPONSIBLE FOR PAYMENT OF MUNICIPAL FINES (\$500 PER OCCURENCE) DUE TO AIRFIELD NCURSIONS BY HIS EMPLOYEES, SUBCONTRACTORS, SUPPLIERS, CONSULTANTS AND/OR AGENTS
- ANY PAVEMENT DAMAGED BY CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY BY HIM TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER AT NO ADDITIONAL COST TO THE OWNER PAVEMENT SHALL BE CONTINUALLY SWEPT TO PROVIDE DEBRIS FREE SUBFACE DURING ALL HALL BOAD OPERATIONS THIS COST SHALL NOT BE PAID SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 3. WORK WITHIN THE A.O.A. SHALL BE EXPEDITED, ANY DROP OFF SHALL BE ADEQUATELY LIGHTED, SIGNED AND BARICADED. NO MATERIAL SHALL BE STOCKPILED WITHIN THE A.O.A. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE MEN AND EQUIPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER TEN (10) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS.

LIMITATIONS ON CONSTRUCTION WITHIN RUNWAY'S AIRCRAFT OPERATIONS AREA (AOA) AND TAXIWAY/TAXILANE OBJECT FREE AREA (TOFA)

RUNWAYS

THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER TEN (14) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. WORK SHALL BE EXPEDIED IN THESE AREAS AND AT THE END OF EACH WORKING DAY THESE AREAS SHALL BE SMOOTHLY GRADED TO ALLOW THE RUNWAY TO BE REOPENED. AT LEAST ONE OF THE RUNWAYS SHALL REMAIN IN OPERATION AT ALL TIMES. IF NECCESSARY STEEL PLATES SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR TO COVER ANY OPEN TRENCHES OR EXCAVATION WITHIN THE BSA IF DUBING BUNWAY CLOSUBE AN EMERGENCY IS DECLARED. THE CONTRACTOR SHALL IMMEDIATELY LEAR THE RUNWAY OF ALL VEHICLES, MEN AND EQUIPMENT. REFERENCE TABLE ON PREVIOUS SHEET FOR SAFETY AREA WIDTHS.

TAXIWAYS / TAXILANES:

ANY WORK WITHIN TAXIWAY / TAXILANE OBJECT FREE AREA (TOFA) WILL REQUIRE A TAXIWAY / TAXILANE CLOSURE. WORK WITHIN THE TOFA SHALL BE EXPEDITED. ANY DROP OFF SHALL BE ADEQUATELY LIGHTED, SIGNED AND BARRICADED. NO MATERIAL SHALL BE STOCKPILED WITHIN THE TOFA. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE COUPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER FIVE (5) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. REFERENCE TABLE ON PREVIOUS VICINING AN INTROVINCE AND TAKE THE AREA WIDTHS. NO DROPORTS OR OPEN EXCAVATIONS WILL BE ALLOWED WITHIN THE TAXIWAY / TAXILANE SAFETY AREAS OF OPEN TAXIWAYS / TAXILANES.

PHASING NOTES (ALL PHASES)

- THE INTENT OF THE PHASING PLANS IS TO MINIMIZE THE IMPACT OF CONSTRUCTION ON THE OPERATION OF THE AIRPORT. THE CONTRACTOR SHALL CONSTRUCT THE PROJECT IN CONSECUTIVE PHASES AS OUTLINED IN THE PLANS UNLESS OTHERWISE APPROVED BY THE RESIDENT ENGINEER AND AIRPORT EXECUTIVE DIRECTOR
- 2. PRIOR TO REOPENING A CLOSED RUNWAY, THE ENTIRE (RSA) RUNWAY SAFETY AREA (250 FEET FROM CENTERLINE AND INCLUDING BEYOND THE END OF THE RUNWAY WITHIN AIRPORT PROPERTY) AND (TOFA) TAXIWAY OBJECT FREE AREA MUST MEET FAA CRITERIA. FAA CRITERIA REQUIRES THAT THERE BE NO OPEN EXCAVATIONS OR TRENCHES IN THE SAFETY AREA(S), THE MAXIMUM PAVEMENT DROP OFF BE 3 INCHES, AND ALL GRADES IN ANY DIRECTION BE LESS THAN 3 PERCENT, STEEL PLATES TEMPORARY WEDGING OF BASE COURSE AND BITUMINOUS CONCRETE MAY BE REQUIRED TO MEET CRITERIA. ALL NECESSARY EMPORARY MEASURES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 3. THE CONTRACTOR SHALL SUBMIT A CONSTRUCTION SCHEDULE. STRICT ADHERENCE TO THE APPROVED SCHEDULE WILL BE ENFORCED TO AVOID CONFLICTS WITH OTHER CONSTRUCTION ACTIVITIES ON THE AIRPORT AND THE ADVERSE EFFECTS THEY COULD HAVE ON AIRPORT OPERATIONS.
- THE CONTRACTOR SHALL COORDINATE CLOSELY WITH THE AIRPORT STAFF TO SCHEDULE THE RUNWAY/TAXIWAY CLOSURES. ITEMS SUCH AS THE EXTENDED WEATHER FORECAST, MATERIAL AVAILABILITY, EQUIPMENT DEPENDABILITY AND MANPOWER AVAILABILITY SHALL BE DISCUSSED PRIOR TO SCHEDULING THIS CRITICAL CLOSURE. THE AIRPORT MANAGER AND THE CONTRACTOR SHALL MUTUALLY AGREE ON THE EXACT DATES AND TIMES OF THE CLOSURE(S).
- 5. CONTRACTOR MUST MAINTAIN ACCESS TO ALL ACTIVE AND OPEN AREAS AT ALL TIMES. CONTRACTOR SHALL RELOCATE FOUIPMENT AT NO ADDITIONAL COST TO CONTRACT TO ALLOW AIRCRAFT TO PASS CONTRACTOR SHALL COORDINATE CONSTRUCTION OPERATIONS AT ALL ACTIVE AND OPEN AREAS TO PROVIDE MINIMAL DISRUPTIONS TO AIRCRAFT MOVEMENT IN
- 6. FAA AND AIRPORT ACCESS ROAD(S) SHALL NOT BE USED AS A HAUL ROAD BY THE CONTRACTOR WITHOUT PRIOR APPROVAL.
- 7. TO THE EXTENT POSSIBLE THE CONTRACTOR SHALL HAVE ALL EMPLOYEE PARKING OUTSIDE OF AIRPORT FENCE OR AS INDICATED AT THE LOCATION SHOWN
- THE AIRPORT RESERVES THE RIGHT TO MODIFY THE SEQUENCE OF CONSTRUCTION INCLUDING BUT NOT LIMITED TO PHASING, WORK AREAS, BARRICADE PLACEMENT, ACCESS AND HAUL ROUTES, AND CONTRACTOR MOVEMENTS AT ANY TIME DURING THE PROJECT WITH FAA, IDA AND ATCT APPROVAL
- ALL WORK IN THIS PHASE WILL REQUIRE FULL TIME CROSSING GUARDS OR ESCORTS IN RADIO CONTACT WITH UNICOM FREQUENCY AT LOCATIONS DESIGNATED, AIRCRAFT AND CONSTRUCTION EQUIPMENT WILL BE REQUIRED TO USE SECTIONS OF TAXIMAY A. THE CONTRACTOR WILL BE REQUIRED TO HAVE A MOTORIZED SWEEPER TO REMOVE DEBRIS TO THE SATISFACTION OF THE RESIDENT ENGINEER. COST OF CROSSING GUARDS/ESCORT AND SWEEPERS SHALL BE INCIDENTAL TO THE CONTRACT.

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE STANDARD SPECIFICATIONS SECTION 50-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS

FAA CRITICAL POINT TABLE					
POINT	NEAREST ACTIVE RUNWAY	LATITUDE	LONGITUDE	ANTICIPATED EQUIPMENT HEIGHT	SITE ELEVATION
1	RUNWAY 16/34	N41°04'23.01"	W87°50'43.60"	25'	620
2	RUNWAY 16/34	N41°04'27.45"	W87°50'45.61"	25'	621
3	RUNWAY 16/34	N41°04'32.92"	W87°51'48.08"	25'	620
4	RUNWAY 16/34	N41°04'29.76"	W87°50'43.20"	25'	621
5	RUNWAY 16/34	N41°04'25.31"	W87°50'41.19"	25'	619
6	RUNWAY 4/22	N41°04'14.67"	W87°50'54.80"	25'	620
7	RUNWAY 4/22	N41°04'22.14"	W87°50'47.00"	25'	619
8	RUNWAY 4/22	N41°04'25.83"	W87°50'43.15"	25'	621
9	RUNWAY 4/22	N41°04'27.69"	W87°50'49.52"	25'	618
10	RUNWAY 4/22	N41°04'31.33"	W87°50'45.67"	25'	621
11	RUNWAY 4/22	N41°04'34.63"	W87°50'33.95"	25'	621
12	RUNWAY 4/22	N41°04'41.48"	W87°50'26.79"	25'	626
13	RUNWAY 4/22	N41°04'06.39"	W87°51'00.96"	25'	622



CONSULTANTS

IL. CONTRACT: KA054

IL. LETTING ITEM: 084 IL. PROJECT: IKK-5198 S.B.G. PROJECT: 3-17-SBGP-TBD

REHABILITATE TAXIWAY A -PHASE 1

FINAL

APRIL 18, 2025

OWNER



MARK	DATE	DES	CRIPTION	
AIP PF	ROJECT	NO.	3-17-SBGP-TBD	
IL PRO	DJECT N	О.	IKK-5198	
CMT F	ROJEC	NO:	24007098-00	
CADE	WG FILI	:		
DESIG	NED BY	:	EJR	
DRAW	/N BY:		JRO	
CHEC	KED BY:		DKP	
APPR	OVED B	/ :	DKP	
COPY	RIGHT:			
1				

SHEET TITLE

SEQUENCE OF CONSTRUCTION PLAN **NOTES AND DETAILS - 1**

7

SHEET

OF





NOT TO SCALE

CLOSED TAXIWAY MARKER DETAIL NOTES

- CLOSED TAXIWAY MARKERS SHALL BE PAINTED YELLOW WITH TEMPORARY MARKING CAPABLE OF BEING REMOVED WITH LOW PRESSURE WATER BLASTING OR OTHER MATERIAL THAT DOES NOT VIOLATE THE OBJECT FREE AREA CRITERIA AND RUNWAY SAFETY AREA CRITERIA PER ADVISORY CIRCULAR 150/5300-13 (LATEST EDITION) AND ARE APPROVED BY THE RESIDENT ENGINEER AND AIRPORT
- 2. CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE CONSTRUCTION
- 3. COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- PLACE MARKERS OVER TAXIWAY CENTERLINE
- MARKERS SHALL BE ADEQUATELY SECURED TO PREVENT MOVEMENT BY PROPELLER WASH, JET BLAST OR OTHER WIND CURRENTS.
- MARKERS ARE ONLY REQUIRED FOR CLOSURES EXCEEDING 72 HOURS.
- AS THE CONSTRUCTION OF THE PORTION OF THE TAXIWAY WITHIN THE RUNWAY SAFETY AREA PROGRESSES, SHOULD THE NEW TAXIWAY BE CLOSED FOR MORE THAN 72 HOURS, THI CONTRACTOR SHALL INSTALL A CLOSED TAXIWAY MARKER AS SHOWN IN THE DETAIL. THE CLOSED TAXIWAY MARKER SHALL NOT BE REMOVED UNLESS THE TAXIWAY WILL BE OPENED AND REMAIN OPEN WITHIN 72 HOURS OF MARKER REMOVAL.





OFF PAVEMENT TEMPORARY

ON PAVEMENT TEMPORARY CLOSED RUNWAY MARKER DETAIL

CLOSED RUNWAY MARKER DETAIL NOT TO SCALE

- MARKERS SHALL BE MATERIAL APPROVED BY THE ENGINEER. 2
- CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE CONSTRUCTION
- MARKERS ON PAVEMENT SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS AS SHOWN.
- COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED 5. INCIDENTAL TO THE CONTRACT.
- DURING VARIOUS PHASES OF WORK, IT WILL BE NECESSARY TO CLOSE RUNWAYS TO AIR TRAFFIC ON A TEMPORARY BASIS AS COORDINATED WITH THE AIRPORT AND TOWER PERSONNEL. THE CONTRACTOR SHALL MARK THE RUNWAYS TO BE CLOSED BY PLACING A YELLOW CROSS AT THE LOCATION AND DIMENSIONS DETAILED ON THIS SHEET. THE CROSSES ARE SHOWN ON THE RESPECTIVE RUNWAYS ACCORDING TO THE VARIOUS PHASES OF WORK AS DELINEATED IN THE SUGGESTED SEQUENCE OF CONSTRUCTION

- LIGHTS ON CLOSED TAXIWAYS UNTIL THE TAXIWAY IS RE-OPENED FOR AIRCRAFT USE. THE METHOD AND MATERIALS USED TO COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL. COST INCIDENTAL TO THE CONTRACT. REMOVING LAMPS FROM ENERGIZED FIXTURES AS A MEANS TO REMOVE THE LIGHTS OR FIXTURES FROM SERVICE SHALL NOT BE ACCEPTABLE
- 2. CONTRACTOR SHALL TURN OFF RUNWAY EDGE LIGHTING REGULATOR AND LOCK-OUT/TAG-OUT CIRCUIT BREAKER AND CUT OUT INSIDE THE ELECTRICAL VAULT. DURING ALL RUNWAY CLOSURES. CONTRACTOR SHALL COORDINATE ACCESS TO THE VAULT WITH THE AIRPORT MANAGER/RESIDENT ENGINEER PRIOR TO RE-OPENING THE RUNWAY, THE CONTRACTOR SHALL COORDINATE WITH AIRPORT MANAGER/RESIDENT ENGINEER TO





AIRSIDE LOW PROFILE LIGHTED BARRICADE



RUNWAY	tyf Rui
16-34	NON-PI
4-22	PRE



RUNWAY END	ELEVA
16	62
34	61
4	62
22	63





STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEERAME SPECIFIED HEBEIN AND AS DIBECTED BY THE ENGINEER. THEREFORE MINIMIZING THE AMOUNT OF AREA SPECIFIED REACTION AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE AT THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY TH ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION:

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF REHABILITATION OF AN EXISTING BITUMINOUS PAVEMENT AT THE GREATER KANKAKEE AIRPORT. THE PROJECT INCLUDES TURF SHOULDER ADJUSTMENT, BITUMINOUS MILLING, BITUMINOUS PAVING, PAVEMENT MARKING AND OTHER MISCELLANEOUS CONSTRUCTION WORK.

DESCRIPTION OF CONSTRUCTION ACTIVITY:

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS GRUBBING, EXCAVATION AND GRADING:

PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL.

BITUMINOUS PAVEMENT MILLING AND PAVING

TURF SHOULDER ADJUSTMENTS, SEEDING AND MULCHING

INSTALLATION OF NEW PAVEMENT MARKING.

REMOVAL AND DISPOSAL OF TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES.

AREA OF CONSTRUCTION SITE:

IT IS ESTIMATED THAT MORE THAN 1 ACRE BUT LESS THAN 5 ACRES OF LAND WILL BE DISTURBED BY GRADING AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS

- 1. INFORMATION OF THE SOLS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY FROSION CONTROL SYSTEMS
- PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORABY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

THE CONSTRUCTION SITE DRAINS INTO THE KANKAKEE RIVER THROUGH A STORM SEWER SYSTEM.

EROSION AND SEDIMENT CONTROL:

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION:

THE DRAWINGS SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, SOD, PROTECTION OF TREES, PRESERVATION OF NATURAL VEGETATION, AND ALL OTHER APPROPRIATE MEASURES AS DIRECTED BY THE INSIDE A STATISTICS AND MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OF PERMANENTLY CEASED.

AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION

DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10. ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIBECTED BY THE ENGINEER). PABKING OF VEHICLES OB CONSTBUCTION FOUIPMENT TOBAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES

WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.

EARTH STOCKPILES SHALL BE <u>TEMPORARILY SEEDED, AT THE CONTRACTOR'S EXPENSE</u>, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN SEVEN (7) DAYS.

THE DOWN STREAM SIDE OF ALL STOCKPILES SHALL BE ENCOMPASSED WITH EROSION CONTROL BARRIER.

AS CONSTRUCTION PROCEEDS. THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER

A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.

CONSTRUCTION FOUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS WITHIN THE STAGING AREA. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE

THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT PERIODICALLY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2" OR GREATER OR EQUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE RESIDENT ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT THE EROSION AND SEDIMENT CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER EROSION CONTROL WORK IS NECESSARY

SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCIDENTAL TO THE CONTRACT.

THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCIDENTAL TO THE CONTRACT.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING SOIL CONTAMINATION FROM BUILDING MATERIALS FERTILIZERS, CHEMICALS, PAVEMENT MARKING, WASTE PILES, FUEL CONTAINMENT, AND ANY OTHER POTENTIAL HAZABDOUS MATERIALS THAT MAY EXIST ONSITE

NO DEDICATED CONCRETE OR ASPHALT BATCH PLANTS SHALL BE LOCATED ON THIS SITE

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED

COST OF MAINTAINING THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE INCIDENTAL TO THE CONTRAC

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RE-SEEDED AND/OR SODDED.

MAINTENANCE AFTER CONSTRUCTION

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AFRONAUTICS. MAINTENANCE OF TEMPORARY AND PERMANENT EROSION CONTROL SYSTEMS UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR

DOCUMENTATION

PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL COMPLETE AND SUBMIT A "NOTICE OF INTENT (NOI)" PROPERLY SIGNED TO THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY

PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL POST A SIGN OR OTHER NOTICE NEAR THE MAIN ENTRANCE OF THE CONSTRUCTION SITE, IF THIS IS NOT POSSIBLE. THEN IT MAY BE PERMITTED TO POST THIS NOTICE IN A LOCAL PUBLIC BUILDING. THE SIGN OR NOTICE MUST CONTAIN THE FOLLOWING

1. A COPY OF THE COMPLETED NOTICE OF INTENT (NOI) AS SUBMITTED TO THE IEPA

2. THE LOCATION OF THE SWPPP AND NAME AND 24/7 TELEPHONE NUMBER OF THE CONTACT PERSON.

THROUGHOUT CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN AND UPDATE AN "AS-BUILT" SET OF STORM WATER MODIFICATION PREVENTION PLANS IN THE PROJECT FILES. THE SWPPP SHALL BE UPDATED WITHIN 7-DAYS OF ANY MODIFICATIONS TO THE PLANS. THE SWPPP AND ALL REVISIONS SHALL BE RETAINED FOR THREE YEARS AFTER FINAL STABILIZATION OF THE SITE, WHICH SHALL BE DEFINED AS VEGETATION COVER OF AT LEAST 70% OF HISTORIC CONDITIONS.

A STORM WATER POLLUTION PREVENTION PLAN EROSION CONTROL INSPECTION REPORT (FORM BC 2259) SHALL BE BE COMPLETED WITH INSPECTION FREQUENCIES AS OUTLINED HEREIN. SWPPP REPORTS SHALL BE RETAINED FOR THREE YEARS AFTER THE DATE OF FINAL STABILIZATION AS DEFINED HEREIN.

IF ANY VIOLATION OF THE PROVISIONS OF THE PLAN IS IDENTIFIED DURING THE CONDUCT OF THE CONSTRUCTION COVERED IN THIS PLAN, THE ENGINEER AND/OR CONTRACTOR SHALL COMPLETE AND FILE AN "INCIDENT OF NONCOMPLIANCE (ION)" REPORT FOR THE IDENTIFIED VIOLATION. THE FORMS SHALL BE AS PROVIDED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY, AND SHALL INCLUDE SPECIFIC INFORMATION ON THE INCIDENT THAT CAUSED NONCOMPLIANCE, ACTIONS THAT WERE TAKEN TO CORRECT THE NONCOMPLIANCE AND TO PREVENT ITS' REOCCURRENCE, AND A STATEMENT DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE NONCOMPLIANCE. ALL REPORTS OF NONCOMPLIANCE SHALL BE SIGNED BY A RESPONSIBLE AUTHORITY IN ACCORDANCE WITH PART VI. G. OF THE GENERAL PERMIT

AFTER PROJECT FINAL ACCEPTANCE, THE CONTRACTOR SHALL COMPLETE AND SUBMIT A "NOTICE OF TERMINATION (NOT) FORM PROPERLY SIGNED TO THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY. FORMS FOR THE IEPA SHALL BE MAILED TO THE FOLLOWING ADDRESS"

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL, MAIL CODE #15 ATTN: PERMIT SECTION 1021 NORTH GRAND AVENUE EAST P.O. BOX 19276 SPRINGFIELD, ILLINOIS 62794-9276

NPDES PERMIT #		
DATE ISSUED		
DATE EXPIRED		

GENERAL NOTES FOR SOIL EROSION AND SEDIMENT CONTROL:

- ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION.
- NO WORK SHALL BE PERFORMED IN FLOWING WATER WORK IN AND NEAR FLOWING WATER SHALL BE ISOLATED FROM CONCENTRATED FLOWS OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL FOR ISOLATION WILL NOT BE
- 3. CONSTRUCTION MATERIALS AND/OR OTHER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN THE PATH OF STREAM FLOV
- 4. TEMPORARY EROSION CONTROL DEVICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS DIRECTED BY THE
- 5. PERMANENT SEEDING SHALL BE USED WHENEVER POSSIBLE, UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG GRADING OR SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONE TIME
- THE CONTRACTOR SHALL INSPECT ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN NECESSARY. ADJACENT STREETS SHALL BE KEPT FREE OF SOIL AND DEBRIS
- SHOULD IT BE NECESSARY TO REMOVE ANY EROSION CONTROL DEVICES FOR CONSTRUCTION REASONS, THE CONTRACTOR SHALL FIRST OBTAIN PERMISSION AND SHALL REPLACE AND/OR REPAIR THE REMOVED DEVICES THE SAME DAY. THE COST OF REMOVING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 8. ALL OTHER SOIL EROSION AND SEDIMENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE RESIDENT ENGINEER COOK COUNTY, CHICAGO EXECUTIVE AIRPORT, IDOT DIVISION OF AFRONAUTICS, AND THE IEPA SHALL BE IMPLEMENTED IMMEDIATELY UPON NOTIFICATION OF THE CONTRACTOR
- 9. THE CONTRACTOR SHALL PROVIDE LOCATIONS FOR CONCRETE TRUCK WASHOUT, AS APPROVED BY THE ENGINEER, PRIOR TO ANY CONCRETE POURS. THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY OF WATER. LOCATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. ADDITIONALLY THE CONTRACTOR SHALL PROVIDE ADEQUATE FACILITIES TO WASH OUT PAVING EQUIPMENT AND FINISHING TOOLS. ALL WASTE WATER AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN APPROVED CONCRETE WASHOUT FACILITY
- 10. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL MEASURES ARE CONSISTENT BETWEEN ALL PROJECT PHASES AND ALL SUB-CONTRACTORS
- 11. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY SEDIMENT, CONSTRUCTION EQUIPMENT, OR BY HIS PERSONNEL, THE CONTRACTOR SHALL ASSURE THAT DEBRIS OR ANY CONSTRUCTION MATERIAL IS NOT DISPOSED OF IN THE WETLANDS.
- 12. WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED BY AN APPROVED MEANS.
- 13. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON A REGULAR BASIS, SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE DEVICE OR AS RECOMMENDED BY THE MANUFACTURER.
- 14. ALL EBOSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE RIOD OF LAND DISTURBANCE UNTIL PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES ARE OPERATIONAL
- 15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER. ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL RECEIVE TEMPORARY EROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND/OR EROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE ABEAS TO BE WORKED BEYOND THE END OF THE GROWING SEASON. MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING
- 16. PERMANENT STABILIZATION SHALL BE COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED.

CONTRACTOR CERTIFICATION STATEMENT

THIS CERTIFICATION STATEMENT IS A PART OF THE STORM WATER POLLUTION PREVENTION PLAN FOR THE PROJECT DESCRIBED BELOW IN ACCORDANCE WITH NPDES PERMIT NO. ILR10 ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY

PROJECT INFORMATION

ROUTE: GREATER KANKAKEE AIRPORT	MARKED:	REHABILI
SECTION: 16, 20, & 21	PROJECT N	UMBER:
COUNTY: KANKAKEE	CONTRACT	NUMBER:_

I CERTIEV LINDER PENALTY OF LAW THAT I LINDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLITION DISCHARGE ELIMINATION SYSTEM (NPDES) PERIMIT (ILB10) THAT A UTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION.

SIGNATURE:	DATE:	
PRINTED NAME:	TITLE:	
NAME OF FIRM:		
STREET ADDRESS:		

CITY.	STATE	ZIP:	

PHONE NUMBER:

THE INFORMATION WITHIN THIS BOX SHALL BE COMPLETED BY THE CONTRACTOR AFTER THE AWARD OF THE CONTRACT TO OBTAIN THE REQUIRED NPDES PERMIT FROM IEPA. COMPLETION OF THIS IS A CONTRACT REQUIREMENT

REG	CORD OF SITE DISTURBANCE AND STABILIZATION
MAJOR GRADING ACTIVITIES:	BEGINNING DATE:
LOCATION:	COMPLETION DATE:
MAJOR GRADING ACTIVITIES:	BEGINNING DATE:
LOCATION:	COMPLETION DATE:
SITE STABILIZATION:	BEGINNING DATE:
LOCATION:	COMPLETION DATE:
SITE STABILIZATION:	BEGINNING DATE:
LOCATION:	COMPLETION DATE:
CONSTRUCTION CEASED:	BEGINNING DATE:
EXPLANATION:	COMPLETION DATE:

THE INFORMATION WITHIN THIS BOX SHALL BE COMPLETED BY THE CONTRACTOR AS CONSTRUCTION PROGRESSES IN ACCORDANCE WITH THE NPDES GENERAL PERMIT FOR STORMWATER DISCHARGES. THIS INFORMATION MAY ALSO BE NOTED DIRECTLY ON THE SWPPP SITE MAP.

TATE TAXIWAY A - PHASE 1

IKK-5198

N/A



CONSULTANTS

IL. CONTRACT: KA054 IL. LETTING ITEM: 084 IL. PROJECT: IKK-5198 S.B.G. PROJECT: 3-17-SBGP-TBD

REHABILITATE TAXIWAY A -PHASE 1

FINAL

APRIL 18, 2025

OWNER



MARK DATE DESCRIPTION AIP PROJECT NO

IL PROJECT NO. IKK-5198 CMT PROJECT NO: 24007098-00 CAD DWG FILE: DESIGNED BY EJR DRAWN BY JRO CHECKED BY DKP APPROVED BY DKP COPYRIGHT

3-17-SBGP-TBE

SHEET TITLE



SHEET

10 OF







r: K:\KankakeeAp\24007098-00_RehabTxyAPh1\DrawSheets\IKK Rehab Txy A - Existing Conditions s: Firdav. Aoni 18, 2025 5:08:40 PM



THE INFORMATION SHOWN ON THESE PLANS HAS BEEN OBTAINED FROM AVAILABLE RECORDS. NEITHER THE OWNER NOB THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY OR SUFFICIENCY OF THE INFORMATION AND THERE IS NO GUARANTEE EITHER EXPRESSED OR IMPLIED THAT THE CONDITIONS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE FIELD. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VISIT THE SITE AND ACQUAINT HIMSELF WITH THE EXISTING CONDITIONS.



098-00_Ref 5:08:42 PM April <:\Kanl Friday. Path: Date:



CONSULTANTS

162

IL. CONTRACT: KA054 IL. LETTING ITEM: 08A IL. PROJECT: IKK-5198 S.B.G. PROJECT: 3-17-SBGP-TBD

REHABILITATE TAXIWAY A -PHASE 1

FINAL

APRIL 18, 2025

OWNER



PC-5: 10.75" BITUMINOUS ASPHALT PAVEMENT 10.75" AGGREGATE BASE

BORING INFORMATION

SB-3: 10" BITUMINOUS ASPHALT PAVEMENT 32" AGGREGATE BASE

SEE EXISTING CONDITIONS AND REMOVALS TAXIWAY A - 1 FOR LEGEND AND NOTES

MARK DATE DESCRIPTION AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. IKK-5198 CMT PROJECT NO: 24007098-00 CAD DWG FILE: DESIGNED BY: EJR DRAWN BY: JRO DKP CHECKED BY: APPROVED BY: DKP COPYRIGHT

SHEET TITLE

EXISTING CONDITIONS AND REMOVALS **TAXIWAY A - SHEET 3**

of 26 SHEET 14







°~	NCMT
<u></u> - <u></u> 142	
	CONSULTANTS
•	IL. CONTRACT: KA054
	IL. LETTING ITEM: 08A
	IL. PROJECT: IKK-5198 S.B.G. PROJECT: 3-17-SBGP-TBD
1/3 V	
	REHABILITATE TAXIWAY A -
	PHASE 1
LEGEND	FINAL
PROPOSED LIMITS OF 2" BITUMINOUS MILLING AND 2" (AND VARIES) OVERLAY	
141+00 142+00	APRIL 18, 2025
	_
	OWNER
	KANKAKEE VALLEY
	AIRPORTAUTHORITY
	MARK DATE DESCRIPTION
	AIP PROJECT NO. 3-17-SBGP-TBD IL PROJECT NO. IKK-5198
	CMT PROJECT NO: 24007098-00 CAD DWG FILE:
	DESIGNED BY: EJR DRAWN BY: JRO
	CHECKED BY: DKP
	APPROVED BY: DKP COPYRIGHT:
	TAXIWAY A - SHFFT 1
	SHEET 16 OF 26



Path: K:\KankakeeAp\24007098.00_RehabTxyAPh1\DrawSheets\IKK Rehab Txy A - Plan and Profiles.ch Date: Friday, April 18, 2025.50854 PM



Path: K:/KankakeeAp/24007088-00_RehabTxyAPh1\UrawiSheets\IKK Rehab Txy A - Plan and Profiles Date: Friday, April 18, 2025 5:08:55 PM



Path: Kr)KankakeeAp/24007098-00. FlenabTxyAPh1\Draw/Sheets\IKK Rehab Txy A - Plan and Profile Date: Friday, April 18, 2025 5:08:57 PM



Path: K:/KankakeeApi/24007098-00_RehabTxyAPh1\Draw/Sheets\IKK Rehab Txy A - Intersection Gra

rath: K:KankakeeAp.24007098-00_RehabTxyAPh1\DrawSheets\IKK Rehab Txy A - Intersection Grading

P/	AVEMENT MA	RKING CONT	ROL POINTS		
NO.	NORTHING	EASTING	STATION/OFFSET		
1	1604807.62	1118455.75	STA. 131+82.28		
2	1604965.47	1118502.97	STA. 133+35.80, 60' L		
3	1605096.27	1118652.91	STA. 135+31.13, 25' L		
4	1605065.39	1118692.42	STA. 135+31.13, 25' R		
5	1605093.81 1118496.66		STA. 111+06.02, 25' R		
6	1605110.34	1118543.93	STA. 111+06.02, 25' L		
7	1605274.53	1118394.33	STA. 109+01.20, 60' R		
8	1605386.90	1118482.08	STA. 108+23.90, 60' L		
9	1605755.82	1118265.01	STA. 104+04.88 25' R		
10	1605771.98	1118312.72	STA. 104+04.88, 25' L		
11	1606085.18	1118239.37	STA. 100+84.70, 60' L		
12	1606176.57	1118500.01	STA. 3+40.40, 60' R		
13	1605442.58	1118952.04	STA. 139+82.28		
14	1605585.57	1119034.01	STA. 141+31.13, 25' L		
15	1605554.90	1119073.24	STA. 141+31.13, 25' R		
16	1606460.16	1119320.26	STA.150+16.90, 60' R		
17	1606289.56	1119538.52	STA. 150+16.60, 60' L		
18	1606384.08	1119612.47	STA. 151+36.6, 60' L		
19	1606979.67	1120026.51	STA. 158+60.90, 100' L		
20	1607158.90	1119862.02	STA. 162+50.00 60' L		

CONSULTANTS

IL. CONTRACT: KA054 IL. LETTING ITEM: **08A** IL. PROJECT: IKK-5198 S.B.G. PROJECT: 3-17-SBGP-TBD

REHABILITATE TAXIWAY A -PHASE 1

FINAL

APRIL 18, 2025

OWNER

IARK	DATE	DESCRIPTIO	N						
AIP PF	ROJECT	NO. 3	-17-SBGP-TBD						
L PRC	DJECT N	0.	IKK-5198						
CMT F	ROJECT	I NO:	24007098-00						
CAD D	WG FILE	:							
DESIG	NED BY	:	EJR						
DRAW	'N BY:		JRO						
CHEC	KED BY:		DKP						
APPR	OVED B	<i>(</i> :	DKP						
COPY	COPYRIGHT:								

SHEET TITLE

SHEET

of 26

Path: K:KantakeeApi04007098-00. RehabTxyAPh1UDrawSheetsIKK Rehab Txy A - Pavement Marking Plar Date: Friday, April 18, 2025 5:09:20 PM

	25' LEFT OF CENTERLINE				SECONDEN I		TERLINE		2	5 <u>' RIGHT </u> O	F CENTER	LINE	
STATION	OVERLAY	PROP	EXST	MILL	PROP	EXST	MILL	OVERLAY	PROP	EXST	MILL	OVERLAY	STATION
	THICKNESS	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	THICKNESS	ELEV.	ELEV.	DEPTH	THICKNESS	
$\frac{31+87.30}{122+00}$	0.17	620.21	620.21	-0.17	620.74	620.74	-0.17	0.17	620.16	620.16	-0.17	0.17	131+87.30
132+00	0.17	610.01	610.01	-0.17	620.71	620.72	-0.18	0.17	620.14	620.14	-0.17	0.17	132+00
132+50	0.17	610.70	610 70	-0.17	620.39	620.38	-0.17	0.18	620.22	610.04	-0.17	0.34	132+30
133+50	0.17	619.79	619.86	-0.17	620.48	620.47	-0.17	0.18	619.99	619.79	-0.17	0.30	133+50
134+00	0.22	619.89	619.73	-0.17	620.26	620.23	-0.17	0.20	619.89	619.71	-0.17	0.34	134+00
134+50	0.17	619.41	619.41	-0.17	620.16	620.15	-0.17	0.18	619.79	619.58	-0.17	0.37	134+50
135+00	0.17	619.67	619.67	-0.17	620.06	620.04	-0.17	0.19	619.60	619.46	-0.17	0.31	135+00
135+50	0.17	619.50	619.50	-0.17	619.96	619.95	-0.17	0.18	619.50	619.34	-0.17	0.33	135+50
136+00	0.21	619.49	619.44	-0.17	619.86	619.85	-0.17	0.18	619.49	619.24	-0.17	0.41	136+00
136+50	0.17	619.20	619.20	-0.17	619.71	619.69	-0.17	0.19	619.13	619.13	-0.17	0.17	136+50
136+93.53	0.17	618.99	618.99	-0.17	619.55	619.55	-0.17	0.17	619.17	619.17	-0.17	0.17	136+93.53
			TAXIW	AY A - SEG	MENT 2 (R	UNWAY 16/	34 TO RUN	WAY 22 END)	- GRADINO	GTABLE			
	25'	LEFT OF C	ENTERLIN	Е		CENT	ERLINE		25	S' RIGHT O	F CENTERI	LINE	
STATION	OVERLAY	PROP	EXST	MILL	PROP	EXST	MILL	OVERLAY	PROP	EXST	MILL	OVERLAY	STATION
100-05-5	THICKNESS	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	THICKNESS	ELEV.	ELEV.	DEPTH	THICKNESS	120:07
139+93.19	0.17	619.04	619.04	-0.17	619.50	619.50	-0.17	0.17	619.11	619.11	-0.17	0.17	139+93.19
140+00	0.17	619.00	619.00	-0.17	619.48	619.48	-0.17	0.17	619.07	619.07	-0.17	0.17	140+00
140+50	0.17	618.95	618.95	-0.17	619.35	619.32	-0.17	0.20	618.95	618.95	-0.17	0.17	140+50
141+00	0.22	018.84	018.78	-0.17	619.21	619.21	-0.17	0.17	018.84	618.74	-0.17	0.26	141+00
141+50	0.17	618.66	618.65	-0.17	619.02	619.02	-0.17	0.17	618.65	618.63	-0.17	0.18	141+50
142+00	0.18	618.47	618.50	-0.21	618.82	618.82	-0.17	0.17	618.45	618.41	-0.17	0.20	142+00
142+50	0.17	618.27	618.29	-0.19	618.62	618.60	-0.17	0.19	618.26	618.26	-0.18	0.17	142+50
143+00	0.17	618.06	618.06	-0.17	618.41	618.43	-0.19	0.17	618.05	618.05	-0.18	0.17	143+00
143+50	0.17	617.83	617.82	-0.17	618.19	618.18	-0.17	0.18	617.82	617.78	-0.17	0.20	143+50
144+00	0.18	617.67	617.65	-0.17	618.04	618.00	-0.17	0.21	617.67	617.58	-0.17	0.25	144+00
144+50	0.17	617.61	617.60	-0.17	617.98	617.95	-0.17	0.20	617.61	617.58	-0.17	0.19	144+50
145+00	0.20	617.60	617.56	-0.17	617.97	617.92	-0.17	0.22	617.60	617.59	-0.17	0.17	145+00
145+50	0.19	617.59	617.56	-0.17	617.96	617.91	-0.17	0.22	617.59	617.56	-0.17	0.19	145+50
146+00	0.18	617.61	617.59	-0.17	617.98	617.90	-0.17	0.25	617.61	617.58	-0.17	0.19	146+00
146+50	0.17	617.58	617.58	-0.18	617.95	617.89	-0.17	0.23	617.59	617.61	-0.19	0.17	146+50
147+00	0.17	617.58	617.59	-0.18	617.94	617.92	-0.17	0.19	617.58	617.58	-0.18	0.17	147+00
147+50	0.17	617.58	617.59	-0.18	617.94	617.95	-0.18	0.17	617.59	617.59	-0.17	0.17	147+50
148+00	0.17	017.01	617.62	-0.18	617.96	617.96	-0.17	0.17	617.61	617.62	-0.18	0.17	148+00
148+50	0.17	017.01	617.61	-0.18	617.97	617.94	-0.17	0.20	017.01	617.58	-0.17	0.19	148+50
149+00	0.18	617.65	617.60	-0.17	617.99	617.97	-0.17	0.19	617.63	617.77	-0.18	0.17	149+00
149+30	0.20	617.60	617.79	-0.17	618.02	618.03	-0.18	0.17	617.69	617.77	-0.27	0.17	149+30
150+50	0.17	618.22	618.22	-0.20	618.04	618.08	-0.21	0.17	617.08	617.65	-0.19	0.17	150+50
151+00	0.17	619.19	619.19	-0.17	619.15	619.16	-0.21	0.17	617.70	617.03	-0.17	0.21	151+00
151+50	0.17	618 10	618.10	-0.17	618.42	618.30	-0.13	0.17	618.05	618.00	-0.17	0.21	151+50
151+50	0.17	618.10	618.51	-0.21	618.82	618.79	-0.17	0.20	618.05	618.00	-0.17	0.19	151+50
152+50	0.17	618.97	618.87	-0.21	619.02	619.73	-0.17	0.20	618.86	618.87	-0.17	0.17	152+50
153+00	0.17	619.27	619.27	-0.17	619.62	619.59	-0.17	0.10	619.26	619.26	-0.18	0.17	153+00
153+50	0.19	619.68	619.66	-0.17	620.03	620.00	-0.17	0.20	619.67	619.66	-0.17	0.17	153+50
154+00	0.17	620.08	620.08	-0.17	620.43	620.42	-0.17	0.18	620.07	620.08	-0.18	0.17	154+00
154+50	0,17	620.49	620.49	-0.17	620.84	620.85	-0.18	0.17	620.47	620.46	-0.17	0.17	154+50
155+00	0.17	620.88	620.88	-0.18	621.24	621.24	-0.17	0.17	620.87	620.88	-0.18	0.17	155+00
155+50	0.18	621.29	621.27	-0.17	621.65	621.63	-0.17	0.19	621.28	621.26	-0.17	0.18	155+50
156+00	0.20	621.68	621.64	-0.17	622.05	622.05	-0.17	0.17	621.68	621.67	-0.17	0.17	156+00
156+50	0.21	622.08	622.03	-0.17	622.45	622.45	-0.17	0.17	622.08	622.08	-0.18	0.17	156+50
157+00	0.21	622.49	622.44	-0.17	622.86	622.86	-0.17	0.17	622.49	622.51	-0.19	0.17	157+00
157+50	0.20	622.89	622.85	-0.17	623.26	623.26	-0.17	0.17	622.89	622.87	-0.17	0.18	157+50
158+00	0.17	623.28	623.27	-0.17	623.65	623.59	-0.17	0.23	623.28	623.25	-0.17	0.19	158+00
158+50	0.17	623.68	623.71	-0.20	624.04	624.00	-0.17	0.21	623.67	623.58	-0.17	0.25	158+50
159+00	0.20	624.06	624.02	-0.17	624.43	624.34	-0.17	0.26	624.06	623.96	-0.17	0.26	159+00
159+50	0.22	624.45	624.39	-0.17	624.82	624.74	-0.17	0.25	624.45	624.33	-0.17	0.28	159+50
160+00	0.22	624.87	624.81	-0.17	625.24	625.05	-0.17	0.36	624.87	624.73	-0.17	0.30	160+00
160+50	0.27	625.47	625.36	-0.17	625.84	625.60	-0.17	0.41	625.47	625.23	-0.17	0.40	160+50
100.00	0.40	626.21	625.97	-0.17	626.58	626.29	-0.17	0.46	626.21	625.97	-0.17	0.40	161+00
161+00	. v. TV	020.21	020.71	0.17	020.00	020.27	v.17	0.10	020.21	020.71	0.17	V.TV	101.00
161+00 161+50	0.26	626.96	626.86	-0.17	627 33	627.18	_0.17	032 I	626.07	626.00	-0.10	0.17	161+50
161+00 161+50 162+00	0.26	626.96 627 73	626.86 627.79	-0.17	627.33 628.08	627.18 628.01	-0.17	0.32	626.97 627.89	626.99 627.89	-0.19	0.17	161+50
161+00 161+50 162+00 162+50	0.26 0.17 0.17	626.96 627.73 628.57	626.86 627.79 628.57	-0.17 -0.23	627.33 628.08 628.83	627.18 628.01 628.73	-0.17 -0.17 -0.17	0.32 0.24 0.27	626.97 627.89 628.78	626.99 627.89 628.78	-0.19 -0.17	0.17 0.17 0.17	161+50 162+00 162+50

	TAXIWAY A2 - GRADING TABLE												
	25'	LEFT OF CI	ENTERLINI	E		CENT	ERLINE		25	S' RIGHT O	F CENTERI	LINE	
STATION	OVERLAY	PROP	EXST	MILL	PROP	EXST	MILL	OVERLAY	PROP	EXST	MILL	OVERLAY	STATION
	THICKNESS	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	THICKNESS	ELEV.	ELEV.	DEPTH	THICKNESS	
0+49.26	0.17	622.43	622.43	-0.17	622.34	622.34	-0.17	0.17	622.15	622.15	-0.17	0.17	0+49.26
0+50.00	0.17	622.43	622.43	-0.17	622.33	622.33	-0.17	0.17	622.15	622.15	-0.17	0.17	0+50
1+00.00	0.17	621.57	621.57	-0.17	621.73	621.79	-0.23	0.17	621.37	621.37	-0.18	0.17	1+00
1+50.00	0.18	620.76	620.74	-0.17	621.13	621.13	-0.17	0.17	620.78	620.78	-0.17	0.17	1+50
2+00.00	0.30	620.19	620.05	-0.17	620.56	620.54	-0.17	0.19	620.19	620.18	-0.17	0.17	2+00
2+50.00	0.35	619.63	619.44	-0.17	620.00	619.98	-0.17	0.19	619.63	619.59	-0.17	0.20	2+50
3+00.00	0.34	618.98	618.80	-0.17	619.35	619.35	-0.17	0.17	618.98	618.97	-0.17	0.17	3+00
3+50.00	0.26	618.27	618.18	-0.17	618.70	618.68	-0.17	0.19	618.40	618.40	-0.17	0.17	3+50
4+00.00	0.17	618.16	618.16	-0.17	618.12	618.12	-0.17	0.17	618.22	618.22	-0.17	0.17	4+00.00

	25'1	FFT OF C	ENTERLINI	F	115	CENT	TERLINE	TITULE	25' RIGHT OF CENTERLINE				
STATION	OVEDIAN	DDOD	EVET	MILL	DDOD	FVST	MILI	OVEDLAV	DD OD	FVST	F CENTER.	OVEDIAV	STATION
	THICKNESS	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	THICKNESS	ELEV.	ELEV.	DEPTH	THICKNESS	
100 + 24.84	0.17	617.53	617.53	-0.17	617.65	617.61	-0.17	0.21	617.32	617.32	-0.17	0.17	100+24.84
100+50	0.17	617.34	617.34	-0.17	617.58	617.54	-0.17	0.21	617.22	617.22	-0.17	0.17	100+50
101 + 00	0.20	617.09	617.05	-0.17	617.46	617.46	-0.17	0.17	617.13	617.15	-0.19	0.17	101+00
101 + 50	0.23	617.11	617.04	-0.17	617.48	617.47	-0.17	0.18	617.13	617.12	-0.17	0.18	101+50
102+00	0.17	617.12	617.12	-0.18	617.49	617.49	-0.17	0.17	617.15	617.19	-0.21	0.17	102+00
102+50	0.20	617.14	617.10	-0.17	617.51	617.52	-0.18	0.17	617.17	617.17	-0.17	0.17	102+50
103+00	0.18	617.16	617.14	-0.17	617.53	617.51	-0.17	0.19	617.18	617.15	-0.17	0.20	103+00
103+50	0.21	617.17	617.12	-0.17	617.54	617.53	-0.17	0.18	617.19	617.16	-0.17	0.20	103+50
104+00	0.17	617.17	617.16	-0.17	617.54	617.55	-0.18	0.17	617.19	617.19	-0.17	0.17	104+00
104+50	0.17	617.25	617.24	-0.17	617.62	617.61	-0.17	0.18	617.26	617.26	-0.18	0.17	104+50
105+00	0.21	617.57	617.52	-0.17	617.94	617.87	-0.17	0.24	617.57	617.53	-0.17	0.20	105+00
105+50	0.23	618.14	618.07	-0.17	618.51	618.39	-0.17	0.29	618.14	618.12	-0.17	0.18	105+50
106+00	0.32	618.89	618.73	-0.17	619.26	619.05	-0.17	0.38	618.89	618.77	-0.17	0.28	106+00
106+50	0.23	619.64	619.57	-0.17	620.01	619.84	-0.17	0.34	619.64	619.57	-0.17	0.23	106+50
107+00	0.17	620.80	620.80	-0.17	620.76	620.69	-0.17	0.24	620.36	620.36	-0.17	0.17	107+00
107 + 27.92					621.19	621.19	-0.17	0.17	621.23	621.23	-0.17	0.17	107+27.92
108+46.99	0.17	621.31	621.31	-0.17	621.38	621.36	-0.17	0.19					108+46.99
108+50	0.17	620.95	620.95	-0.17	621.35	621.33	-0.17	0.19					108+50
109+00	0.20	620.32	620.28	-0.17	620.69	620.60	-0.17	0.26	620.60	620.60	-0.17	0.17	109+00
109+50	0.17	619.66	619.69	-0.21	620.03	620.01	-0.17	0.19	619.66	619.66	-0.18	0.17	109+50
110+00	0.31	619.09	618.94	-0.17	619.46	619.29	-0.17	0.34	619.09	618.95	-0.17	0.30	110+00
110+50	0.32	618.78	618.62	-0.17	619.15	619.08	-0.17	0.24	618.78	618.74	-0.17	0.20	110+50
111+00	0.25	618.71	618.62	-0.17	619.08	619.06	-0.17	0.19	618.71	618.69	-0.17	0.18	111+00
111+50	0.33	618.90	618.73	-0.17	619.27	619.14	-0.17	0.30	618.90	618.76	-0.17	0.30	111+50
112+00	0.27	619.32	619.21	-0.17	619.69	619.47	-0.17	0.39	618.98	618.98	-0.17	0.17	112+00
112+50					620.15	620.11	-0.17	0.21					112+50
112+61.98	0.17	620.24	620.24	-0.17	620.26	620.26	-0.17	0.17	620.33	620.33	-0.17	0.17	112+61.98

	TAXIWAY BB - GRADING TABLE												
	25'	LEFT OF CI	ENTERLINI	3		CENT	FERLINE		2	5' RIGHT C	OF CENTER	LINE	
STATION	OVERLAY	PROP	EXST	MILL	PROP	EXST	MILL	OVERLAY	PROP	EXST	MILL	OVERLAY	STATION
	THICKNESS	ELEV.	ELEV.	DEPTH	ELEV.	ELEV.	DEPTH	THICKNESS	ELEV.	ELEV.	DEPTH	THICKNESS	
0+00.00	0.17	617.39	617.39	-0.17	617.62	617.62	-0.17	0.17	617.54	617.54	-0.17	0.17	0+00.00
0+50	0.17	617.25	617.25	-0.17	617.60	617.46	-0.17	0.31	617.23	617.09	-0.17	0.30	0+50
1+00	0.18	617.26	617.25	-0.17	617.60	617.53	-0.17	0.24	617.23	617.17	-0.17	0.22	1+00
1+50	0.15	617.46	617.47	-0.17	617.78	617.77	-0.17	0.18	617.41	617.39	-0.17	0.18	1+50
2+00	0.17	617.87	617.87	-0.17	618.18	618.15	-0.17	0.20	617.83	617.84	-0.18	0.16	2+00
2+50	0.17	618.50	618.50	-0.18	618.81	618.76	-0.17	0.22	618.44	618.40	-0.17	0.20	2+50
3+00	0.17	619.24	619.24	-0.18	619.51	619.45	-0.17	0.23	619.36	619.36	-0.17	0.17	3+00
3+50	0.17	620.11	620.11	-0.17	620.21	620.21	-0.17	0.17	620.27	620.27	-0.17	0.17	3+50
3+50.43	0.17	620.11	620.11	-0.17	620.22	620.22	-0.17	0.17	620.27	620.27	-0.17	0.17	3+50.43

HMA Mixture Requirement Table										
ltem	Runway/Taxiway	PG Binder	Aggregate	Max RAP	De					
	(60k+ lbs) Ndes		Quality		Acce					
401: Surface	<u>N50@3.0%</u>	Overlay: SBS PG 70-28	A	0 (N/A)	P' Mai Co					
		Leveling/Patches PG 64-22			Joints					

ensity eptance PWL ainline: Cores ts: Cores

CONSULTANTS

IL. CONTRACT:	(A054
---------------	--------------

IL. LETTING ITEM: **08A** IL. PROJECT: IKK-5198 S.B.G. PROJECT: 3-17-SBGP-TBD

REHABILITATE TAXIWAY A -PHASE 1

FINAL

APRIL 18, 2025

OWNER

MARK	DATE	DESC	RIPTION	
AIP PF	ROJECT	NO.	3-17-SBGP-TBD	
IL PRO	DJECT N	0.	IKK-5198	
CMT F	ROJECT	r NO:	24007098-00	
CADE	WG FILE	E:		
DESIG	NED BY	:	EJR	
DRAW	/N BY:		JRO	
CHEC	KED BY:		DKP	

DKP

COPYRIGHT: SHEET TITLE

APPROVED BY:

PAVING TABLES

SHEET 26 OF 26