

\* SP Special Provision x SI Speciality Item

SI	SP	PAY ITEM CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ITEP				NON-PARTICIPATING ROADWAY 100% 0004
						TRAINEES 80/20 (%) 0042	LANDSCAPING 80/20 (%) 0031	LIGHTING 80/20 (%) 0031	LIGHTING 50/50 (%) 0031	
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	116		116			
		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	48		48			
		20101000	TEMPORARY FENCE	FOOT	221		221			
		20200100	EARTH EXCAVATION	CU YD	1145		833			512
		20800150	TRENCH BACKFILL	CU YD	50		50			
X		21101885	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	202		202			
X		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1			1		
X		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1			1		
X		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1			1		
X		25200110	SODDING, SALT TOLERANT	SQ YD	150			100		50
X		25200200	SUPPLEMENTAL WATERING	UNIT	6			6		
		28000400	PERIMETER EROSION BARRIER	FOOT	819		819			
		28000510	INLET FILTERS	EACH	27		27			
		28200200	FILTER FABRIC	SQ YD	1720		1668			52
		35101800	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	60		13	47		
		35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	2649		2397			252
		35102200	AGGREGATE BASE COURSE, TYPE B 10"	SQ YD	1913					1913
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	623					623
		40600300	AGGREGATE (PRIME COAT)	TON	2					2
		40600895	CONSTRUCTING TEST STRIP	EACH	1					1
		40600962	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	64					64
		40600990	TEMPORARY RAMP	SQ YD	114					114
		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	183					183
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	884					884
		42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	18		18			
		42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	545		120	425		
		42400800	DETECTABLE WARNINGS	SQ FT	100		50	50		

\* SP Special Provision x SI Speciality Item

SI	SP	PAY ITEM CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ITEP				NON-PARTICIPATING ROADWAY 100% 0004
						TRAINEES 80/20 (%) 0042	LANDSCAPING 80/20 (%) 0031	LIGHTING 80/20 (%) 0031	LIGHTING 50/50 (%) 0031	
		44000100	PAVEMENT REMOVAL	SQ YD	2016					2016
		44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	6811					6811
		44000300	CURB REMOVAL	FOOT	252		252			
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2087		2087			
		44000600	SIDEWALK REMOVAL	SQ FT	9811		7649	425		1737
		44201896	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	150			150		
		44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	6747					6747
X		56500200	DOMESTIC WATER SERVICE BOXES TO BE MOVED	EACH	3		3			
X	*	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	4		4			
X		60266600	VALVE BOXES TO BE ADJUSTED	EACH	12		12			
		60500205	FILLING CATCH BASINS	EACH	1			1		
	*	80604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	2509		2509			
X		88900200	NON-SPECIAL WASTE DISPOSAL	CU YD	66		66			
X		88900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1		1			
X		66900530	SOIL DISPOSAL ANALYSIS	EACH	1		1			
		67100100	MOBILIZATION	L SUM	1		1			
X		72000100	SIGN PANEL - TYPE 1	SQ FT	4		4			
X		72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	84.75		80.75			4
X		72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	84.75		80.75			4
X		73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	17		17			
X		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	300					300
X		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5100					5100
X		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	490					490
X		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	276					276
X		78000850	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100					100
X	*	80400100	ELECTRIC SERVICE INSTALATION	EACH	1			1		
X	*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1		

FILE NAME = 3737\_16SUMB1.DGN

USER NAME = mgarvey  
 PLOT SCALE = 1:1  
 PLOT DATE = 3/25/2013

DESIGNED - BS  
 DRAWN -  
 CHECKED - JCK  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES - 1

SCALE: SHEET 1 OF 3 SHEETS STA. TO STA.

F.A. RTE. SECTION 10-00149-00-LS COUNTY COOK TOTAL SHEETS 69 SHEET NO. 3 CONTRACT NO. 63723  
 [ILLINOIS] FED. AID PROJECT