

SUMMARY OF QUANTITIES					CONSTRUCTION CODE			
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUAN.	STU FUNDS			
					0004	0021	0031	0042
	54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	3	3			
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	151	151			
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	92	92			
	550A4100	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	180	180			
	55100500	STORM SEWER REMOVAL 12"	FOOT	456	456			
	55100700	STORM SEWER REMOVAL 15"	FOOT	126	126			
	60107600	PIPE UNDERDRAINS 4"	FOOT	846	846			
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
	60500050	REMOVING CATCH BASINS	EACH	1	1			
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	4.5	4.5			
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	365	365			
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	565	565			
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9			
	67100100	MOBILIZATION	L SUM	1	1			
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2650	2650			
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2			
*	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1500	1500			
*	70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	200	200			
*	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	21765	21765			
*	70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	50	50			
*	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7854	7854			
*	72000100	SIGN PANEL - TYPE 1	SQ FT	47	47			

SUMMARY OF QUANTITIES					CONSTRUCTION CODE			
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUAN.	STU FUNDS			
					0004	0021	0031	0042
	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1		1		
	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	3		3		
	72900100	METAL POST - TYPE A	FOOT	24		24		
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	400		400		
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13252		13252		
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1534		1534		
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	219		219		
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	196		196		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	236		236		
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	104		104		
*	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1		
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA	FOOT	1918		1918		
*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA	FOOT	70		70		
*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA	FOOT	46		46		
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA	FOOT	409		409		
*	81028740	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/2" DIA	FOOT	87		87		
*	81028770	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3" DIA	FOOT	85		85		
*	81400100	HANDHOLE	EACH	3		3		
*	81400200	HEAVY-DUTY HANDHOLE	EACH	10		10		
*	81400300	DOUBLE HANDHOLE	EACH	2		2		
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2		
*	86400100	TRANSCIVER - FIBER OPTIC	EACH	1		1		
*	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4106		4106		
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	280		280		

FILE NAME = 08361_02-QUAN-01 - IDOT P02

USER NAME =

DESIGNED -- WPD

REVISED -- 01-16-13

CHECKED -- PB

REVISED --

PLOT SCALE =

DRAWN -- RG

REVISED --

PLOT DATE = 02-26-13

CHECKED -- AG

REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERSECTION IMPROVEMENT
IL RTE 53 AT MATERIAL ROAD
SUMMARY OF QUANTITIES

SCALE: NONE

SHEET NO. 5 OF 54 SHEETS

STA.

TO STA.

F&P
RTE.

112

SECTION

09-00065-00-CH

COUNTY

WILL

TOTAL
SHEETS

54

SHEET
NO.

5

CONTRACT NO. 63753

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-8003(629)