



# NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)  
UNLESS OTHERWISE SHOWN.

FILE NAME = 06981_02-DTL9-04-TC22 - TC-22	USER NAME = geglionobc	DESIGNED —	REVISED — R. MIRS 09-15-97	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ARTERIAL ROAD INFORMATION SIGN	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED —	REVISED — R. MIRS 12-11-97			112	09-00055-00-CH	WILL	54	42
	PLOT SCALE = 50.000' / IN.	DRAWN —	REVISED — J. RAMMACHER 02-02-99			TC-22		CONTRACT NO. 63753		
	PLOT DATE = 1/4/2008	CHECKED —	REVISED — C. JUCIUS 01-31-07			FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	M-9003(829)	

SCALE: SHEET NO. 42 OF 54 SHEETS STA. TO STA.